ARCHITECTURAL ABBREVIATIONS

A	#	POUNDS / NUMBER
A	&	AND
A	@	AT
A	A	ANGLE
A	A/C	AIR CONDITIONER / CONDITIONING
A	AAF	ALL ABOARD FLORIDA
A	ABV	ABOVE
A	ACCS	ACCESSORIES
A	ACSDR	ACCESS DOOR
A	ACSFLR	ACCESS FLOOR
A	ACST / ACOUS	ACOUSTICAL
A	ACT	ACOUSTICAL CEILING TILE
A	AD	AREA DRAIN
A	ADA	AMERICANS WITH DISABILITIES ACT
A	ADDL	ADDITIONAL
A	ADDM	ADDENDUM
A	ADJ	ADJUSTABLE / ADJACENT
A	ADMIN	ADMINISTRATION
A	AFC	ABOVE FINISHED COUNTER
A	AFF	ABOVE FINISHED FLOOR
A	AFG	ABOVE FINISHED GRADE
A	AFS	ABOVE FINISHED SLAB
A	AGGR	AGGREGATE
A	AHR	ANCHOR
A	AHU	AIR HANDLING UNIT
A	AL / ALUM	ALUMINUM
A	ALNMT	ALIGNMENT
A	ALT	ALTERNATE
A	ANOD	ANODIZED
A	AP	ACCESS PANEL
A	APC	ACOUSTICAL PANEL CEILING
A	APPROX	APPROXIMATELY
A	APPVD	APPROVED
A	ARCH	ARCHITECTURAL
A	ASPH	ASPHALT
A	ASTM	AMERICAN SOCIETY FOR TESTING MATERIALS
A	AUTO	AUTOMATIC
A	AVG	AVERAGE
B	BD	BOARD
B	BET	BETWEEN
B	BG	BUMPER GUARD
B	BITUM	BITUMINOUS
B	BL	BLACK
B	BLDG	BUILDING
B	BLK	BLOCK
B	BLKG	BLOCKING
B	BM	BEAM
B	BMS	BALANCE MAGNETIC SWITCH
B	BOS	BOTTOM OF STEEL
B	BOT	BOTTOM
B	BS	BOTH SIDES
C	CAB	CABINET
C	CAS	CASEWORK
C	CB	CATCH BASIN
C	CEM	CEMENT
C	CER	CERAMIC
C	CF	CUBIC FOOT
C	CG	CORNER GUARD
C	CH	CEILING HEIGHT
C	CHAM	CHAMFER
C	CHBD	CHALKBOARD
C	CI	CAST IRON
C	CI	CONTRACTOR INSTALLED
C	CIP	CAST IN PLACE
C	CJ	CONTROL JOINT
C	CL	CENTER LINE
C	CLG	CEILING
C	CLO	CLOSET
C	CLR	CLEAR
C	CMU	CONCRETE MASONRY UNIT
C	CO	CLEAN/CLEAR OUT
C	COL	COLUMN
C	CONC	CONCRETE
C	CONST	CONSTRUCTION
C	CONT	CONTINUOUS
C	CORR	CORRIDOR
C	CPR	COPPER
C	CPT	CARPET(ED)(ING)
C	CT	CERAMIC TILE
C	CTR	COUNTER
C	CTSK	COUNTERSUNK
D	DBL	DOUBLE
D	DEFS	DIRECT APPLIED EXTERIOR FINISH SYSTEM
D	DEG	DEGREE
D	DEMO	DEMOLISH
D	DEP	DEPRESSION
D	DET	DETAIL
D	DF	DRINKING FOUNTAIN
D	DIA	DIAMETER
D	DIAG	DIAGONAL
D	DIM	DIMENSION
D	DISP	DISPENSER
D	DIV	DIVISION
D	DN	DOWN
D	DR	DOOR
D	DS	DOWNSPOUT
D	DTL	DETAIL
D	DWG	DRAWING
E	E	EAST
E	EA	EACH
E	EF	EACH FREE
E	EIFS	EXTERIOR INSULATION AND FINISH SYSTEM
E	EJ	EXPANSION JOINT
E	EL	ELEVATION
E	ELEC	ELECTRICAL
E	ELEV	ELEVATOR
E	EMER	EMERGENCY
E	ENCL	ENCLOSED / ENCLOSURE
E	ENG	ENGINEER
E	EOD	EDGE OF DECK
E	EOS	EDGE OF SLAB
E	EQ	EQUAL(LY)
E	EQPT	EQUIPMENT
E	EST	ESTIMATE
E	EWC	ELECTRIC WATER COOLER
E	EXIST	EXISTING
E	EXP	EXPANSION
E	EXT	EXTERIOR
F	FA	FIRE ALARM
F	FAST	FASTEN(ER)
F	FCO	FLOOR CLEAN OUT
F	FD	FLOOR DRAIN
F	FDN	FOUNDATION
F	FE	FIRE EXTINGUISHER
F	FEC	FIRE EXTINGUISHER CABINET
F	FEC (R)	FIRE EXTINGUISHER CABINET, RECESSED
F	FEC (SR)	FIRE EXTINGUISHER CABINET, SEMI-RECESSED
F	FEW	FIRE EXTINGUISHER, WALL MOUNTED
F	FF	FINISHED FLOOR
F	FGL	FIBERGLASS
F	FIN	FINISH(ED)
F	FIXT	FIXTURE
F	FL	FLOOR
F	FLASH	FLASH(ING)
F	FLUOR	FLUORESCENT
F	FOC	FACE OF CONCRETE
F	FOF	FACE OF FINISH
F	FOM	FACE OF MASONRY
F	FOS	FACE OF STUDS
F	FOW	FACE OF WALL
F	FP	FIREPROOF
F	FPL	FLORIDA POWER AND LIGHT
F	FR	FRAME
F	FRC	FIBER REINFORCED CONCRETE
F	FRGP	FIBER REINFORCED GYPSUM PLASTER
F	FRT	FIRE RETARDANT TREATED
F	FS	FLOOR SINK
F	FTG	FOOTING
F	FURR	FURRING
F	FUT	FUTURE
G	GA	GAUGE
G	GALV	GALVANIZE(D)
G	GB	GRAB BAR
G	GC	GENERAL CONTRACTOR
G	GL	GLASS / GLAZING
G	GND	GROUND
G	GR	GRADE
G	GRV	GRAVEL
G	GT	GLASS TILE
G	GWB	GYPSUM WALL BOARD
G	GYP	GYPSUM
G	GYP BD	GYPSUM BOARD
H	HB	HOSE BIB
H	HC	HOLLOW CORE
H	HCP	HANDICAPPED
H	HD	HEAVY DUTY
H	HD	HARD
H	HDR	HEADER
H	HDWR	HARDWARE
H	HI	HIGH
H	HM	HOLLOW METAL
H	HMI	HOLLOW METAL INSULATED
H	HOR / HORIZ	HORIZONTAL
H	HP	HIGH POINT
H	HR	HANDRAIL
H	HR	HOUR
H	HT	HEIGHT
H	HVAC	HEATING / VENTILATION / AIR CONDITIONING
H	HW	HARDWARE
H	HYD	HYDRANT
I	ID	INSIDE DIAMETER
I	IDF	INTERMEDIATE DISTRIBUTION FRAME
I	IN	INCH / INCHES
I	INCL	INCLUDE(D) / INCLUDING
I	INSUL	INSULATE / INSULATION
I	INT	INTERIOR
J	JAN	JANITOR
J	JC	JANITORS CLOSET
J	JT	JOINT
K	KIT	KITCHEN
L	LAB	LABORATORY
L	LAM	LAMINATE(D)
L	LAV	LAVATORY
L	LB(S)	POUND(S)
L	LF	LINEAR FOOT (FEET)
L	LH	LEFT HAND
L	LIB	LIBRARY
L	LKR	LOCKER
L	LNS	LINOLEUM SHEET
L	LNT	LINOLEUM TILE
L	LP	LOW POINT
L	LT	LIGHT
L	LVR	LOUVER
L	LWT	LIGHT WEIGHT
M	MACH	MACHINE
M	MAINT	MAINTENANCE
M	MATL	MATERIAL
M	MAX	MAXIMUM
M	MC	MEDICINE CABINET
M	MDF	MAIN DISTRIBUTION FRAME
M	ME	MECHANICAL EQUIPMENT
M	MECH	MECHANICAL
M	MEZZ	MEZZANINE
M	MFR	MANUFACTURE(R)
M	MH	MANHOLE
M	MIN	MINIMUM
M	MIR	MIRROR
M	MISC	MISCELLANEOUS
M	MLD / MLDG	MOULDING
M	MO	MASONRY OPENING
M	MR	MOISTURE RESISTANT
M	MTD	MOUNTED
M	MTL	METAL
M	MUL	MULLION
N	N	NORTH
N	NA OR N/A	NOT AVAILABLE / APPLICABLE
N	NAVD	NORTH AMERICAN VERTICAL DATUM
N	NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
N	NGVD	NATIONAL GEODETIC VERTICAL DATUM
N	NIC	NOT IN CONTRACT
N	NO / #	NUMBER
N	NOM	NOMINAL
N	NTS	NOT TO SCALE
O	OA	OVERALL
O	OBS	OBSCURE
O	OC	ON CENTER
O	OD	OUTSIDE DIAMETER
O	OFCI	OWNER FURNISHED CONTRACTOR INSTALLED
O	OFF	OFFICE
O	OPG / OPNG	OPENING
O	OPP	OPPOSITE
O	ORD	OVERFLOW ROOF DRAIN
O	OZ	OUNCE
P	P	POINT
P	PART	PARTIAL
P	PAT	PATTERN
P	PBD	PARTICLE BOARD
P	PC / PCC	PRECAST CONCRETE
P	PED	PEDESTAL
P	PER	PERIMETER
P	PERF	PERFORATED
P	PERP	PERPENDICULAR
P	PF	PRE-FINISHED
P	PIP	POURED-IN-PLACE
P	PL	PROPERTY LINE
P	PL	PLATE
P	PLAM	PLASTIC LAMINATE
P	PLAS	PLASTER
P	PLF	POUNDS PER LINEAR FEET
P	PLYWD	PLYWOOD
P	PMF	PRESSED METAL FRAMES
P	POP	POINT OF PRESENCE
P	PR	PAIR
P	PRCST	PRE-CAST
P	PREFAB	PREFABRICATED
P	PROP	PROPERTY
P	PRT	PORCELAIN TILE
P	PSF	POUNDS PER SQUARE FOOT
P	PSI	POUNDS PER SQUARE INCH
P	PT	PRESSURE TREATED / POINT
P	PTD	PAPER TOWEL DISPENSER
P	PTD/WR	PAPER TOWEL DISPENSER &WASTE RECEPTACLE
P	PTDF	PRESSURE TREATED DOUGLAS FIR
P	PTN	PARTITION
P	PTR	PAPER TOWEL RECEPTACLE
P	PVC	POLYVINYL CHLORIDE
Q	Q	QUARTZ
Q	QT	QUARRY TILE
Q	QTY	QUANTITY
R	R	RISER
R	RAD	RADIUS
R	RB	RUBBER BASE
R	RCP	REFLECTED CEILING PLAN
R	RD	ROOF DRAIN
R	REF	REFERENCE
R	REFR	REFRIGERATOR
R	REG	REGISTER
R	REINF	REINFORCE(D)
R	REQ	REQUIRED
R	RESIL	RESILIENT
R	RESS	RESILIENT SHEET
R	REST	RESILIENT TILE
R	RET	RETAINING
R	REV	REVISE / REVISION
R	RF	RESILIENT FLOORING
R	RFG	ROOFING
R	RFL	REFLECTED
R	RH	RIGHT HAND
R	RM	ROOM
R	RO	ROUGH OPENING / ROOF OVERFLOW
R	RS	RUBBER SHEET FLOORING
R	RST	RUBBER STAIR TREADS
R	RSTR	RUBBER STAIR TREADS & RISERS
R	RT	RUBBER TILE
R	RWD	REDWOOD
R	RWL	RAIN WATER LEADER
S	S	SOUTH
S	SC	SOLID CORE
S	SCD	SEAT COVER DISPENSER
S	SCHED	SCHEDULE
S	SCN	SCREEN
S	SCR	SCREEN
S	SD	SOAP DISPENSER / STORM DRAIN
S	SDC	SEALED CONCRETE
S	SECT	SECTION
S	SF	SQUARE FEET
S	SFRM	SPRAYED-APPLIED FIRE RESISTIVE MATERIAL
S	SHT	SHEET
S	SHTG	SHEATHING
S	SHWR	SHOWER
S	SIM	SIMILAR
S	SND	SANITARY NAPKIN DISPENSER
S	SNR	SANITARY NAPKIN RECEPTACLE
S	SOG	SLAB ON GRADE
S	SPEC	SPECIFY / SPECIFICATION
S	SPK	SPEAKER
S	SQ	SQUARE
S	SQFT	SQUARE FEET
S	SQIN	SQUARE INCH(ES)
S	SS	STAINLESS STEEL
S	ST	STONE
S	STA	STATION
S	STC	STAINED CONCRETE
S	STD	STANDARD
S	STDS	STUDS
S	STIFF	STIFFENER
S	STL	STEEL
S	STN	STAINED
S	STOR	STORAGE
S	STRUCT	STRUCTURE / STRUCTURAL
S	SUSP	SUSPENDED
S	SW	SWITCH
S	SYM	SYMMETRICAL
S	SYN	SYNTHETIC
S	SYS	SYSTEM
T	T&B	TOP AND BOTTOM
T	T&G	TONGUE AND GROOVE
T	T.O.	TOP OF
T	TB	TOWEL BAR
T	TBD	TO BE DETERMINED
T	TC	TOP OF CURB
T	TEL	TELEPHONE
T	TEMP	TEMPORARY / TEMPERATURE
T	TER	TERRAZZO
T	THK	THICK
T	THRU	THROUGH
T	TOC	TOP OF CONCRETE
T	TOS	TOP OF SLAB
T	TOW	TOP OF WALL
T	TPD	TOILET PAPER DISPENSER
T	TPTN	TOILET PARTITION
T	TV	TELEVISION
T	TYP	TYPICAL
U	UC	UNDERCUT
U	UG	UNDERGROUND
U	UL	UNDERWRITER'S LABORATORY
U	UNF / UNFIN	UNFINISHED
U	UON	UNLESS OTHERWISE NOTED
U	UPS	UNINTERRUPTIBLE POWER SUPPLY
U	UR	URINAL
V	V	VOLT
V	VAC	VACUUM
V	VB	VAPOR BARRIER
V	VCT	VINYL COMPOSITION TILE
V	VENT	VENTILATE
V	VERT	VERTICAL
V	VEST	VESTIBULE
V	VIF	VERIFY IN FIELD
V	VNR	VENEER
V	VOL	VOLUME
V	VST	VINYL STAIR TREADS
V	VSTR	VINTYL STAIR TREADS & RISERS
V	VT	VINYL TILE
V	VTR	VENT THRU ROOF
V	VWC	VINYL WALLCOVERING
W	W	WEST
W	W/	WITH
W	W/O	WITHOUT
W	WC	WATER CLOSET
W	WCV	WALLCOVERING
W	WD	WOOD
W	WF	WIDE FLANGE
W	WG	WIRE GLASS
W	WH	WALL HOSE / HYDRANT
W	WI	WROUGHT IRON
W	WIN	WINDOW
W	WK	WORK
W	WNSCT	WAINSCOT
W	WP	WATERPROOF(ING)
W	WPT	WORK POINT
W	WR	WATER RESISTANT
W	WRR	WOOD RISER
W	WT	WEIGHT
Y	YD	YARD

Project Management Initials:

Designer: Designer Checked: Checker Approved: ApproverARCH E1 30"x42"

Last Plotted: 8/26/2019 3:58:25 PM
Filename: BM 300\60601397-Publix HQ\60601397_Publix HQ_ARCH_E2019.rvt

Printed on ___% Post-Consumer Recycled Content Paper

This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever to any party that modifies this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

©2016 AECOM Corporation

Building Inspection Division

THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE

Lakeland Permit Services

Date: 11/15/19

Permit Number: BLD19-06035

AECOM

BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

www.aecom.com

REGISTRATION

STATE OF FLORIDA
STEPHEN PANZARINO
AR92622
REGISTERED ARCHITECT

STEPHEN PANZARINO, REGISTERED ARCHITECT, STATE OF FLORIDA, LICENSE NO. AR92622

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY STEPHEN PANZARINO, REGISTERED ARCHITECT, STATE OF FLORIDA, LICENSE NO. AR92622 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES

Panzarino, Stephen

Digitally signed by Panzarino, Stephen
DN: CN="Panzarino, Stephen", OU=USTPA1, OU=US, OU=AMER, OU=AECOMUsers, DC=na, DC=aecomnet, DC=com
Date: 2019.08.26 16:37:17-04'00'

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G1-16.005 F.A.C.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
0	AUG 23, 2019	CONSTRUCTION DOCUMENTS
	JUN. 27, 2019	CURTAIN WALL DESIGN PACKAGE
	JUN. 27, 2019	STEEL DESIGN PACKAGE
	MAY 31, 2019	35% DESIGN COMPLETION
	MAY 01, 2019	ISSUED FOR APPROVAL

PROJECT NUMBER

60601397

SHEET TITLE

ABBREVIATIONS

SHEET NUMBER

A0-1-01