Project Management Initials:
Designer: Designer Checker: Checker Approved: ApproverARCH E1 30"x42"

Building Inspection Division
Lakeland
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Date: 11/15/19
Permit Number: BLD19-06035

LEVEL 1	SF	OCCUPANCY (NEW)
BUSINESS (EXISTING)	72,900	
STORAGE (EXISTING)	5,100	
ASSEMBLY NOT CONCENTRATED (EXISTING)	16,890	
ASSEMBLY CONCENTRATED (EXISTING)	3,471	
BUSINESS	**63,229**	**633**
STORAGE	**491**	**2**
TOTAL:	**162,081**	

LEVEL 2	SF	OCCUPANCY (NEW)
BUSINESS (EXISTING)	108,900	
BUSINESS	**64,743**	**648**
TOTAL:	**173,643**	

LEVEL 3	SF	OCCUPANCY (NEW)
BUSINESS (EXISTING)	108,900	
BUSINESS	**64,743**	**648**
TOTAL:	**173,643**	

TOTAL AREAS	SF	OCCUPANCY (NEW)
TOTAL AREA EXISTING	316,161	
TOTAL AREA NEW	193,206	**1,931**
OVERALL TOTAL AREA	509,367	

BUILDING AREAS AND OCCUPANCY COUNT

APPLICABLE CODES
Florida Building Code Sixth Edition 2017 - Building
Florida Building Code Sixth Edition 2017 - Existing Building
Florida Building Code Sixth Edition 2017 - Accessibility
Florida Fire Prevension code Sixth Edition
NFPA 101 - 2018

APPLICABLE CODES

BUILDING CODE ANALYSIS: EXISTING BUILDING

Year Built: 2001

Building Code in Effect at the time of Construction:		**1997 Standard Building Code**	***Current Building Code in Effect:***		**Florida Building Code, Sixth Edition (2017)**
Occupancy:	Business	Section 305.1	Occupancy:	Business	Section 304.1
Construction Type:	*II Non-Combustible*	Section 604 & Table 600	Construction Type:	*IB Non-Combustible*	Section 602.2 & Table 601
Fire Resistance Ratings:			**Fire Resistance Ratings:**		
Interior Bearing Walls	3 Hours	Table 600	**Interior Bearing Walls**	2 Hours	Table 601
Exterior Bearing Walls	3 Hours	Table 600	**Exterior Bearing Walls**	2 Hours	Table 601
Columns:			**Primary Structural Frame (Columns, Beams, Girders & Bracing Members)**	2 Hours	Table 601
Supporting Columns or more than one floor	3 Hours	Table 600			
Supporting one floor only	2 Hours	Table 600			
Supporting roofs only	2 Hours	Table 600			
Beams, Girders, Trusses & Arches:					
Supporting Columns or more than one floor	3 Hours	Table 600			
Supporting one floor only	2 Hours	Table 600			
Supporting roofs only	1 Hour	Table 600	Supporting roofs only	1 Hour	Table 601, Note a.
Floors & Floor-Ceiling Assemblies	2 Hours	Table 600	**Floor Construction & associ -ated secondary members**	2 Hours	Table 601
Roof & Roof-Ceiling Assemblies	1 Hour	Table 600	**Roof Construction & associ-ated secondary members**	1 Hour	Table 601
Building Limitations:			**Building Limitations:**		
Maximum Height:	80 Feet	Table 500	Maximum Height:	180	Table 504.3
Fire Sprinklers?	Yes		Fire Sprinklers?	Yes	
Maximum No. of Stories:	Not Limited	Table 500	Maximum No. of Stories:	12 Stories	Table 504.4
Maximum Area	Unlimited	Table 500	Maximum Area	Unlimited	Table 506.2 (See NOTE 1)

NOTES:
1. Per Table 506.2, an addition of Type IA construction can be attached to the existing building without requiring a fire wall
2. The Florida Fire Prevention Code, Sixth Edition, does not address the types of construction or their limitations

CODE ANALYSIS EXISTING BUILDING

PUBLIX HQ EXPANSION - Code Analysis Summary	REQUIREMENT	Reference to Florida Building Code Sixth Edition 2017 BUILDING
GENERAL		
Construction Type	1B - Non-Combustible	602.2 / Table 601
Fire Protection	Sprinklered	
HEIGHT AND LIMITS		
Maximum Height	180'	Table 504.3
Maximum No. of Stories Above Grade	12	Table 504.4
Maximum Area	Unlimited	Table 506.2
FIRE PROTECTION		
Primary Structural Frame	2 hrs.	Table 601
Interior Bearing Wall	2 hrs.	
Exterior Bearing Walls	2 hrs.	
Exterior Non-Bearing Wall Partitions		
Interior Non-Bearing Wall Partitions	0 hrs.	
Floor Construction and Associated Secondary Members	2 hrs.	
Roof Construction and Associated Secondary Members	1 hr.	
Fire Separation between S-1 AND B Occupancies	No Requirement	Table 508.4
Shaft Enclosures	2 hr.	713.4
Opening Fire Protection Assemblies , Ratings and Markings:	2 hr. (Wall)	Table 716.5
Enclosures for Shafts, Interior Exit Stairways and Interior Exit Ramps	1 1/2 hr. (Door)	
Interior Finishes Classification 1		Table 803.11
Fire Extinguishers	Max Floor Area: 3,000 SF Max Reach Distance: 75' Count per Level: 1st.: 63,720 / 3,000 = 22 2nd.: 64,743 / 3,000 = 22 3rd.:64,743 / 3,000 = 22	Table 906.3(1)
OCCUPANCY		
Business	Load Factor: 100 SF/Occupant (Gross)	Table 1004.1.2
Storage	Load Factor: 300 SF/Occupant (Gross)	
MEANS OF EGRESS		
No. of Exits	4	Table 1006.3.1
Common Path of Egress - Business	100' (Max. Occupant load: 49)	Table 1006.2.1
Common Path of Egress - Storage	100' (Max. Occupant load: 29)	
Dead end	50'	1020.4.2
Travel Distance	Business: 300'	Table 1017.2
	Storage: 400'	
Vertical Rise Between Stair Landings	12' Max.	1011.8

CODE ANALYSIS SUMMARY - ADDITION

NEW EXPANSION

		AREA	OCCUPANCY	FEMALE Water Closets required	FEMALE Water Closets provided	FEMALE Lavatories required	FEMALE Lavatories provided	MALE Water Closets required	MALE Water Closets provided	MALE Urinals* provided	MALE Lavatories required	MALE Lavatories provided	Drinking Fountains required	Drinking Fountains provided**	Service Sinks required	Service Sinks provided
BUSINESS / STORAGE	Level 1	63,720 SF	635/2 =318	8	**8**	6	**6**	8	**4**	**4**	6	**6**	7	6	1	1
	Level 2	64,743 SF	648/2 = 324	8	**8**	6	**6**	8	**4**	**4**	6	**6**	7	6	1	1
	Level 3	64,743 SF	648/2 = 324	8	**8**	6	**6**	8	**4**	**4**	6	**6**	7	6	1	1
				24	**24**	18	18	24	12	12	18	18	21	18	3	3

* one water dispenser provided at each break room

EXISTING

BUSINESS	Level 1	72,900 SF	720/2 = 360	8.2		5.7		8.2			5.7		7.2			
	Level 2	108,862 SF	1089/2 = 545	11.9		7.8		11.9			7.8		10.9			
	Level 3	108,862 SF	1089/2 = 545	11.9		7.8		11.9			7.8		10.9			
ASSEMBLY	Level 1	20,311 SF	2283/2 = 1142	15.2		5.7		15.2			5.7		4.6			
	Level 2	0 SF														
	Level 3	0 SF														
STORAGE	Level 1	5,100 SF	17/2= 9	0.1		0.1		0.1			0.1		0.0			
	Level 2	0 SF														
	Level 3	0 SF														
TOTAL	Level 1			**24**		**12**		**24**			**12**		**12**			
	Level 2			**12**		**8**		**12**			**8**		**11**			
	Level 3			**12**		**8**		**12**			**8**		**11**			

TOILET COUNT CALCULATION

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

www.aecom.com

REGISTRATION

STATE OF FLORIDA
STEPHEN PANZARINO
AR92622
REGISTERED ARCHITECT

STEPHEN PANZARINO, REGISTERED ARCHITECT, STATE OF FLORIDA, LICENSE NO. AR92622

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY STEPHEN PANZARINO, REGISTERED ARCHITECT, STATE OF FLORIDA, LICENSE NO. AR92622 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES

Panzarino, Stephen
Digitally signed by Panzarino, Stephen
DN: CN="Panzarino, Stephen", OU=USTPA1, OU=US, OU=AMER, OU=AECOMUsers, DC=na, DC=aecomnet, DC=com
Date: 2019.09.30 16:28:54-04'00'

ISSUE/REVISION

I/R	DATE	DESCRIPTION
1	SEP 30, 2019	100% CONSTRUCTION DOCUMENTS
0	AUG 23, 2019	CONSTRUCTION DOCUMENTS
	MAY 31, 2019	35% DESIGN COMPLETION
	MAY 01, 2019	ISSUED FOR APPROVAL

PROJECT NUMBER

60601397

SHEET TITLE

CODE ANALYSIS SUMMARY

SHEET NUMBER

A0-2-00

This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever to any party that modifies this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G1-16.005 F.A.C.

Last Plotted: 9/27/2019 5:17:39 PM
Filename: BM 3600\60601397-Publix HQ\60601397_Publix HQ_ARCH_R2019.rvt

Printed on ___% Post-Consumer Recycled Content Paper

©2016 AECOM Corporation