Building Inspection Division
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Lakeland
Date: 11/15/19
Permit Number: BLD19-06035

GENERAL NOTES:

GENERAL

1. THE CONTRACTOR SHALL BECOME FAMILIAR WITH THE PERMIT AND INSPECTION REQUIREMENTS SPECIFIED BY THE VARIOUS GOVERNMENTAL AGENCIES, THE ENGINEER, AND THE ARCHITECT; OBTAIN ALL NECESSARY PERMITS PRIOR TO CONSTRUCTION; PROVIDE A COMPLETE SET OF TESTING REPORTS FOR ALL TESTS PERFORMED, AND SCHEDULE ANY NECESSARY INSPECTIONS ACCORDING TO AGENCY INSTRUCTIONS (AT CONTRACTOR'S EXPENSE).

2. DIGITAL OR ELECTRONIC REPRESENTATION OF THESE CONSTRUCTION PLANS DOES NOT CONSTITUTE A COORDINATE CONTROL MAP OR MATHEMATICALLY CONTROLLED INFORMATION FOR THE USE OF CONSTRUCTION STAKEOUT. IT IS THE RESPONSIBILITY OF THE CONTRACTOR AND/OR CONTRACTOR'S SURVEYOR TO ENSURE THAT ANY DIGITAL OR ELECTRONIC REPRESENTATION OF THESE PLANS IS IN COMPLETE CONFORMANCE WITH ALL OF THE NOTATIONS, SPECIFICATIONS, DETAILS AND OTHER DATA APPEARING ON OR AS MAY BE DERIVED FROM THESE CONSTRUCTION PLANS.

3. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY AND ACCEPT ALL CONSTRUCTION STAKES PRIOR TO STARTING ANY CONSTRUCTION. ANY QUESTIONS RAISED RELATIVE TO THE ACCURACY OF IMPROVEMENT INSTALLATION WILL NOT BE RAISED SUBSEQUENT TO THE COMPLETION OF WORK UNLESS ALL SURVEY STAKES ARE MAINTAINED INTACT. SHOULD SUCH STAKES NOT BE PRESENT AND VERIFIED AS TO THEIR ORIGIN, NO CLAIM FOR ADDITIONAL COMPENSATION CORRECTION WILL BE PRESENTED TO ANY PARTY AND SUCH WORK WILL BE CORRECTED BY THE CONTRACTOR AT HIS/HER OWN EXPENSE.

4. LOCATIONS, ELEVATIONS, AND DIMENSIONS OF EXISTING UTILITIES, STRUCTURES AND OTHER FEATURES ARE SHOWN ACCORDING TO THE BEST INFORMATION AVAILABLE AT THE TIME OF PREPARATION OF THESE PLANS, BUT DO NOT PURPORT TO BE ABSOLUTELY CORRECT. ALL CONTRACTORS ARE DIRECTED, PRIOR TO BIDDING AND CONSTRUCTION, TO CONDUCT WHATEVER INVESTIGATION NECESSARY TO DETERMINE THE ACTUAL CONDITIONS THAT WILL BE ENCOUNTERED. THERE MAY BE OTHER IMPROVEMENTS, UTILITIES, ETC. WHICH ARE WITHIN THE PROJECT AREA AND WHICH HAVE BEEN INSTALLED AND CONSTRUCTED SINCE THE PREPARATION OF THESE PLANS. THE CONTRACTOR SHALL VERIFY, PRIOR TO CONSTRUCTION, THE LOCATIONS, ELEVATIONS, AND DIMENSIONS OF ALL EXISTING UTILITIES, STRUCTURES AND OTHER FEATURES (WHETHER OR NOT SHOWN ON THE PLANS) AFFECTING THIS WORK PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY THE OWNER'S PROJECT REPRESENTATIVE OR ENGINEER OF RECORD (E.O.R.) IMMEDIATELY WHEN CONFLICTS BETWEEN DRAWINGS AND ACTUAL CONDITIONS ARE DISCOVERED.

5. THE CONTRACTOR SHALL EXERCISE EXTREME CAUTION IN AREAS OF BURIED UTILITIES AND SHALL PROVIDE AT LEAST 48 HOURS NOTICE TO THE UTILITY COMPANIES PRIOR TO CONSTRUCTION TO OBTAIN FIELD LOCATIONS OF EXISTING UNDERGROUND UTILITIES. CALL SUNSHINE 811 / SUNSHINE STATE ONE CALL CENTER OF FLORIDA AT 1-800-432-4770 TO ARRANGE FIELD LOCATIONS.

6. THE CONTRACTOR SHALL VERIFY LOCATIONS AND DEPTHS OF ALL EXISTING UNDERGROUND UTILITIES PRIOR TO BEGINNING CONSTRUCTION AND REPORT ANY DISCREPANCIES TO THE OWNER OR ENGINEER IMMEDIATELY FOR RESOLUTION.

7. CONTRACTOR SHALL FIELD-VERIFY ALL DEPTHS, LENGTHS, DIMENSIONS, ETC. IN THE FIELD AND SHALL NOT RELY ON SCALING PRINTS. DRAWING SCALES MAY NO LONGER BE ACCURATE WHEN SHEETS ARE PLOTTED TO SIZES OTHER THAN THOSE INDICATED ON THE DRAWINGS. REPRODUCTION MAY CAUSE DISTORTION OF DRAWINGS AND/OR SCALES.

8. EXISTING POTABLE WATER SERVICE, SEWER SERVICE, TELEPHONE SERVICE, POWER SERVICE, AND CABLE TV SERVICE LINES TO INDIVIDUAL PROPERTIES ARE NOT SHOWN ON THE DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD LOCATING ALL SERVICES AND FOR MAINTAINING THEM AT ALL TIMES.

9. THE CONTRACTOR IS RESPONSIBLE FOR REPAIRING ANY DAMAGE TO EXISTING FACILITIES (AT THE CONTRACTOR'S EXPENSE), ABOVE OR BELOW GROUND THAT MAY OCCUR AS A RESULT OF THE WORK PERFORMED BY THE CONTRACTOR IN THIS CONTRACT.

10. THE CONTRACTOR SHALL RESTRICT ALL WORK TO WITHIN THE PROPERTY AREA/RIGHT-OF-WAY LINES AS DESIGNATED UNLESS OTHERWISE SPECIFIED. DAMAGES TO PROPERTY OUTSIDE THE PROJECT LIMITS/RIGHT-OF-WAY SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.

11. THE CONTRACTOR SHALL REPLACE ALL EXISTING FEATURES OUTSIDE THE PROJECT LIMITS THAT ARE DISTURBED DURING CONSTRUCTION INCLUDING BUT NOT LIMITED TO CURB, PAVEMENTS, SIDEWALKS, AND LANDSCAPING TO A CONDITION EQUAL TO OR BETTER THAN THE PRE-EXISTING CONDITION. ALL REPLACEMENTS SHALL BE IN ACCORDANCE WITH RELEVANT LOCAL ENGINEERING CONSTRUCTION STANDARDS AND THE FDOT STANDARDS AND SPECIFICATIONS AT NO COST TO THE OWNER.

12. A REGISTERED LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE SHALL RESET ALL SECTION CORNERS OR PROPERTY CORNERS DISLOCATED OR DISTURBED BY THE CONSTRUCTION ACTIVITIES.

13. DURING LAND ALTERATION AND CONSTRUCTION ACTIVITIES, IT SHALL BE UNLAWFUL TO REMOVE VEGETATION BY GRUBBING OR TO PLACE SOIL DEPOSITS, DEBRIS, SOLVENTS, CONSTRUCTION MATERIAL, MACHINERY OR OTHER EQUIPMENT OF ANY KIND WITHIN THE DRIPLINE OF A TREE REMAINING ON SITE UNLESS APPROVED BY THE RELEVANT AGENCY OR LANDSCAPE ARCHITECT OF RECORD.

14. ALL MATERIALS, INSTALLATION, EROSION AND SEDIMENT CONTROLS AND CONSTRUCTION SHALL BE IN ACCORDANCE WITH RELEVANT LOCAL ENGINEERING CONSTRUCTION STANDARDS, CITY OF LAKELAND ENGINEERING STANDARDS MANUAL (LATEST EDITION), FLORIDA DEPARTMENT OF TRANSPORTATION STANDARDS PLANS (LATEST EDITION), FLORIDA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION (LATEST EDITION), PROJECT TECHNICAL SPECIFICATIONS, AND FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION (FDEP) STANDARDS (LATEST EDITION).

15. SIGHT TRIANGLES SHALL BE UNOBSTRUCTED, AND SHALL BE INSPECTED AND MAINTAINED IN ACCORDANCE WITH FDOT STANDARDS, LATEST EDITION.

16. NO STOCKPILING OR MATERIAL IN ROADWAY OR ON SIDEWALK; ALL DIRT AND DEBRIS WILL BE REMOVED FROM JOB SITE DAILY. ROADS AND SIDEWALKS TO BE SWEPT DAILY AS PART OF DAILY CLEAN-UP.

17. THERE ARE NO KNOWN HISTORIC RESOURCES ON SITE. HOWEVER, IF, DURING CONSTRUCTION ACTIVITIES, ANY EVIDENCE OF HISTORIC RESOURCES INCLUDING, BUT NOT LIMITED TO, ABORIGINAL OR HISTORIC POTTERY, PREHISTORIC STONE TOOLS, BONE OR SHELL TOOLS, HISTORIC TRASH PITS, OR HISTORIC BUILDING FOUNDATIONS ARE DISCOVERED, WORK SHALL COME TO AN IMMEDIATE STOP, AND THE LOCAL MUNICIPALITY AND THE FLORIDA DIVISION OF HISTORICAL RESOURCES (STATE HISTORIC PRESERVATION OFFICER) SHALL BE NOTIFIED WITHIN TWO WORKING DAYS.

18. IF, DURING CONSTRUCTION ACTIVITIES, ANY EVIDENCE OF THE PRESENCE OF STATE AND FEDERALLY PROTECTED PLANT AND/OR ANIMAL SPECIES ARE DISCOVERED, WORK SHALL COME TO AN IMMEDIATE STOP AND THE LOCAL MUNICIPALITY SHALL BE NOTIFIED WITHIN TWO WORKING DAYS.

19. THE CERTIFICATE OF OCCUPANCY WILL NOT BE ISSUED UNTIL THE FOLLOWING HAS BEEN COMPLETED:
 19.A. FINAL INSPECTION IN CONJUNCTION WITH OWNER'S PROJECT REPRESENTATIVE AND ENGINEER
 19.B. RECORD DRAWINGS HAVE BEEN SUBMITTED AND ACCEPTED BY THE ENGINEER AND PRESIDING AGENCIES
 19.C. ALL NECESSARY TESTS HAVE BEEN COMPLETED AND CERTIFIED BY THE ENGINEER AND PRESIDING AGENCIES
 19.D. PAYMENTS OF ALL CAPACITY FEES (BY THE OWNER)

20. REFER TO THE UTILITY NOTES FOR SPECIFIC CITY OF LAKELAND WATER AND WASTEWATER GENERAL REQUIREMENTS, TESTING PROCEDURES AND CERTIFICATION REQUIREMENTS.

21. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO REVIEW AND MAINTAIN A COPY OF THE SWFWMD, NPDES, CITY OF LAKELAND AND ALL OTHER JURISDICTIONAL PERMITS AT THE CONSTRUCTION SITE, AND ABIDE BY ALL CONDITIONS OF THOSE PERMITS.

22. HORIZONTAL AND VERTICAL CONTROL IS BASED ON THE PROJECT TOPOGRAPHIC AND BOUNDARY SURVEY PROVIDED BY: POLARIS ASSOCIATES, INC. BY DAN H. RIZZUTO (LS#5227), DATED JUNE 27, 2019. BOUNDARY SURVEY INFORMATION PROVIDED BY CHASTAIN SKILLMAN, BY ROBERT F. DUBOIS (LS#5293), DATED DECEMBER 9, 1999.

23. ALL REMOVED MATERIAL FROM THE SITE SHALL BE TRANSPORTED AND DISPOSED OF IN A LEGAL MANNER. ALL PERMITS REQUIRED FOR REMOVAL AND DISPOSAL SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

24. ALL DIMENSIONS, RADII, AND SPOT ELEVATIONS ARE REFERENCED TO THE EDGE OF PAVEMENT UNLESS OTHERWISE SHOWN.

25. CONTRACTOR IS RESPONSIBLE FOR ENSURING ALL REQUIRED MAINTENANCE OF TRAFFIC IS IN ACCORDANCE WITH FDOT ROADWAY AND TRAFFIC DESIGN STANDARDS, LATEST EDITION. CONTRACTOR'S MAINTENANCE OF TRAFFIC PLAN (WHEN APPLICABLE) MUST BE SUBMITTED AND APPROVED BY APPLICABLE AGENCIES AND ENGINEER PRIOR TO CONSTRUCTION ACTIVITIES.

26. QUANTITIES LISTED ON THESE PLANS ARE ESTIMATED ONLY. CONTRACTOR IS RESPONSIBLE FOR QUANTITY VERIFICATION.

GENERAL NOTES (CONTINUED):

AS-BUILTS/RECORD DRAWINGS

1. CERTIFIED AS-BUILT SURVEYS ARE NECESSARY FOR CONSTRUCTION CERTIFICATION BY THE ENGINEER OF RECORD. CERTIFIED AS-BUILTS SHALL BE PROVIDED TO THE E.O.R. AT LEAST FOUR (4) WEEKS PRIOR TO THE DATE OF RECORD DRAWING SUBMITTAL OR CONSTRUCTION CERTIFICATION SUBMITTAL TO APPLICABLE AGENCIES HAVING JURISDICTION (AHJ). CERTIFIED AS-BUILTS (SIGNED & SEALED) MEETING REQUIREMENTS OF SECTION 61617, F.A.C. SHALL BE PROVIDED BY A SURVEYOR LICENSED IN THE STATE OF FLORIDA. HORIZONTAL COORDINATES ARE BASED ON NAD 83 FLORIDA STATE PLANE COORDINATE SYSTEM, EAST ZONE. VERTICAL ELEVATIONS ARE BASED ON NAVD 88 DATUM. FILE FORMAT SHALL BE AUTOCAD (.DWG), VERSION 2013 (OR LATER). CONTRACTOR SHALL CONTRACT WITH, AND COORDINATE, THE AS-BUILT SURVEYOR. RECORD DRAWINGS AND AS-BUILTS SHALL ADHERE TO THE FOLLOWING REQUIREMENTS:
 A. HORIZONTAL AND VERTICAL CONTROL OF CONSTRUCTED ITEMS INCLUDING BUILDINGS; ROAD/PAVEMENT ELEVATIONS; ROADWAY CROSS SLOPES; PAVEMENT WIDTH; PAVEMENT SPOT ELEVATIONS NECESSARY TO CONFIRM STORMWATER DRAINAGE PATTERNS AT INTERSECTIONS AND SIDEWALKS; CURB SLOPES;
 B. STORMWATER PIPE SIZES, LENGTHS AND INVERT ELEVATIONS; ALL STORM STRUCTURE BOTTOM, TOP AND INVERT ELEVATIONS; LOCATION OF OUTFALL STRUCTURE(S) WITH AS-BUILT ELEVATIONS FOR ALL CONTROL STRUCTURE & SKIMMER ELEVATIONS SHOWN ON THE APPROVED PLANS; TOP OF BANK, GRADE BREAKS, BOTTOM ELEVATIONS FOR ALL STORMWATER PONDS OR BERM AREAS, DITCHES AND LITTORAL ZONES;
 C. LOCATE PIPE (HORIZONTAL AND VERTICAL ALIGNMENT/DEPTH OF COVER OR TOP OF PIPE ELEVATION AND PIPE LENGTH) AT REGULAR INTERVALS; PARTICULARLY NOTING WHERE PIPE ALIGNMENT (HORIZONTAL AND VERTICAL) VARIES FROM DESIGN. DESIGNATE TYPE OF PIPE (SIZE AND MATERIAL). SKETCH DETAILS AS REQUIRED. INVERT ELEVATIONS REQUIRED FOR SANITARY SEWER PIPE.
 D. LOCATE ALL ALIGNMENT CHANGES, BOTH HORIZONTAL AND VERTICAL, BY STATION AND OFFSET, ELEVATION AND DEPTH OF COVER FROM FINISHED GRADE.
 E. LOCATE ALL VALVES, BY STATION AND OFFSET, ELEVATION AND DEPTH OF COVER FROM FINISHED GRADE AND SHOW TYPE OF VALVE.
 F. LOCATE ALL FITTINGS (BENDS, REDUCERS, SLEEVES, PLUGS, CAPS, OFFSETS, TEES, CROSSES, ETC.) BY STATION AND OFFSET, ELEVATION, AND DEPTH OF COVER FROM FINISHED GRADE. DESIGNATE TYPE OF FITTINGS. SKETCH DETAILS AS REQUIRED.
 G. LOCATE CASING PIPES BY STATION AND OFFSET, ELEVATION AND DEPTH OF COVER FROM FINISHED GRADE AT BOTH ENDS. NOTE CASING SIZE.
 H. PROVIDE CHANGES TO FINISHED GRADE.
 I. REPORT ANY CHANGES IN ALIGNMENT OR ELEVATION OF OTHER UTILITIES. REPORT ALL UTILITIES NOT SHOWN ON PLANS.
 J. WHERE APPROPRIATE, LOCATE PIPE IN RELATION TO OTHER PHYSICAL FEATURES.
 K. PROVIDE VALVE TO HYDRANT DIMENSIONS INCLUDING DIAMETER.
 L. VERIFY BY INDICATING ON AS-BUILT DRAWING (BY CIRCLING OR CHECK MARKING) WHETHER OR NOT DESIGN DIMENSIONS ARE CORRECT.
 M. FIELD CHANGES OF THE DESIGN SHOULD BE ADEQUATELY DETAILED. STATIONS AND OFFSETS SHALL BE NOTED. SKETCH DETAILS AS REQUIRED.
 N. ALL STREET NAMES SHALL MATCH THOSE ON THE LATEST PLAT. NO ALPHABETIC OR NUMERIC SYMBOLS WILL BE ACCEPTED FOR STREET NAMES.
 O. ALL SANITARY SEWER STRUCTURE BOTTOM, TOP AND INVERT ELEVATIONS.
 P. PROVIDE CALCULATED SLOPE OF ALL SANITARY SEWER AND STORM SEWER LINES.
 Q. HORIZONTAL AND VERTICAL CONTROL ELEVATIONS OF ALL ELEMENTS OF SANITARY SEWER LIFT STATIONS AND GREASE INTERCEPTS (AS APPLICABLE) INCLUDING TOP AND BOTTOM SLABS, INVERTS, ELEVATIONS AT WHICH THE FLOAT SWITCHES ENGAGE, ALL VALVES AND ASSOCIATED APPURTENANCES.
 R. ANY OTHER AS-BUILT DATA THAT IS APPLICABLE TO THE PROJECT TO ENSURE COMPLETION IN ACCORDANCE WITH THE APPROVED CONSTRUCTION PLANS

RESTORATION

1. ROADWAY RESTORATION SHALL BE IN CONFORMANCE WITH CORRESPONDING JURISDICTIONS LATEST'S STANDARDS. 2. ALL ASPHALT OPEN CUTS WITHIN CITY RIGHT-OF-WAY SHALL BE FULLY MILLED AND OVERLAYED FROM EDGE OF PAVEMENT TO EDGE OF PAVEMENT PER THE WATER DEPARTMENT'S STANDARD DETAIL.

2. DISTURBANCE TO ANY PROPERTY, PUBLIC OR PRIVATE, AS PART OF THE CONSTRUCTION OF PUBLIC WATER FACILITIES, SHALL BE RESTORED TO ORIGINAL OR BETTER CONDITION.

PAVING, GRADING, AND DRAINAGE NOTES:

1. ALL UNDERGROUND UTILITIES INCLUDING CONDUIT FOR ELECTRICAL, IRRIGATION, CABLE TV AND TELEPHONE CROSSINGS MUST BE INSTALLED AND TESTED OR INSPECTED PRIOR TO BASE AND PAVEMENT CONSTRUCTION.

2. JOINTS OF STORM SEWER SHALL BE STAGGERED FOR CROSSINGS OF THE SANITARY SEWER WITH LESS THAN 18 INCHES OF VERCIAL CLEARANCE SO THAT THE PIPE BELL IS NOT LOCATED AT THE CROSSING.

3. ALL EARTHWORK, PLACEMENT OF FILL AND PAVEMENT PREPARATION TO CONFORM TO THE MORE STRICT OF THE LOCAL AGENCY TECHNICAL SPECIFICATIONS OR THE GEOTECHNICAL REPORT.

4. CONTRACTOR IS RESPONSIBLE FOR PROVIDING APPLICABLE SOILS AND MATERIALS TESTING AND SUBMIT TESTING TO THE OWNER'S PROJECT REPRESENTATIVE OR ENGINEER ON A WEEKLY BASIS. TESTS WILL BE REQUIRED PURSUANT WITH THE TESTING SCHEDULE REQUIRED BY THE AGENCY HAVING JURISDICTION OVER THE WORK, PERMIT CONDITIONS, PROJECT TECHNICAL SPECIFICATIONS GEOTECHNICAL ENGINEER AND THE CONTRACT DOCUMENTS.

5. A QUALIFIED TESTING LABORATORY SELECTED BY THE OWNER SHALL PERFORM ALL TESTING NECESSARY TO ASSURE COMPLIANCE OF THE IN PLACE MATERIALS AS REQUIRED BY THESE PLANS AND THE VARIOUS AGENCIES. SHOULD ANY RETESTING BE REQUIRED DUE TO THE FAILURE OF ANY TESTS TO MEET THE REQUIREMENTS, THE CONTRACTOR WILL BEAR ALL COSTS OF SAID RETESTING.

6. AS A COST SAVINGS MEASURE, STORM STRUCTURES WITH MULTIPLE PIPE CONNECTIONS MAY BE OFFSET FROM THE CENTER OF THE STRUCTURE TO REDUCE THE OVERALL STRUCTURE SIZE. CONTRACTOR IS TO COORDINATE OFFSET CONNECTIONS WITH OWNER'S PROJECT REPRESENTATIVE OR ENGINEER.

7. ALL PROPOSED STORM GRATES AND RING & COVERS TO MEET H-20 LOAD RATING. ALL STORM GRATES TO BE HOT DIPPED GALVANIZED RETICULINE STEEL GRATES. ALL EXISTING STRUCTURES TO BE LOCATED IN TRAFFIC AREAS TO BE MODIFIED AS REQUIRED TO MEET H-20 LOAD RATING AND ADJUSTED TO MEET PROPOSED GRADE.

8. STORM SEWER PIPE LINES WILL NOT BE INSTALLED PRIOR TO PLACEMENT AND ALIGNMENT OF INLET AND MANHOLE STRUCTURES.

9. ALL STORM DRAINAGE PIPING SHALL BE SUBJECT TO LAMPING INSPECTION BY THE OWNER'S PROJECT REPRESENTATIVE AND THE ENGINEER PRIOR TO PLACEMENT OF BACKFILL, AS NECESSARY. CONTRACTOR TO NOTIFY THE OWNER, ENGINEER, AND ANY APPLICABLE AGENCIES 48 HOURS IN ADVANCE TO SCHEDULE INSPECTIONS. CONTRACTOR MUST PROVIDE INSTRUMENTS NECESSARY TO PERFORM LAMPING INSPECTION.

10. THROUGH THE USE OF BEST MANAGEMENT PRACTICES (BMPS) THE CONTRACTOR SHALL MAINTAIN AND PROTECT FROM MUD, DIRT, DEBRIS, ETC. THE STORM DRAINAGE SYSTEM UNTIL FINAL ACCEPTANCE OF THE PROJECT. THE CONTRACTOR MAY BE REQUIRED TO RE-CLEAN PIPES AND INLETS FOR INSPECTION PURPOSES, AND FOR FINAL ACCEPTANCE OF THE SYSTEM.

11. THE CONTRACTOR SHALL REPLACE ALL PAVING, STABILIZED EARTH, CURBS, DRIVEWAYS, SIDEWALKS, ETC. PER LOCAL AGENCY ENGINEERING CONSTRUCTION STANDARDS WITH MATERIALS OF THE SAME TYPE OR BETTER THAN THAT ARE REMOVED OR DAMAGED DURING CONSTRUCTION.

12. CONTRACTOR SHALL SAW CUT EXISTING EDGE-OF-PAVEMENT PRIOR TO ASPHALT OR CONCRETE REMOVAL.

13. ALL STORMWATER INLETS SHALL MEET FDOT CRITERIA AS SPECIFIED IN THE FDOT STANDARD PLANS (LATEST EDITION).

14. ALL GASKETS SHALL BE LUBRICATED BEFORE BEING INSTALLED.

15. ALL FITTINGS SHALL MEET THE MINIMUM RESTRAINED REQUIREMENTS PER ANSI/AWWA/DIPRA.

16. ALL PVC ROOF DRAIN COLLECTION SYSTEMS PIPES SHALL BE C900 PVC PIPE. ALL FITTINGS FOR THE UNDERGROUND COLLECTION MANIFOLD SYSTEM AND ALL FITTINGS FOR THE ROOF DRAIN CONNECTIONS TO THE SYSTEM SHALL BE MECHANICAL JOINTS. PUSH-ON/GLUE JOINT RESTRAINTS SHALL NOT BE USED FOR THE ROOF DRAIN COLLECTION SYSTEM.

EROSION AND SEDIMENT CONTROL NOTES:

1. CONTRACTOR SHALL ENSURE EROSION CONTROL MEASURES REQUIRED PER THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP) ARE INSTALLED PRIOR TO ANY LAND DISTURBANCE, CLEARING OR MASS GRADING ACTIVITIES.

2. TO MINIMIZE SOIL EROSION, PROPOSED LAND ALTERATION ACTIVITIES SHALL NOT UNNECESSARILY REMOVE EXISTING VEGETATION OR ALTER EXISTING TOPOGRAPHY. APPROPRIATE PROTECTION MEASURES SHALL BE PROVIDED, AS NECESSARY, TO MINIMIZE EROSION AND DOWNSTREAM SEDIMENTATION CAUSE BY SURFACE WATER RUN-OFF ON EXPOSED LAND SURFACES.

3. THE INSTALLATION OF THE TEMPORARY EROSION CONTROL MEASURES SHALL BE COORDINATED WITH THE CONSTRUCTION OF THE PERMANENT EROSION CONTROL FEATURES TO THE EXTENT NECESSARY TO ENSURE ECONOMICAL, EFFECTIVE AND CONTINUOUS CONTROL OF EROSION AND WATER POLLUTION THROUGHOUT THE LIFE OF THE CONSTRUCTION PHASE.

4. ALL EROSION CONTROL MEASURES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST ONCE DAILY DURING ANY PROLONGED RAINFALL, AND AS REQUIRED PER THE SWPPP. REQUIRED REPAIRS TO THE EROSION CONTROL FEATURES SHALL BE MADE IMMEDIATELY.

5. EROSION CONTROL FEATURES THAT DECOMPOSE OR BECOME OTHERWISE INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE OR THE END OF THE CONSTRUCTION ACTIVITY ON THE PROJECT SHALL BE REPLACED IMMEDIATELY.

6. THE TYPE OF EROSION CONTROL BARRIERS USED SHALL BE TAILORED TO THE NATURE OF THE CONSTRUCTION OPERATION AND SOIL TYPE(S) THAT WILL BE EXPOSED. FLOATING TURBIDITY CURTAINS SHALL BE USED IN OPEN WATER SITUATIONS. DIVERSION DITCHES OR SWALES SHALL BE USED WHERE NECESSARY TO PREVENT TURBID STORMWATER RUNOFF FROM BEING DISCHARGED TO WETLANDS OR OTHER WATER BODIES.

7. WHERE CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED PUBLIC ROADS, PROVISIONS SHALL BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT OFF-SITE THROUGH SOIL TRACKING PREVENTION DEVICES PER FDOT AND FDOT STANDARDS, AND DETAIL ON SHEET CG-541. PROPOSED LOCATIONS ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL ENSURE THE SWPPP ACCURATELY REFLECTS THE LOCATION OF THE SITE CONSTRUCTION ENTRANCE AND IS UPDATED IMMEDIATELY UPON ANY CHANGE IN LOCATION OF THE ENTRANCE DURING CONSTRUCTION. IF SEDIMENT IS TRANSPORTED ONTO A PUBLIC ROAD, THE ROAD SHALL BE CLEANED THOROUGHLY AT THE END OF EACH DAY BY MEANS OF SHOVELING OR SWEEPING THE ROAD AND TRANSPORTING THE MATERIAL TO AN ONSITE SEDIMENT CONTROL DISPOSAL AREA.

8. THE CONTRACTOR SHALL PROVIDE ROUTINE MAINTENANCE OF PERMANENT AND TEMPORARY EROSION CONTROL FEATURES UNTIL THE PROJECT IS COMPLETE AND ALL BARED SOIL IS STABILIZED. SILTATION ACCUMULATIONS GREATER THAN THE LESSER OF 12 INCHES OR ONE-HALF THE DEPTH OF THE SILTATION CONTROL BARRIER SHALL BE IMMEDIATELY REMOVED AND PLACED IN UPLAND AREAS.

9. SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN SYSTEM, DITCH OR CHANNEL (EXISTING AND PROPOSED). ALL STORM SEWER INLETS IN OPERATION DURING CONSTRUCTION ACTIVITY SHALL BE PROTECTED TO PREVENT SEDIMENT-LADEN WATER FROM ENTERING THE CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR TREATED TO REMOVE SEDIMENT.

10. CONTRACTOR SHALL BE RESPONSIBLE FOR DEWATERING, TESTING AND OBTAINING ANY PERMITS ASSOCIATED WITH DEWATERING ACTIVITIES AS OUTLINED IN THE CONTRACT DOCUMENTS.

11. ANY DISCHARGE FROM DEWATERING ACTIVITY SHALL BE FILTERED AND CONVEYED TO THE OUTFALL IN SUCH A MANNER THAT PREVENTS EROSION AND TRANSPORTATION OF SUSPENDED SOLIDS TO THE RECEIVING OUTFALL.

12. SOD ALL AREAS LEFT BARREN AND OR DISTURBED BY CONSTRUCTION IN ACCORDANCE WITH THE LANDSCAPE PLANS, PROJECT TECHNICAL SPECIFICATIONS AND THE REQUIREMENTS OF THE SWPPP.

13. EROSION AND SEDIMENT CONTROL FEATURES SHALL ONLY BE REMOVED AFTER COMPLETION OF CONSTRUCTION AND ONLY AFTER ALL AREAS HAVE BEEN STABILIZED.

14. ALL PROPOSED EROSION AND SEDIMENT CONTROL FEATURES SHOWN ON THESE PLANS ARE FOR REFERENCE ONLY AND SHALL BE ADJUSTED, AS REQUIRED, TO SUIT THE CONSTRUCTION ACTIVITY AND SEQUENCING. THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING AND OBTAINING APPROVAL FOR THE PROPOSED STORMWATER POLLUTION PREVENTION PLAN (SWPPP) USED DURING CONSTRUCTION.

15. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND AIR AND WATER POLLUTION WILL BE MINIMIZED. CONTRACTOR TO COMPLY WITH ALL REGULATIONS AS SET FORTH BY THE FDEP NPDES STORMWATER REGULATORY PROGRAM AS WELL AS ALL APPLICABLE STATE AND LOCAL LAWS.

16. THE CONTRACTOR SHALL BE REQUIRED TO RESPOND TO ALL WATER MANAGEMENT DISTRICT AND FDEP INQUIRIES RELATIVE TO THE COMPLIANCE OF EROSION AND SEDIMENTATION CONTROLS. THE COST OF THIS COMPLIANCE AND COORDINATION SHALL BE PART OF THE CONTRACT. COPIES OF ALL INQUIRIES SHALL BE FORWARDED TO THE ENGINEER FOR REVIEW.

UTILITY NOTES:

GENERAL

1. THE CONTRACTOR SHALL VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO ANY DEMOLITION TO INSURE THAT ONLY THE UTILITIES AND FEATURES MARKED FOR DEMOLITION ARE REMOVED AND OTHER UTILITIES AND FEATURES ARE NOT DISTURBED. ANY UTILITIES TO REMAIN WHICH ARE DISTURBED BY THE CONTRACTOR SHALL BE IMMEDIATELY REPAIRED BY THE CONTRACTOR AT HIS EXPENSE.

2. EXISTING SERVICES SHALL NOT BE REMOVED OR DISRUPTED, UNLESS COORDINATED AND APPROVED BY THE APPROPRIATE UTILITY COMPANY, AND UNTIL THE NEW RELOCATED SERVICE (IF APPLICABLE) HAS BEEN INSTALLED.

3. THE CONTRACTOR SHALL REMOVE ALL EXISTING, DEACTIVATED AND DECOMMISSIONED UNDERGROUND UTILITIES WITHIN THE EARTHWORK EXCAVATION LIMITS OF THE PROJECT. DECOMMISSIONED UTILITIES UNDER PAVEMENT MAY BE GROUTED IN-PLACE.

4. ALL EXISTING INFRASTRUCTURE AND UTILITIES TO REMAIN IN AND AROUND THE CONSTRUCTION LIMITS SHALL BE MAINTAINED TO ITS EXISTING STATE WHEN THE CONTRACTOR BEGINS WORK. ANY DAMAGE TO THE INFRASTRUCTURE OR UTILITIES ONCE WORK BEGINS SHALL BE THE CONTRACTORS RESPONSIBILITY TO REPAIR.

5. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS ON ALL PRE CAST AND MANUFACTURED ITEMS TO THE OWNER'S ENGINEER FOR APPROVAL. FAILURE TO OBTAIN APPROVAL BEFORE FABRICATION AND/OR INSTALLATION MAY RESULT IN REMOVAL AND REPLACEMENT AT CONTRACTOR'S EXPENSE.

6. DURING THE CONSTRUCTION AND MAINTENANCE OF THIS PROJECT, ALL SAFETY REGULATIONS ARE TO BE ENFORCED. THE CONTRACTOR OR HIS REPRESENTATIVE SHALL BE RESPONSIBLE FOR THE CONTROL AND SAFETY OF THE TRAVELING PUBLIC AND THE SAFETY OF HIS PERSONNEL.

7. POTABLE WATER-SANITARY SEWER-RECLAIMED WATER SEPARATION NOTES:

A) VERTICAL CROSSINGS:
 WHEREVER IT IS PHYSICALLY POSSIBLE:
 SANITARY SEWER SYSTEMS REQUIRE A PREFERRED 10-FOOT HORIZONTAL SEPARATION DISTANCE (MINIMUM 6-FOOT) OUTSIDE TO OUTSIDE OF PIPE BETWEEN ANY POTABLE WATER MAIN IN PARALLEL INSTALLATIONS.

 STORM SEWER SYSTEMS REQUIRE A MINIMUM OF A 3-FOOT OUTSIDE TO OUTSIDE OF PIPE HORIZONTAL SEPARATION DISTANCE BETWEEN ANY POTABLE WATER MAIN IN PARALLEL INSTALLATIONS.

 RECLAIMED WATER MAINS REQUIRE A MINIMUM OF A 3-FOOT OUTSIDE TO OUTSIDE OF PIPE HORIZONTAL SEPARATION DISTANCE BETWEEN ANY POTABLE WATER MAIN AND/OR SANITARY SEWER SYSTEM PARALLEL INSTALLATIONS.

 WHEREVER EITHER ARE NOT PHYSICALLY POSSIBLE, THEN THE POTABLE WATER MAIN SHALL BE LAID AT THE MAXIMUM PHYSICAL HORIZONTAL SEPARATION DISTANCE POSSIBLE, AND EITHER LAID:
 1) IN A SEPARATE TRENCH;
 2) ON AN UNDISTURBED EARTH SHELF; AND CONFORMING TO THE MINIMUM VERTICAL CROSSINGS IN PARAGRAPH #1.

C) CONFLICTS:
 WHEREVER IT IS NOT POSSIBLE TO MAINTAIN THE MINIMUM STANDARDS IN A) AND B), THEN ALL PIPING MATERIAL SHALL BE DUCTILE IRON PIPE (DIP). ALL DIP SHALL BE CLASS 50 OR HIGHER. ADEQUATE PROTECTIVE MEASURES AGAINST CORROSION SHALL BE USED AS DETERMINED BY THE DESIGN AND SITE CONDITIONS. ADDITIONALLY, THE POTABLE WATER MAIN SHALL HAVE A FULL JOINT CENTERED ON THE CONFLICT AND MECHANICALLY RESTRAINED. AN ABSOLUTE MINIMUM VERTICAL SE