Building Inspection Division
Lakeland
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Date: 11/15/19
Permit Number: BLD19-06035

ELECTRICAL ABBREVIATIONS

1PH	SINGLE-PHASE
1P	1 POLE (2P,3P,4P, ETC.)
2/C	2 CONDUCTOR (3/C, 4/C, ETC.)
2W	2-WIRE (3W, 4W, ETC.)
3PH	THREE-PHASE
A	AMMETER, AMPERE, AMPS
AC	ALTERNATING CURRENT OR ARMORED CABLE
A/C	AIR CONDITIONING UNIT
ACT	ABOVE COUNTERTOP
ADDL	ADDITIONAL
ADJ	ADJACENT, ADJOINING
ADO	AUTOMATIC DOOR OPENER
A/E	ARCHITECT/ENGINEER
AF	AMPERE FRAME OR AMP FUSE
AFC	AVAILABLE FAULT CURRENT
AFCI	ARC FAULT CIRCUIT INTERRUPTER
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AHJ	AUTHORITY HAVING JURISDICTION
AHU	AIR HANDLING UNIT
AIC	AMPERE INTERRUPTING CAPACITY
AL. ALUM.	ALUMINUM
ALT	ALTERNATE
AMB	AMBIENT
AMP	AMPERE, AMPACITY, AMPLIFIER
ANSI	AMERICAN NATIONAL STANDARDS INSTITUTE
APPROX	APPROXIMATELY
ARCH	ARCHITECT, ARCHITECTURAL
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS
AT	AMPERE TRIP
ATS	AUTOMATIC TRANSFER SWITCH
AUTO	AUTOMATIC
AUX	AUXILIARY
A/V	AUDIO / VISUAL
AWG	AMERICAN WIRE GAUGE
BAT	BATTERY
BKR	BREAKER
BLDG	BUILDING
BMS	BUILDING MANAGEMENT SYSTEM
BYP	BYPASS
C	CONDUIT
CAP	CAPACITY
CAT	CATALOG
CATV	COMMUNITY ANTENNA TELEVISION
CCTV	CLOSED CIRCUIT TELEVISION
CD	CANDELA
CD	CONSTRUCTION DOCUMENTS
CFCI	CONTRACTOR FURNISHED, CONTRACTOR INSTALLED
CFOI	CONTRACTOR FURNISHED, OWNER INSTALLED
CKT	CIRCUIT
CKT BKR	CIRCUIT BREAKER
CLF	CURRENT LIMITING FUSE
CLG	CEILING
CMU	CONCRETE MASONRY UNIT
COAX	COAXIAL CABLE
COMB	COMBINATION
COMM	COMMUNICATION
CONC	CONCRETE
CONN	CONNECTION
CONST	CONSTRUCTION
CONT	CONTINUE, CONTINUATION
CONTR	CONTRACTOR
CPT	CONTROL POWER TRANSFORMER
CR	CRITICAL
CRI	COLOR RENDERING INDEX
CT	CURRENT TRANSFORMER
CTR	CENTER
CU	COPPER
DB	DECIBEL, DUCTBANK
DC	DIRECT CURRENT
DEG C	DEGREES CELSIUS
DEG F	DEGREES FAHRENHEIT
DEMO	DEMOLITION
DIA	DIAMETER
DIAG	DIAGRAM
DISC	DISCONNECT
DIST	DISTRIBUTION
DN	DOWN
DPDT	DOUBLE POLE, DOUBLE THROW
DPST	DOUBLE POLE, SINGLE THROW
DS	DISCONNECT SWITCH
DWG	DRAWING
EC	ELECTRICAL CONTRACTOR
EG	EQUIPMENT GROUND
EL	ELEVATION
ELEC	ELECTRIC, ELECTRICAL
EM	EMERGENCY
EMI	ELECTROMAGNETIC INTERFERENCE
EMT	ELECTRICAL METALLIC TUBING
E.O.	ELECTRICALLY OPERATED
EPMS	ELECTRICAL POWER MANAGEMENT SYSTEM
EPO	EMERGENCY POWER OFF
EQUIP.	EQUIPMENT
ETC.	ET CETERA
EWC	ELECTRIC WATER COOLER
EWH	ELECTRIC WATER HEATER
EXIST	EXISTING
EXP	EXPLOSION PROOF
EXT	EXTERIOR
FA	FIRE ALARM
FAAP	FIRE ALARM ANNUNCIATOR PANEL
FABP	FIRE ALARM BOOSTER POWER SUPPLY PANEL
FACP	FIRE ALARM CONTROL PANEL
FBO	FURNISHED BY OTHERS
FC	FOOTCANDLE
FCU	FAN COIL UNIT
FIXT	FIXTURE
FLA	FULL LOAD AMPS
FLEX	FLEXIBLE METALLIC CONDUIT
FLR	FLOOR
FLT	FLOODLIGHT
FLUOR	FLUORESCENT
FOC	FIBER OPTIC CAMERA
FT	FEET OR FOOT
FTL	FEED THRU LUGS
FTM	FUEL TANK MONITOR
FU	FUSE
FUT	FUTURE
G/GRD/GND	GROUND
GA	GAUGE
GAL	GALLON
GC	GENERAL CONTRACTOR
GCB	GENERATOR CIRCUIT BREAKER
GEC	GROUNDING ELECTRODE CONDUCTOR
GEN	GENERATOR
GFI	GROUND FAULT INTERRUPTER
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
GRC	GALVANIZED RIGID CONDUIT
GTB	GROUND TERMINAL BOX
HH	HANDHOLE
HID	HIGH INTENSITY DISCHARGE
HOA	HAND-OFF-AUTOMATIC
HP	HORSEPOWER
HRG	HIGH RESISTANCE GROUND
HV	HIGH VOLTAGE
HVAC	HEATING, VENTILATING AND AIR CONDITIONING
HZ	HORIZONTAL, HERTZ
ICCB	INSULATED CASE CIRCUIT BREAKER
I.D.	INDENTIFICATION
IESNA	ILLUMINATION ENGINEERING SOCIETY OF NORTH AMERICA

IG	ISOLATED GROUND
IMC	INTERMEDIATE METAL CONDUIT
IN.	INCHES
I/O	INPUT / OUTPUT
IR	INFRARED
J-BOX, JB	JUNCTION BOX
KA	KILOAMPERES
KV	KILOVOLT
KVA	KILOVOLT AMPERE
KV/H	KILOVOLT AMPERE PER HOUR
KVAR	KILOVOLT AMPERE REACTIVE
KW	KILOWATT
KWH	KILOWATT HOUR
LAN	LOCAL AREA NETWORK
LCP	LIGHTING CONTROL PANEL
LED	LIGHT EMITTING DIODE
LF	LINEAR FEET (FOOT)
LFMC	LIQUID-TIGHT, FLEXIBLE, METAL CONDUIT
LP	LIGHT POLE, LIGHTNING PROTECTION
LOC.	LOCATION
LRA	LOCKED ROTOR AMPS
LRP	LIGHTING RELAY PANEL
LSIG	LONG, SHORT, INSTANTANEOUS, GROUND
LS	LIFE SAFETY
LTG	LIGHTING
LTNG	LIGHTNING
LV	LOW VOLTAGE
MAX	MAXIMUM
MC	METAL-CLAD OR MECHANICAL CONTRACTOR
MCA	MINIMUM CIRCUIT AMPS
MCB	MAIN CIRCUIT BREAKER
MCC	MOTOR CONTROL CENTER
MCCB	MOLDED CASE CIRCUIT BREAKER
MDP	MAIN DISTRIBUTION PANEL
MECH	MECHANICAL
MFR	MANUFACTURER
MH	MANHOLE
MIN	MINIMUM
MISC	MISCELLANEOUS
MOCP	MAXIMUM OVERCURRENT PROTECTION
ML	MAIN LINE
MLO	MAIN LUGS ONLY
MSB	MAIN SWITCHBOARD
MT,MTD,MTG	MOUNT, MOUNTED, MOUNTING
MTR	MOTOR, MOTORIZED
MTS	MANUAL TRANSFER SWITCH
MV	MEDIUM VOLTAGE
MVA	MEGAVOLT-AMPERE
MW	MEGAWATT
N/A	NOT APPLICABLE
NB	NOTRTHBOUND
N.C.	NORMALLY CLOSED
NEC	NATIONAL ELECTRICAL CODE
NEMA	NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION
NEUT OR N	NEUTRAL
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NIC	NOT IN CONTRACT
NL	NIGHT LIGHT
NO.	NUMBER
N.O.	NORMALLY OPEN
NTS	NOT TO SCALE
OC	ON CENTER
OFCI	OWNER FURNISHED, CONTRACTOR INSTALLED
OFOI	OWNER FURNISHED, OWNER INSTALLED
OL	OVERLOAD
Ø	PHASE
P	POLE
PA	PUBLIC ADDRESS
PB	PULL BOX, OR PUSHBUTTON
PCB	POLYCHLORINTED BIPHENYL
PF	POWER FACTOR
PH	PHASE
PIV	POST INDICATOR VALVE
PLC	PROGRAMMABLE LOGIC CONTROLLER
PNL	PANEL
PP	POWER POLE
PR	PAIR
PRI	PRIMARY
PT	POTENTIAL TRANSFORMER
PVC	POLYVINYL CHLORIDE (PLASTIC)
PWR	POWER
QTY	QUANTITY
RCP	REFLECTED CEILING PLAN
RCPT, RECPT.	RECEPTACLE
RGS	RIGID GALVANIZED STEEL
RMS	ROOT MEAN SQUARE
RTU	ROOF TOP UNIT
SA	SURGE ARRESTER
SB	SOUTHBOUND
SCADA	SUPERVISORY CONTROL & DATA ACQUISITION
SCC	SHORT CIRCUIT CAPACITY
SCH	SCHEDULE
SEC	SECONDARY
SER.	SERVICE ENTRANCE RATED
SF	SQUARE FOOT (FEET)
SP	SPARE
SPD	SURGE PROTECTIVE DEVICE
SPEC	SPECIFICATION
SPST	SINGLE POLE, SINGLE THROW
SQ	SQUARE
S.S.	STAINLESS STEEL
STD	STANDARD
STP	SHIELD TWISTED PAIR
SW	SWITCH
SWBD	SWITCHBOARD
SWGR	SWITCHGEAR
SYM	SYMMETRICAL
SYS	SYSTEM
T/C	TIME CLOCK
TL	TWIST LOCK
TR	TAMPER RESISTANT, TIMER RELAY
TSP	TECHNICAL SPECIAL PROVISIONS
TTB	TELEPHONE TERMINAL BOARD
TV	TELEVISION
TYP	TYPICAL
UC	UNDER COUNTER
UG	UNDERGROUND
UL	UNDERWRITERS LABORATORY
UPS	UNINTERRUPTIBLE POWER SUPPLY
UON	UNLESS OTHERWISE NOTED
UTIL	UTILITY
V	VOLT, VOLTAGE
VA	VOLT AMPERE
VAC	VOLT ALTERNATING CURRENT
VAR	VOLT AMPERE REACTIVE
VFD	VARIABLE FREQUENCY DRIVE
W	WIRE, WATT
W/	WITH
WG	WIRE GUARD
WH	WATT HOUR, WATER HEATER
W/O	WITHOUT
WP	WEATHERPROOF
XFER	TRANSFER
XFMR	TRANSFORMER

NOTE:

NOT ALL SYMBOLS AND ABBREVIATIONS LISTED APPLY TO THIS PROJECT. REFER TO CONSTRUCTION DOCUMENTS FOR SCOPE OF WORK.

POWER PLAN SYMBOLS

X Y Z	NORMAL POWER DUPLEX RECEPTACLE WITH COVERPLATE, NEMA 5-20R, STANDARD MOUNTING HEIGHT 18" A.F.F. UNLESS OTHERWISE NOTED: X INDICATES CIRCUIT NUMBER, Y INDICATES NON-STANDARD MOUNTING HEIGHT, AND Z INDICATES THE FOLLOWING: AC =HVAC CONTROL CONNECTION ABOVE CEILING COPY =COPIER; MTD 42" A.F.F. COFF =COFFEE MAKER; MTD 44" A.F.F. CS =CHARTING STATION; MTD 72" A.F.F. DW =DISHWASHER GD =GARBAGE DISPOSAL ICE =ICE MAKERNE; MTD 44" A.F.F. M =MICROWAVE; MTD 44" A.F.F. MN =PATIENT MONITOR; MTD 72" A.F.F. P =PRINTER; MTD 44" A.F.F. PX =PYXIS DISPENSER REF =REFRIGERATOR; MTD 48" A.F.F. S =SURGE PROTECTED SHR =SHREDDER TL =TWIST LOCK T =TAMPER RESISTANT U =USB UC REF =UNDER COUNTER REFRIGERATOR V =TELEVISION; MTD 72" A.F.F. (U.O.N.) VM =VENDING MACHINE, MD 48" A.F.F. WP =WEATHER PROOF WC =WARMER CABINET X =XRAY XP =EXPLOSION PROOF
	DUPLEX RECEPTACLE MOUNTED BOTTOM 44" AFF UNLESS OTHERWISE NOTED. SAME NOTATION AS ABOVE.
	DUPLEX RECEPTACLE 18" AFF TOP HALF SWITCH OPERATED. SAME NOTATION AS ABOVE.
	GFCI RECEPTACLE 18" AFF, INSTALLED IN READILY ACCESSIBLE LOCATION, SAME NOTATION AS ABOVE.
	GFCI RECEPTACTLE INSTALLED IN READILY ACCESSIBLE LOCATION, MOUNTED BOTTOM 44" AFF UNLESS OTHERWISE NOTED. SAME NOTATION AS ABOVE.
	QUAD GFCI RECEPTACLE. SAME NOTATION AS ABOVE.
	QUAD GFCI RECEPTACLE ABOVE COUNTER, MOUNTED BOTTOM 44" AFF. SAME NOTATION AS ABOVE.
	QUAD (DOUBLE DUPLEX) RECEPTACLE , SAME NOTATION AS ABOVE.
	QUAD EMERGENCY (DOUBLE DUPLEX) RECEPTACLE, SAME NOTATION AS ABOVE.
	QUAD (DOUBLE DUPLEX) RECEPTACLE ABOVE COUNTER, MOUNTED BOTTOM 44" AFF. SAME NOTATION AS ABOVE.
	SIMPLEX RECEPTACLE, SAME NOTATION AS ABOVE.
	SPECIAL RECEPTACLE - NEMA CONFIGURATION AS NOTED WALL MOUNTED AT HEIGHT AS NOTED, SAME NOTATION AS ABOVE.
	FLOOR BOX WITH FLUSH MOUNTED DEVICE
	QUAD FLOOR BOX WITH FLUSH MOUNTED DEVICE
	COMBINATION ROOF MOUNTED LIGHT AND WEATHERPROOF RECEPTACLE
	FLOOR BOX WITH FLUSH MOUNTED DEVICE
	CEILING MOUNTED DUPLEX RECEPTACLE
J	JUNCTION BOX / EQUIPMENT CONNECTION
M	1-PHASE MOTOR CONNECTION
M	3-PHASE MOTOR CONNECTION
	MANUAL MOTOR STARTER, TOGGLE TYPE, WITH THERMAL OVERLOAD DEVICE
	MAGNETIC STARTER
	NON-FUSED DISCONNECT SWITCH
	FUSED DISCONNECT SWITCH, FUSE SIZE AS SHOWN
	COMBINATION MOTOR STARTER/DISCONNECT
	PUSH BUTTON, TYPE AS INDICATED OR NOTED
	PANELBOARD/CONTROL PANEL AS NOTED. (SIZED TO SCALE)
	POWER TRANSFORMER (SIZED TO SCALE)
	GROUND ROD
	GROUND BONDING POINT TO STEEL STRUCTURE, REBAR, PIPE, ETC.
	GROUNDING CONNECTION (TYPE AS SHOWN OR NOTED)
	BARE COPPER GROUND CONDUCTOR, SIZE AS SHOWN
	GROUND BAR
MH X	MANHOLE: X INDICATES TYPE AS FOLLOWS P = POWER MANHOLE T = TELECOMMUNICATIONS MANHOLE

DATA/SYSTEMS SYMBOLS

	REFER TO SHEET T0-0-01 FOR DATA/SYSTEMS LEGEND.

GENERAL ELECTRICAL NOTES

1. ALL RECEPTACLES AND DEVICES WITH (2) #12, (1) #12 GND IN 3/4" C, UON.
2. PROVIDE (2) #12, (1) #12 GND AND #12 SWITCHLEGS AS REQUIRED. IN 3/4" C FOR ALL NEW BUILDING LIGHTING, UON.
3. PROVIDE AN EQUIPMENT GROUNDING CONDUCTOR IN ALL FEEDER AND BRANCH CIRCUIT RACEWAYS.
4. ALL 120V, 20A CIRCUIT HOMERUNS OVER 50FT. SHALL BE #10 CU MINIMUM, UON.
5. ALL 120V, 20A CIRCUIT HOMERUNS OVER 150FT. SHALL BE #8 CU MINIMUM, UON.
6. ALL 208V OR 240V, 20A CIRCUIT HOMERUNS OVER 150FT. SHALL BE #10 CU. MINIMUM, UON.
7. ALL 208V OR 240V, 20A CIRCUIT HOMERUNS OVER 300FT. SHALL BE #8 CU MINIMUM, UON.
8. PROVIDE PULLSTRINGS IN ALL EMPTY CONDUIT AND RACEWAYS WITH LABELING AND CAPS AT EACH END.
9. LOCATE EXISTING UTILITIES AND PROTECT THEM FROM DAMAGE.
10. UNDERGROUND CONDUIT SHALL BE PVC SCH. 40, UON. UNDERGROUND CONDUIT SHALL TRANSITION TO RGS CONDUIT WITH PVC TO RGS CONDUIT FITTINGS. EXTERIOR CONDUIT SHALL BE RGS ABOVE GRADE THROUGH AND INCLUDING THE FIRST 90 DEGREE FITTING UNDERGROUND UON.
11. INTERIOR CONDUIT WITH A TRADE SIZE OF LESS THAN 2" SHALL BE EMT. CONDUIT WITH A TRADE SIZE OF 2" AND GREATER SHALL BE RGS.
12. UNDERGROUND CONDUITS SHALL BE INSTALLED A MINIMUM OF 36" BELOW GRADE.
13. EXPOSED EXTERIOR CONDUIT SHALL BE RGS THROUGH AND INCLUDING THE FIRST 90° BEND INSTALLED UNDERGROUND. TRANSITIONS BETWEEN RGS AND PVC CONDUIT SHALL BE MADE WITH A RGS TO PVC CONDUIT FITTING.
14. PLASTIC END CAPS SHALL BE INSTALLED ON ENDS OF UNISTRUT.
15. ADJUST THE LOCATIONS OF THE SPDS SUCH THAT THE MAXIMUM SPD BRAIDED/TWISTED LEADS LENGTH DO NOT EXCEED 24 INCHES AND HAVE NO SHARP TURNS.
16. FUNCTIONAL TEST OF THE LIGHTING CONTROL SYSTEM SHALL BE PERFORMED PER FBC ENERGY CONSERVATION SECTION 408.3. PRIOR TO PASSING FINAL INSPECTION, THE DESIGN PROFESSIONAL SHALL PROVIDE EVIDENCE THAT THE LIGHTING CONTROL SYSTEMS HAVE BEEN TESTED TO ENSURE THAT CONTROL HARDWARE AND SOFTWARE ARE CALIBRATED, ADJUSTED, PROGRAMMED AND IN PROPER WORKING CONDITION IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AND MANUFACTURES INSTRUCTIONS. FUNCTIONAL TESTING SHALL BE IN ACCORDANCE WITH SECTIONS C408.3.1.1 AND C408.3.1.2 FOR APPLICATION CONTROL TYPE.
17. CONTRACTOR SHALL PROVIDE RECORD DRAWINGS OF THE ACTUAL INSTALLATION, OPERATIONS MANUALS, AND MAINTENANCE MANUALS TO THE BUILDING OWNER WITHIN 30 DAYS AFTER THE DATE OF SYSTEM ACCEPTANCE AS REQUIRED BY FBC ENERGY CONSERVATION SECTION C405.6.4 AND ITS SUBSECTIONS.

LIGHTING PLAN SYMBOLS

x $ Y	WALL SWITCH WITH COVERPLATE, STANDARD MOUNTING HEIGHT 48" A.F.F.: x INDICATES SWITCH AND LUMINAIRE GROUPS, Y INDICATES THE FOLLOWING: BLANK =SINGLE POLE 2 =DOUBLE POLE (2-WAY) 3 =THREE POLE (3-WAY) 3D =3-WAY DIMMING 4 =FOUR POLE (4-WAY) D =DIMMER SWITCH LV =LOW VOLTAGE MOMENTARY SWITCH ML =MASTER OVERRIDE SWITCH OS =OCCUPANCY SENSOR W/ 0-10 V DIMMING T =TIMER SWITCH WP =WEATHERPROOF SWITCH VS =VACANCY SENSOR
$WS	WIRELESS WALL MOUNTED LIGHT SWITCH WITH ON/OFF AND RAISE/LOWER 0-10V DIMMING.
#-#	LIGHT SWITCH CONTROL ZONE TAG.
OS	WIRELESS CEILING MOUNTED OCCUPANCY SENSOR. SENSOR SHALL NOT TURN FIXTURES ON TO MORE THAN 50% POWER PER FBC ENERGY CONSERVATION SECTION C405.2. LISTED EXCEPTION AREAS SHALL BE FULL AUTOMATIC-ON.
DS	CEILING MOUNTED DAYLIGHT SENSOR WITH CONTINUOUS DIMMING AND FULL AUTOMATIC-ON OCCUPANCY SENSOR.
PC	PHOTOCELL
PP	POWER PACK - LOW VOLTAGE LIGHTING CONTROL SYSTEM POWER SUPPLY AND RELAY, LOCATED ABOVE ACCESSIBLE CEILING.
XX # x,y	2X4 TROFFER LIGHTING FIXTURE - "#" INDICATES CIRCUIT NUMBER, "XX" INDICATES FIXTURE TYPE (SEE FIXTURE SCHEDULE ON DRAWING E0-0-1), & "x,y" INDICATES SWITCH CONTROL. OTHER TYPICAL FIXTURES AND DESCRIPTIONS AS FOLLOWS: UTILITY LIGHT FIXTURE 2X2 TROFFER LIGHT DOWNLIGHT EXTERIOR WALL PACK SITE LIGHTING FIXTURE. (#) INDICATES POLE NUMBER.
XE N/L	2X4 TROFFER EMERGENCY LIGHTING FIXTURE. NL INDICATES NIGHT LIGHT FIXTURE. LETTER INDICATES FIXTURE TYPE. SEE LIGHTING FIXTURE SCHEDULE. CONNECT TO LINE SIDE (UNSWITCHED CONDUCTOR) OF EMERGENCY GENERATOR CIRCUIT (SAME NOTATION AS ABOVE). TYPICAL SYMBOLS AS FOLLOWS: UTILITY LIGHT FIXTURE 2X2 TROFFER LIGHT DOWNLIGHT
	EMERGENCY BATTERY PACK (SEE FIXTURE SCHEDULE)
X #	CEILING MOUNTED, EXIT SIGN - "X" INDICATES FIXTURE TYPE (SEE FIXTURE SCHEDULE). DIRECTIONAL ARROWS AS INDICATED ON PLANS, SHADED SIDES ARE ILLUMINATED. "#" INDICATES CIRCUIT NUMBER. CONNECT TO LINE SIDE (UNSWITCHED CONDUCTOR) OF CIRCUIT. TYPICAL TYPES AND DESCRIPTIONS AS FOLLOWS: CEILING MOUNTED, DOUBLE FACED EXIT SIGN WALL MOUNTED, SINGLE FACED EXIT SIGN WALL MOUNTED, DOUBLE FACED EXIT SIGN

LIGHTING POWER DENSITY CALCULATION
(BUILDING AREA METHOD FBC ENERGY CONSERVATION 405.4.2)

LEVEL	AREA (FT^2)	TOTAL LIGHTING LOAD (W)	LPD (W/FT^2)
LEVEL 1	63,720	34,269	0.54
LEVEL 2	64,743	34,616	0.53
LEVEL 3	64,743	34,512	0.53
TOTAL	193,206	103,397	0.54

NOTE: THE LPD ALLOWED PER FBC ENERGY CONSERVATION 405.4.2 FOR OFFICES IS 0.8 W/FT^2

RISER DIAGRAM SYMBOLS

XXX	GDP. AMP RATING ETC. AS INDICATED OR SPECIFIED.
XXX XXX	MAIN SWITCHBOARD. AMP RATING, ETC AS INDICATED OR SPECIFED.
XXX	SWITCHBOARD. AMP RATING, ETC AS INDICATED OR SPECIFED.
XXX XXX	SWITCHBOARD. AMP RATING, ETC AS INDICATED OR SPECIFED.
PNL XXX	PANELBOARD.
XXX XXX	TRANSFER SWITCH AMP RATING, NUMBER OF POLES, ETC. AS INDICATED OR SPECIFIED.
XXX XXX	LARGE TRANSFER SWITCH AMP RATING, NUMBER OF POLES, ETC. AS INDICATED OR SPECIFIED.
-P XXX -VE	CEILING MOUNTED TRANSFORMER KVA, PRI & SEC VOLTAGE, K-RATING, ETC. AS INDICATED OR SPECIFIED.
-P XXX -VE	PAD MOUNTED TRANSFORMER KVA, PRI & SEC VOLTAGE, K-RATING, ETC. AS INDICATED OR SPECIFIED.
	GROUNDING BAR
	EARTH GROUND

LIGHTING FIXTURE SCHEDULE

TYPE	DESCRIPTION	MANUFACTURER	CATALOG NUMBER	Voltage	CRI/CCT	WATTS	MOUNTING	DIMMING
A	RECESSED 2X2 DIRECT/INDIRECT TROFFER	ACUITY	2AVL2-40LHE-MDR-LP835	277 V	80/3500K	41 VA	RECESSED	0-10V
C2	CERCHIO II™ Round Pendant Fixture Direct/Indirect	Betacalco™	AE1-BH3-P1-BF20-BG20-L2	277 V	80/3500K	48 VA	PENDANT	0-10V
C4	CERCHIO II™ Round Pendant Fixture Direct/Indirect	Betacalco™	AE3-BH3-P1-BF20-BG20-L3	277 V	80/3500K	105 VA	PENDANT	0-10V
D	6" DOWNLIGHT	GOTHAM	EVO 35/15 6AR MWD 277 GZ10	277 V	85/3500K	19 VA	RECESSED	0-10V
D1	6" WALL WASHER	GOTHAM	EVO WW 35/10 6AR 277 GZ10	277 V	80/3500K	12 VA	RECESSED	0-10V
P	ELEVATOR PIT LIGHT	LITHONIA	XVML L48 5000LM MVOLT 40K 80CRI	277 V	80/4000K	49 VA	SURFACE	
P1	Suspended Mount Direct/Indirect	Mark Architectural Lighting	S2LID-XXX-10-MSL5-80CRI-35K-600LMF	277 V	80/3500K	23 VA	SUSPENDED	0-10V
P2	Suspended Mount Direct/Indirect	Mark Architectural Lighting	S2LID-XXX-MSL8-80CRI-35K-600LMF	277 V	80/3500K	45 VA	SUSPENDED	0-10V
P3	Suspended Mount Direct/Indirect	Mark Architectural Lighting	S2LID-XXX-12-MSL6-80CRI-35K-600LMF	277 V	80/3500K	30 VA	SUSPENDED	0-10V
P4	Wall Mounted Direct/Indirect	Mark Architectural Lighting	S2LWID-XXX-MSL8-80CRI-35K-600LMF	277 V	80/3500K	45 VA	WALL MOUNT	0-10V
S2	Double Head Site Light	CREE	ARE-EDG-5M-AA-08-E-UH-BZ-525	480 V	80/4000K	133 VA	30' CONCRETE POLE	
S2H	Double Head Site Light	CREE	ARE-EDG-3M-AA-08-E-UH-BZ-525	480 V	80/4000K	133 VA	30' CONCRETE POLE	
S4	4-Head Site Light	CREE	ARE-EDG-5M-AA-08-E-UH-BZ-525	480 V	80/4000K	133 VA	30' CONCRETE POLE	
SB	SITE BOLLARD	CREE	PWX-EDG-5M-P4-02-F-27-BZ-525	277 V	80/4000K	34 VA	42" LED BOLLARD	
U	4' STRIP LIGHT	LITHONIA	CLX L48 5000LM SEF L/LENS MVOLT GZ10 40K 80CRI	277 V	80/4000K	35 VA	PENDANT	0-10V
U1	2' STRIP LIGHT	LITHONIA	CLX L24 2500LM SEF L/LENS MVOLT GZ10 40K 80CRI		80/4000K	18 VA	PENDANT	0-10V
W5	Perimeter Direct Wall Wash	GAMMALUX	GPRG6B-1SL358T-277-DVR-4N-XXX/XX/XXX	277 V	80/3500K	24 VA	RECESSED COVE	0-10V
W14	Perimeter Direct Wall Wash	GAMMALUX	GPRG6B-1SL358T-277-DVR-14N-XXX/XX/XXX	277 V	80/3500K	84 VA	RECESSED COVE	0-10V
W21	Perimeter Direct Wall Wash	GAMMALUX	GPRG6B-1SL358T-277-DVR-15N-XXX/XX/XXX	277 V	80/3500K	126 VA	RECESSED COVE	0-10V
XB	EXIT SIGN	ACUITY	EDG	277 V		2 VA	CEILING MOUNTED	
XF	EXIT SIGN	ACUITY	EDG	277 V		2 VA	CEILING MOUNTED	

NOTES:
1. ALL LIGHTING AND LIGHTING CONTROLS SHALL BE OWNER FURNISHED AND CONTRACTOR INSTALLED WITH THE EXCEPTION OF SITE CONCRETE POLES WHICH SHALL BE CONTRACTOR FURNISHED AND INSTALLED.
2. ALL INTERIOR LIGHTING FIXTURES SHALL BE COMPATIBLE (OR MADE COMPATIBLE VIA POWER PACK) WITH THE nLIGHT AIR CONTROL SYSTEM WITH THE EXCEPTION OF THE TYPES P, XB, AND XF.

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

http://www.aecom.com

REGISTRATION

HENRYK B. JUSZCZYK, LICENSE NO. 58082, STATE OF FLORIDA, PROFESSIONAL ENGINEER

HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Henryk B Juszczyk
2019.09.30 17:59:47
-04'00'

ISSUE/REVISION

I/R	DATE	DESCRIPTION
1	SEP 30, 2019	100% CONSTRUCTION DOCUMENTS
0	AUG 23, 2019	CONSTRUCTION DOCUMENTS
	JUNE 7, 2019	35% DESIGN COMPLETION

PROJECT NUMBER

60601397

SHEET TITLE

ELECTRICAL LEGEND, SYMBOLS AND ABBREVIATIONS

SHEET NUMBER

E0-0-01

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

Printed on ___% Post-Consumer Recycled Content Paper
©2016 AECOM Corporation