Designer: Designer Checker: Checker Approved: Approver ARCH E1 30"x42"

Project Management Initials:

Panel: MDP-HF

Location: TELE 1-112
Supply From: MSB2
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: REFER TO FAULT CURRENT SCHEDULE
Mains Type: MCB
Mains Rating: 1600 A
MCB Rating: 1600 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				33.48	7854 VA								2
3	PANEL 1LF1 (VIA 112.5 KVA XFMR)	175 A	3			33480 VA	3989 VA			3	400 A	PANEL 1HF1	4
5								34200 VA	2.49				6
7				18.54	78535 VA								8
9	PANEL 1LF2 (VIA 45 KVA XFMR)	70 A	3			16920 VA	78134 VA			3	400 A	PANEL 1HF2	10
11								18180 VA	78.13				12
13				0.00	7715 VA								14
15	PANEL 1LF3 (VIA 75 KVA XFMR)	110 A	3			0 VA	3579 VA			3	400 A	PANEL 2HF1	16
17								0 VA	1.89				18
19				0.00	78803 VA								20
21	PANEL 2LF1 (VIA 112.5 KVA XFMR)	175 A	3			0 VA	78000 VA			3	400 A	PANEL 2HF2	22
23								0 VA	78.00				24
25				1.08	7597 VA								26
27	PANEL 2LF2 (VIA 45 KVA XFMR)	70 A	3			0 VA	3735 VA			3	400 A	PANEL 3HF1	28
29								0 VA	2.49				30
31				0.00	85881 VA								32
33	PANEL 2LF3 (VIA 75 KVA XFMR)	110 A	3			0 VA	85480 VA			3	400 A	PANEL 3HF2	34
35								0 VA	85.48				36
37				32.40	3060 VA								38
39	PANEL 3LF1 (VIA 112.5 KVA XFMR)	175 A	3			32400 VA	3420 VA			3	70 A	PANEL 3LF2 (VIA 45 KVA XFMR)	40
41								32400 VA	1.76				42
43				11.82	0 VA					--	--	SPACE	44
45	PANEL 3LF3 (VIA 75 KVA XFMR)	110 A	3			10160 VA	0 VA			--	--	SPACE	46
47								10380 VA	0.00	--	--	SPACE	48
49													50
51													52
53													54
				352.2 kVA		335.1 kVA		331.1 kVA					
				1273.6 A		1211.9 A		1195.2 A					

TOTAL CONNECTED LOAD: 1018280 VA

Panel: MDP-HG

Location: FREIGHT ELEV. NO. 6 -
Supply From: MSB2
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: REFER TO FAULT CURRENT SCHEDULE
Mains Type: MCB
Mains Rating: 1600 A
MCB Rating: 1600 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				34.56	11869 VA								2
3	PANEL 1LG1 (VIA 112.5 KVA XFMR)	175 A	3			34560 VA	4912 VA			3	400 A	PANEL 1HG1	4
5								34560 VA	1.38				6
7				16.38	62481 VA								8
9	PANEL 1LG2 (VIA 45 KVA XFMR)	70 A	3			14940 VA	62080 VA			3	400 A	PANEL 1HG2	10
11								13680 VA	62.08				12
13				10.09	7831 VA								14
15	PANEL 1LG3 (VIA 75 KVA XFMR)	110 A	3			8985 VA	6511 VA			3	400 A	PANEL 2HG1	16
17								7140 VA	0.84				18
19				39.96	71347 VA								20
21	PANEL 2LG1 (VIA 112.5 KVA XFMR)	175 A	3			39960 VA	71347 VA			3	400 A	PANEL 2HG2	22
23								39960 VA	71.75				24
25				17.46	7749 VA								26
27	PANEL 2LG2 (VIA 45 KVA XFMR)	70 A	3			17100 VA	6552 VA			3	400 A	PANEL 3HG1	28
29								17280 VA	0.21				30
31				45.92	76223 VA								32
33	PANEL 2LG3 (VIA 75 KVA XFMR)	110 A	3			44500 VA	75822 VA			3	400 A	PANEL 3HG2	34
35								45180 VA	75.82				36
37				0.00	4080 VA								38
39	PANEL 3LG1 (VIA 112.5 KVA XFMR)	175 A	3			0 VA	4080 VA			3	110 A	PANEL 3LG3 (VIA 75 KVA XFMR)	40
41								0 VA	5.04				42
43				16.74	0 VA					--	--	SPACE	44
45	PANEL 3LG2 (VIA 45 KVA XFMR)	70 A	3			16380 VA	0 VA			--	--	SPACE	46
47								16380 VA	0.00	--	--	SPACE	48
49													50
51													52
53													54
				402.6 kVA		387.9 kVA		371.5 kVA					
				1462.4 A		1409.3 A		1341.2 A					

TOTAL CONNECTED LOAD: 1161930 VA

Switchboard: MSB2

Location: MECHANICAL 1-136
Supply From:
Mounting:
Enclosure:

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: REFER TO FAULT CURRENT SCHEDULE
Mains Type: MCB
Mains Rating:
MCB Rating: 4000 A

Notes:

CKT	Circuit Description	Rating	Poles	Load	Remarks
1	MDP-HF	1600 A	3	1018280 VA	
2	MDP-HG	1600 A	3	1161930 VA	
3					
4					
5					
6					
7					
8					
9					
10					
				2176836 VA	VA
				2618 A	Amps

Panel: MDP LS1D

Location: ELEV NO. 5 -
Supply From: EXISTING PANEL EM LOAD SUMMARY
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: REFER TO FAULT CURRENT SCHEDULE
Mains Type: MLO
Mains Rating: 125 A
MCB Rating: 125 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				6.20 kVA	3.99 kVA								2
3	PANEL LSH 1D	60 A	3			4.75 kVA	2.61 kVA			3	60 A	PANEL LSH 2D	4
5								1.84 kVA	0.72 kVA				6
7				3.91 kVA	0.00 kVA					--	--	SPACE	8
9	PANEL LSH 3D	60 A	3			2.57 kVA	0.00 kVA			--	--	SPACE	10
11								0.72 kVA	0.00 kVA	--	--	SPACE	12
13	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	14
15	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	16
17	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	18
19	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	20
21	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	22
23	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	24
25	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	26
27	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	28
29	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	30
31	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	32
33	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	34
35	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	36
37	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	38
39	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	40
41	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	42
				14.1 kVA		9.9 kVA		3.3 kVA					
				54.5 A		39.4 A		11.8 A					

TOTAL CONNECTED LOAD: 27197 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
Lighting	16867 VA	125.00%	21084 VA		
Lighting - Dwelling Unit	196 VA	100.00%	196 VA	**Total Conn. Load:**	27197 VA
Other	1394 VA	100.00%	1394 VA	**Total Est. Demand:**	31392 VA
Power	4520 VA	100.00%	4520 VA	**Total Conn.:**	33 A
Receptacle	4500 VA	100.00%	4500 VA	**Total Est. Demand:**	38 A

Switchboard: MCC2

Location:
Supply From: EXISTING MSB-1 LOAD SUMMARY
Mounting:
Enclosure:

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: REFER TO FAULT CURRENT SCHEDULE
Mains Type: MCB
Mains Rating:
MCB Rating: 800 A

Notes:

CKT	Circuit Description	Rating	Poles	Load	Remarks
1	CH-3	800 A	3	322577 VA	
2	CHWSP-3	100 A	3	33255 VA	
3	CHWPP-3	60 A	3	17459 VA	
4	CT-3	100 A	3	34918 VA	
5	CWP-3	150 A	3	54040 VA	
6	CHWSP-4	100 A	3	33255 VA	
7	SPACE	--	--	0 VA	--
8	SPACE	--	--	0 VA	--
9	SPACE	--	--	0 VA	--
10	SPACE	--	--	0 VA	--
				495505 VA	VA
				596 A	Amps

Panel: EXISTING MSB-1 LOAD SUMMARY

Location:
Supply From:
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating:
Mains Type: MCB
Mains Rating: 4000 A
MCB Rating: 4000 A

Notes: PANEL IS EXISTING TO REMAIN AND SHOWN FOR LOAD SUMMARY PURPOSES TO INDICATE THE ADDED LOAD FROM NEW PANEL(S) ADDED DURING THE EXPANSION

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				433.33	48148 VA								2
3	PEAK WATTS DEMAND OVER PAST 12 MONTHS	4000 A	3			433333 VA	48148 VA			3	0 A	POWER FACTOR ADDED TO PEAK WATTS DEMAND OVER LAST 12 MONTHS	4
5								433333 VA	48.15				6
7				120.33	165168 VA								8
9	25% ADDED TO PEAK VA OVER LAST 12 MONTHS	0 A	3			120333 VA	165168 VA			3	1200 A	(NEW) MCC2	10
11								120333 VA	165.17				12
13													14
15													16
17													18
				740.6 kVA		740.6 kVA		740.6 kVA					
				2673.7 A		2673.7 A		2673.7 A					

TOTAL CONNECTED LOAD: 2221829 VA

Panel: EXISTING PANEL EM LOAD SUMMARY

Location:
Supply From:
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating:
Mains Type: MCB
Mains Rating: 700 A
MCB Rating: 700 A

Notes: PANEL IS EXISTING TO REMAIN AND SHOWN FOR LOAD SUMMARY PURPOSES TO INDICATE THE ADDED LOAD FROM NEW PANEL(S) ADDED DURING THE EXPANSION

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				37.00	31667 VA								2
3	(E) PANEL LSH	225 A	3			37000 VA	31667 VA			3	225 A	(E) PANEL MDPLS1A	4
5								37000 VA	31.67				6
7				29.00	46667 VA								8
9	(E) PANEL MDLS1C	20 A	3			29000 VA	46667 VA			3	20 A	(E) PANEL MDPLS1B	10
11								29000 VA	46.67				12
13				14.08									14
15	(NEW) PANEL MDPLS1D	125 A	3			9904 VA							16
17								3275 VA					18
				158.2 kVA		154.0 kVA		147.6 kVA					
				574.6 A		559.5 A		532.9 A					

TOTAL CONNECTED LOAD: 459770 VA

PANEL KEY	
MDPHF	**MDPHG**
MDPLS1D	**MSB2**
MSB-1	**MCC2**
	EM

This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that modifies this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

Building Inspection Division
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Lakeland
Date: 11/15/19
Permit Number: BLD19-06035

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

http://www.aecom.com

REGISTRATION

HENRYK B. JUSZCZYK
LICENSE NO. 58082
STATE OF FLORIDA
PROFESSIONAL ENGINEER

HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Henryk B Juszczyk
2019.10.25 15:54:26
-04'00'

ISSUE/REVISION

I/R	DATE	DESCRIPTION
2	OCT 25,2019	BUILDING DEPARTMENT COMMENTS
1	SEP 30, 2019	100% CONSTRUCTION DOCUMENTS
0	AUG 23, 2019	CONSTRUCTION DOCUMENTS

PROJECT NUMBER

60601397

SHEET TITLE

ELECTRICAL PANEL SCHEDULES

SHEET NUMBER

E5-1-01

Printed on ___% Post-Consumer Recycled Content Paper

©2016 AECOM Corporation