E5-1-02-ELECTRICAL PANEL SCHEDULES
Designer: Designer Checker: Checker Approved: Approved ARCH E1 30"x42"
Project Management Initials:

Building Inspection Division
Lakeland
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Date: 11/15/19
Permit Number: BLD19-06035

Panel: LSH 1D

Location: ELEV NO. 5 -
Supply From: MDP LS1D
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: 2
Mains Type: MLO
Mains Rating: 125 A
MCB Rating: 125 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1	LIGHTING	20 A	1	2.12 kVA	1.09 kVA					1	20 A	LIGHTING	2
3	LIGHTING	20 A	1			1.19 kVA	1.48 kVA			1	20 A	LIGHTING	4
5	OTHER	20 A	1					8.35 kVA	8.71 kVA	1	20 A	LOUVERS - STAIR 7	6
7	ELEVATOR 5 PIT AND CONTROL ROOM LIGHTING	20 A	1	0.13 kVA	0.12 kVA					1	20 A	SERVICE ELEV 8 ELEVATOR PIT & CONTROL RM LIGHTING	8
9	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	10
11	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	12
13	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	14
15	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	16
17	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	18
19	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	20
21	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	22
23	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	24
25	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	26
27	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	28
29	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	30
31	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	32
33	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	34
35	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	36
37	SPACE	--	--	0.00 kVA	2.80 kVA								38
39	SPACE	--	--			0.00 kVA	2.12 kVA			3	20 A	PANEL LSL 1D (VIA 9KVA XFMR)	40
41	SPACE	--	--					0.00 kVA	1.22 kVA				42
				6.2 kVA		4.7 kVA		1.8 kVA					
				24.0 A		18.8 A		6.6 A					

TOTAL CONNECTED LOAD: 12761 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
Lighting	5707 VA	125.00%	7133 VA		
Lighting - Dwelling Unit	196 VA	100.00%	196 VA	**Total Conn. Load:**	12761 VA
Other	846 VA	100.00%	846 VA	**Total Est. Demand:**	14173 VA
Power	4520 VA	100.00%	4520 VA	**Total Conn.:**	15 A
Receptacle	1620 VA	100.00%	1620 VA	**Total Est. Demand:**	17 A

Panel: LSL 1D

Location: ELEV NO. 5 -
Supply From: T9
Mounting: Surface
Enclosure: 1

Volts: 208/120 Wye
Phases: 3
Wires: 4

A.I.C. Rating: 2
Mains Type: MLO
Mains Rating: 30 A
MCB Rating: 30 A

Notes: Provide 30 Amp, 3 Pole branch mounte main circuit breaker.

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1	NACC	20 A	1	0.70 kVA	0.70 kVA					1	20 A	NACC	2
3	NACC	20 A	1			0.70 kVA	0.70 kVA			1	20 A	NACC	4
5	DRY PIPE FIRE SPRINKLER AIR COMPRESSOR	20 A	1					0.18 kVA	0.36 kVA	1	20 A	IDF ROOM WALL MOUNTED QUAD RECEPTACLE	6
7	IDF ROOM WALL MOUNTED QUAD RECEPTACLE	20 A	1	0.36 kVA	0.36 kVA					1	20 A	IDF ROOM CABLE TRAY MOUNTED QUAD RECEPTACLE	8
9	IDF ROOM CABLE TRAY MOUNTED QUAD RECEPTACLE	20 A	1			0.36 kVA	0.18 kVA			1	20 A	POWER	10
11	POWER	20 A	1					0.50 kVA	0.18 kVA	1	20 A	POWER	12
13	POWER	20 A	1	0.50 kVA	0.18 kVA					1	20 A	POWER	14
15	POWER	20 A	1			0.18 kVA	0.00 kVA			1	20 A	SPARE	16
17	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	18
19	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	20
21	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	22
23	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	24
25	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	26
27	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	28
29	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	30
31	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	32
33	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	34
35	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	36
37	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	38
39	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	40
41	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	42
				2.8 kVA		2.1 kVA		1.2 kVA					
				24.5 A		18.8 A		10.2 A					

TOTAL CONNECTED LOAD: 6140 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
Power	4520 VA	100.00%	4520 VA		
Receptacle	1620 VA	100.00%	1620 VA	**Total Conn. Load:**	6140 VA
				Total Est. Demand:	6140 VA
				Total Conn.:	17 A
				Total Est. Demand:	17 A

PANEL KEY	
LSH1D	**LSL1D**

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

http://www.aecom.com

REGISTRATION

HENRYK B. JUSZCZYK
LICENSE
NO. 58082
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Henryk B Juszczyk
2019.09.30
18:19:45 -04'00'

ISSUE/REVISION

I/R	DATE	DESCRIPTION
1	SEP 30, 2019	100% CONSTRUCTION DOCUMENTS
0	AUG 23, 2019	CONSTRUCTION DOCUMENTS

PROJECT NUMBER

60601397

SHEET TITLE

ELECTRICAL PANEL SCHEDULES

SHEET NUMBER

E5-1-02

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

Last Plotted: 9/30/2019 5:04:51 PM
Filename: BM.360.//60601397-Publix HQ/60601397_Publix HQ_ELECT_R2019.rvt

Printed on ___% Post-Consumer Recycled Content Paper

©2016 AECOM Corporation