Panel: LSH 2D

Location: ELEC 2-136
Supply From: MDP LS1D
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: 2
Mains Type: MLO
Mains Rating: 125 A
MCB Rating: 125 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1	LIGHTING	20 A	1	2.20 kVA	1.09 kVA					1	20 A	LIGHTING	2
3	LIGHTING	20 A	1			1.23 kVA	1.38 kVA			1	20 A	LIGHTING	4
5	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	6
7	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	8
9	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	10
11	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	12
13	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	14
15	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	16
17	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	18
19	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	20
21	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	22
23	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	24
25	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	26
27	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	28
29	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	30
31	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	32
33	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	34
35	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	36
37	PANEL LSL 2D (VIA 9KVA XFMR)	20 A	3	0.72 kVA	0.00 kVA					--	--	SPACE	38
39						0.00 kVA	0.00 kVA			--	--	SPACE	40
41								0.72 kVA	0.00 kVA	--	--	SPACE	42
				4.0 kVA		2.6 kVA		0.7 kVA					
				15.5 A		10.5 A		2.6 A					

TOTAL CONNECTED LOAD: 7296 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
Lighting	5597 VA	125.00%	6997 VA		
Other	318 VA	100.00%	318 VA	**Total Conn. Load:**	7296 VA
Power	0 VA	0.00%	0 VA	**Total Est. Demand:**	8692 VA
Receptacle	1440 VA	100.00%	1440 VA	**Total Conn.:**	9 A
				Total Est. Demand:	10 A

Panel: LSL 2D

Location: ELEC 2-136
Supply From: T9
Mounting: Surface
Enclosure: 1

Volts: 208/120 Wye
Phases: 3
Wires: 4

A.I.C. Rating: 2
Mains Type: MLO
Mains Rating: 30 A
MCB Rating: 30 A

Notes: Provide 30 Amp, 3 Pole branch mounte main circuit breaker.

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1	NACC	20 A	1	0.00	0 VA					1	20 A	NACC	2
3	NACC	20 A	1			0 VA	0 VA			1	20 A	NACC	4
5	IDF ROOM WALL MOUNTED QUAD RECEPTACLE	20 A	1					360 VA	0.36	1	20 A	IDF ROOM WALL MOUNTED QUAD RECEPTACLE	6
7	IDF ROOM CABLE TRAY MOUNTED QUAD RECEPTACLE	20 A	1	0.36	360 VA					1	20 A	IDF ROOM CABLE TRAY MOUNTED QUAD RECEPTACLE	8
9	SPARE	20 A	1			0 VA	0 VA			1	20 A	SPARE	10
11	SPARE	20 A	1					0 VA	0.00	1	20 A	SPARE	12
13	SPARE	20 A	1	0.00	0 VA					1	20 A	SPARE	14
15	SPARE	20 A	1			0 VA	0 VA			1	20 A	SPARE	16
17	SPARE	20 A	1					0 VA	0.00	1	20 A	SPARE	18
				0.7 kVA		0.0 kVA		0.7 kVA					
				6.9 A		0.0 A		6.9 A					

TOTAL CONNECTED LOAD: 1440 VA

PANEL KEY	
LSH2D	**LSL2D**

E5-1-03-ELECTRICAL PANEL SCHEDULES
Designer: Designer Checker: Checker Approved: Approver ARCH E1 30"x42"
Project Management Initials:

Last Plotted: 9/30/2019 5:04:52 PM
Filename: BM_60601397_Publix HQ\60601397_Publix HQ_ELECT_R2019.rvt

Printed on ___% Post-Consumer Recycled Content Paper

©2016 AECOM Corporation

Building Inspection Division
City of Lakeland
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Date: 11/15/19
Permit Number: BLD19-06035

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

http://www.aecom.com

REGISTRATION

HENRYK B. JUSZCZYK
LICENSE
NO. 58082
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Henryk B Juszczyk
2019.09.30
18:19:27 -04'00'

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
1	SEP 30, 2019	100% CONSTRUCTION DOCUMENTS
0	AUG 23, 2019	CONSTRUCTION DOCUMENTS

PROJECT NUMBER

60601397

SHEET TITLE

ELECTRICAL PANEL SCHEDULES

SHEET NUMBER

E5-1-03