Building Inspection Division
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Lakeland
Date: 11/15/19
Permit Number: BLD19-06035

Panel: 1HF1

Location: TELE 1-112
Supply From: MDP-HF
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: 10,000
Mains Type: MLO
Mains Rating: 400 A
MCB Rating: 400 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1	LIGHTING	20 A	1	3.70 kVA	3.56 kVA					1	20 A	LIGHTING	2
3	LIGHTING	20 A	1			3.65 kVA	0.35 kVA			1	20 A	LIGHTING	4
5	LIGHTING	20 A	1					1.87 kVA	0.63 kVA	1	20 A	LIGHTING	6
7	LIGHTING - SITE BOLLARDS	20 A	1	0.61 kVA	0.00 kVA					1	20 A	SPARE	8
9	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	10
11	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	12
13	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	14
15	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	16
17	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	18
19	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	20
21	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	22
23	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	24
25	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	26
27	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	28
29	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	30
31	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	32
33	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	34
35	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	36
37	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	38
39	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	40
41	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	42
				7.9 kVA		4.0 kVA		2.5 kVA					
				29.2 A		15.2 A		9.0 A					

TOTAL CONNECTED LOAD: 14323 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
Lighting	13585 VA	125.00%	16981 VA		
Other	765 VA	100.00%	765 VA	**Total Conn. Load:**	14323 VA
				Total Est. Demand:	17719 VA
				Total Conn.:	17 A
				Total Est. Demand:	21 A

Panel: 1HF2 SEC1

Location: ELEC 1-113
Supply From: MDP-HF
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: 10,000
Mains Type: MLO
Mains Rating: 400 A
MCB Rating: 400 A

Notes: PROVIDE PANELBOARD WITH FEED THROUGH LUGS FOR FUTURE SECTION 2 INSTALLATION.

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				7.73 kVA	7.73 kVA								2
3	AHU-1-8	30 A	3			7.73 kVA	7.73 kVA			3	30 A	AHU-1-9	4
5								7.73 kVA	7.73 kVA				6
7				15.01 kVA	15.01 kVA								8
9	EDH-1-7	70 A	3			15.01 kVA	15.01 kVA			3	70 A	EDH-1-8	10
11								15.01 kVA	15.01 kVA				12
13				9.93 kVA	12.29 kVA								14
15	FPU-1-8-1, FPU-1-8-2, FPU-1-8-3	60 A	3			9.93 kVA	12.29 kVA			3	60 A	FPU-1-9-1, FPU-1-9-2, FPU-1-9-3	16
17								9.93 kVA	12.29 kVA				18
19				10.00 kVA	0.30 kVA								20
21	EWH-1	60 A	3			10.00 kVA	0.30 kVA			3	20 A	FCU-1	22
23								10.00 kVA	0.30 kVA				24
25	SPACE	--	--	4.00 kVA	0.00 kVA					--	--	SPACE	26
27	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	28
29	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	30
31	SPACE	--	--	0.00 kVA	0.17 kVA								32
33	SPACE	--	--			0.00 kVA	0.17 kVA			3	200 A	ELEVATOR NO.5 (40HP)	34
35	SPACE	--	--					0.00 kVA	0.17 kVA				36
37	SPACE	--	--	0.00 kVA	0.50 kVA					1	20 A	VAV CONTROL TRANSFORMER (277 VOLT)	38
39	SPACE	--	--			0.00 kVA	0.00 kVA			1	20 A	SPARE	40
41	SPACE	--	--					0.00 kVA	0.00 kVA	1	20 A	SPARE	42
				78.5 kVA		78.1 kVA		78.1 kVA					
				283.5 A		282.1 A		282.1 A					

TOTAL CONNECTED LOAD: 234802 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
HVAC	187610 VA	100.00%	187610 VA		
Power	1000 VA	100.00%	1000 VA	**Total Conn. Load:**	234802 VA
				Total Est. Demand:	240601 VA
				Total Conn.:	282 A
				Total Est. Demand:	289 A

Panel: 1HG1

Location: FREIGHT ELEV. NO. 6 -
Supply From: MDP-HG
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: 10,000
Mains Type: MLO
Mains Rating: 400 A
MCB Rating: 400 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1	LIGHTING	20 A	1	3.85 kVA	4.02 kVA					1	20 A	LIGHTING	2
3	LIGHTING	20 A	1			3.44 kVA	1.48 kVA			1	20 A	LIGHTING	4
5	LIGHTING	20 A	1					1.25 kVA	0.14 kVA	1	20 A	LIGHTING - SITE BOLLARDS	6
7	LIGHTING - SITE PARKING	20 A	2	2.00 kVA	2.13 kVA					2	20 A	LIGHTING - SITE PARKING	8
9						0.00 kVA	0.00 kVA						10
11	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	12
13	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	14
15	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	16
17	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	18
19	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	20
21	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	22
23	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	24
25	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	26
27	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	28
29	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	30
31	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	32
33	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	34
35	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	36
37	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	38
39	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	40
41	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	42
				11.9 kVA		4.9 kVA		1.4 kVA					
				44.8 A		19.7 A		5.0 A					

TOTAL CONNECTED LOAD: 18130 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
Lighting	14140 VA	125.00%	17675 VA		
Other	4123 VA	100.00%	4123 VA	**Total Conn. Load:**	18130 VA
				Total Est. Demand:	21658 VA
				Total Conn.:	22 A
				Total Est. Demand:	26 A

Panel: 1HG2 SEC1

Location: ELEC 1-137
Supply From: MDP-HG
Mounting: Surface
Enclosure: 1

Volts: 480/277 Wye
Phases: 3
Wires: 4

A.I.C. Rating: 10,000
Mains Type: MLO
Mains Rating: 400 A
MCB Rating: 400 A

Notes: PROVIDE PANELBOARD WITH FEED THROUGH LUGS FOR FUTURE SECTION 2 INSTALLATION.

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				7.73 kVA	7.73 kVA								2
3	AHU-1-10	30 A	3			7.73 kVA	7.73 kVA			3	30 A	AHU-1-11	4
5								7.73 kVA	7.73 kVA				6
7				15.01 kVA	15.01 kVA								8
9	EDH-1-9	70 A	3			15.01 kVA	15.01 kVA			3	70 A	EDH-1-10	10
11								15.01 kVA	15.01 kVA				12
13				7.80 kVA	7.42 kVA								14
15	FPU-1-11-1, FPU-1-11-2	60 A	3			7.80 kVA	7.42 kVA			3	60 A	FPU-1-10-1, FPU-1-10-2, FPU-1-10-3	16
17								7.80 kVA	7.42 kVA				18
19				0.94 kVA	0.00 kVA					--	--	SPACE	20
21	EF-1	20 A	3			0.94 kVA	0.00 kVA			--	--	SPACE	22
23								0.94 kVA	0.00 kVA	--	--	SPACE	24
25				0.30 kVA	0.00 kVA					--	--	SPACE	26
27	FCU-2	20 A	3			0.30 kVA	0.00 kVA			--	--	SPACE	28
29								0.30 kVA	0.00 kVA	--	--	SPACE	30
31				0.00 kVA	0.00 kVA					--	--	SPACE	32
33	COMPACTOR (10HP)	30 A	3			0.00 kVA	0.00 kVA			--	--	SPACE	34
35								0.00 kVA	0.00 kVA	--	--	SPACE	36
37				0.17 kVA	0.50 kVA					1	20 A	VAV CONTROL TRANSFORMER (277 VOLT)	38
39	ELEVATOR NO.6 (40HP)	200 A	3			0.17 kVA	0.00 kVA			1	20 A	SPARE	40
41								0.17 kVA	0.00 kVA	1	20 A	SPARE	42
				62.5 kVA		62.1 kVA		62.1 kVA					
				225.6 A		224.1 A		224.1 A					

TOTAL CONNECTED LOAD: 186640 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
HVAC	139448 VA	100.00%	139448 VA		
Power	1000 VA	100.00%	1000 VA	**Total Conn. Load:**	186640 VA
				Total Est. Demand:	192439 VA
				Total Conn.:	224 A
				Total Est. Demand:	231 A

PANEL KEY	
1HF1	**1HF2**
1HG1	**1HG2**

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

http://www.aecom.com

REGISTRATION

HENRYK B. JUSZCZYK, LICENSE NO. 58082, STATE OF FLORIDA, PROFESSIONAL ENGINEER

HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Henryk B Juszczyk
2019.09.30
18:18:29 -04'00'

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
1	SEP 30, 2019	100% CONSTRUCTION DOCUMENTS
0	AUG 23, 2019	CONSTRUCTION DOCUMENTS

PROJECT NUMBER

60601397

SHEET TITLE

ELECTRICAL PANEL SCHEDULES

SHEET NUMBER

E5-1-10

Printed on ___% Post-Consumer Recycled Content Paper
©2016 AECOM Corporation