Building Inspection Division
Lakeland
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Date: 11/15/19
Permit Number: BLD19-06035

Panel: 3HF1

Location: TELE 3-112
Supply From: MDP-HF
Mounting: Surface
Enclosure: 1
Volts: 480/277 Wye
Phases: 3
Wires: 4
A.I.C. Rating: 10,000
Mains Type: MLO
Mains Rating: 400 A
MCB Rating: 400 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1	LIGHTING	20 A	1	3.75 kVA	3.85 kVA					1	20 A	LIGHTING	2
3	LIGHTING	20 A	1			3.32 kVA	0.43 kVA			1	20 A	LIGHTING	4
5	LIGHTING	20 A	1					1.87 kVA	0.63 kVA	1	20 A	LIGHTING	6
7	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	8
9	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	10
11	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	12
13	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	14
15	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	16
17	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	18
19	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	20
21	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	22
23	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	24
25	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	26
27	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	28
29	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	30
31	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	32
33	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	34
35	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	36
37	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	38
39	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	40
41	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	42
				7.6 kVA		3.7 kVA		2.5 kVA					
				28.1 A		14.2 A		9.0 A					

TOTAL CONNECTED LOAD: 13811 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
Lighting	13075 VA	125.00%	16344 VA		
Other	765 VA	100.00%	765 VA	**Total Conn. Load:**	13811 VA
				Total Est. Demand:	17079 VA
				Total Conn.:	17 A
				Total Est. Demand:	21 A

Panel: 3HF2-SEC1

Location: ELEC 3-113
Supply From: MDP-HF
Mounting: Surface
Enclosure: 1
Volts: 480/277 Wye
Phases: 3
Wires: 4
A.I.C. Rating: 10,000
Mains Type: MLO
Mains Rating: 400 A
MCB Rating: 400 A

Notes: PROVIDE PANELBOARD WITH FEED THROUGH LUGS FOR FUTURE SECTION 2 INSTALLATION.

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				7.73 kVA	7.73 kVA								2
3	AHU-3-7	30 A	3			7.73 kVA	7.73 kVA			3	20 A	AHU-3-8	4
5								7.73 kVA	7.73 kVA				6
7				15.01 kVA	15.01 kVA								8
9	EDH-3-7	70 A	3			15.01 kVA	15.01 kVA			3	70 A	EDH-3-8	10
11								15.01 kVA	15.01 kVA				12
13				9.93 kVA	11.11 kVA								14
15	FPU-3-7-1, FPU-3-7-2, FPU-3-7-3	60 A	3			9.93 kVA	11.11 kVA			3	60 A	FPU-3-8-1, FPU-3-8-2, FPU-3-8-3	16
17								9.93 kVA	11.11 kVA				18
19				8.66 kVA	0.30 kVA								20
21	ERV-4	40 A	3			8.66 kVA	0.30 kVA			3	20 A	FCU-5	22
23								8.66 kVA	0.30 kVA				24
25				10.00 kVA	0.00 kVA					--	--	SPACE	26
27	EWH-3	60 A	3			10.00 kVA	0.00 kVA			--	--	SPACE	28
29								10.00 kVA	0.00 kVA	--	--	SPACE	30
31	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	32
33	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	34
35	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	36
37	VAV CONTROL TRANSFORMER (277 VOLT)	20 A	1	0.50 kVA	0.00 kVA					--	--	SPACE	38
39	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	40
41	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	42
				85.9 kVA		85.9 kVA		85.9 kVA					
				310.0 A		308.6 A		308.6 A					

TOTAL CONNECTED LOAD: 256841 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
HVAC	184069 VA	100.00%	184069 VA		
Power	500 VA	100.00%	500 VA	**Total Conn. Load:**	256841 VA
				Total Est. Demand:	263336 VA
				Total Conn.:	309 A
				Total Est. Demand:	317 A

Panel: 3HG1

Location: FREIGHT ELEV NO. 6 -
Supply From: MDP-HG
Mounting: Surface
Enclosure: 1
Volts: 480/277 Wye
Phases: 3
Wires: 4
A.I.C. Rating: 10,000
Mains Type: MLO
Mains Rating: 400 A
MCB Rating: 400 A

Notes:

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1	LIGHTING	20 A	1	3.73 kVA	4.02 kVA					1	20 A	LIGHTING	2
3	LIGHTING	20 A	1			3.40 kVA	3.16 kVA			1	20 A	LIGHTING	4
5	LIGHTING	20 A	1					0.21 kVA	0.00 kVA	1	20 A	SPARE	6
7	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	8
9	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	10
11	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	12
13	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	14
15	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	16
17	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	18
19	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	20
21	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	22
23	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	24
25	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	26
27	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	28
29	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	30
31	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	32
33	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	34
35	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	36
37	SPARE	20 A	1	0.00 kVA	0.00 kVA					1	20 A	SPARE	38
39	SPARE	20 A	1			0.00 kVA	0.00 kVA			1	20 A	SPARE	40
41	SPARE	20 A	1					0.00 kVA	0.00 kVA	1	20 A	SPARE	42
				7.7 kVA		6.6 kVA		0.2 kVA					
				31.5 A		27.2 A		0.8 A					

TOTAL CONNECTED LOAD: 14508 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
Lighting	14508 VA	125.00%	18135 VA		
				Total Conn. Load:	14508 VA
				Total Est. Demand:	18135 VA
				Total Conn.:	17 A
				Total Est. Demand:	22 A

Panel: 3HG2 SEC1

Location: ELEC 3-137
Supply From: MDP-HG
Mounting: Surface
Enclosure: 1
Volts: 480/277 Wye
Phases: 3
Wires: 4
A.I.C. Rating: 10,000
Mains Type: MLO
Mains Rating: 400 A
MCB Rating: 400 A

Notes: PROVIDE PANELBOARD WITH FEED THROUGH LUGS FOR FUTURE SECTION 2 INSTALLATION.

CKT	Circuit Description	Trip	Poles	A		B		C		Poles	Trip	Circuit Description	CKT
1				7.73 kVA	7.73 kVA								2
3	AHU-3-9	30 A	3			7.73 kVA	7.73 kVA			3	30 A	AHU-3-10	4
5								7.73 kVA	7.73 kVA				6
7				15.01 kVA	15.01 kVA								8
9	EDH-3-9	70 A	3			15.01 kVA	15.01 kVA			3	70 A	EDH-3-10	10
11								15.01 kVA	15.01 kVA				12
13				13.58 kVA	7.80 kVA								14
15	FPU-3-9-1, FPU-3-9-2, FPU-3-9-3, FPU-3-9-4	60 A	3			13.58 kVA	7.80 kVA			3	60 A	FPU-3-10-1, FPU-3-10-2	16
17								13.58 kVA	7.80 kVA				18
19				8.66 kVA	0.30 kVA								20
21	HVAC/MOTOR	20 A	3			8.66 kVA	0.30 kVA			3	20 A	FCU-6	22
23								8.66 kVA	0.30 kVA				24
25	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	26
27	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	28
29	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	30
31	SPACE	--	--	0.00 kVA	0.00 kVA					--	--	SPACE	32
33	SPACE	--	--			0.00 kVA	0.00 kVA			--	--	SPACE	34
35	SPACE	--	--					0.00 kVA	0.00 kVA	--	--	SPACE	36
37	VAV CONTROL TRANSFORMER (277 VOLT)	20 A	1	0.50 kVA	0.00 kVA					--	--	SPACE	38
39	SPARE	20 A	1			0.00 kVA	0.00 kVA			--	--	SPACE	40
41	SPARE	20 A	1					0.00 kVA	0.00 kVA	--	--	SPACE	42
				76.2 kVA		75.9 kVA		75.9 kVA					
				275.2 A		273.7 A		273.7 A					

TOTAL CONNECTED LOAD: 227867 VA

Load Classification	Connected Load	Demand Factor	Estimated Demand	Panel Totals	
HVAC	155095 VA	100.00%	155095 VA		
Power	500 VA	100.00%	500 VA	**Total Conn. Load:**	227867 VA
				Total Est. Demand:	234362 VA
				Total Conn.:	274 A
				Total Est. Demand:	282 A

PANEL KEY

3HF1	3HF2
3HG1	3HG2

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

http://www.aecom.com

REGISTRATION

HENRYK B. JUSZCZYK, LICENSE NO. 58082, STATE OF FLORIDA, PROFESSIONAL ENGINEER

HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY HENRYK B. JUSZCZYK, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 58082 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Henryk B Juszczyk
2019.09.30
18:16:19 -04'00'

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
1	SEP 30, 2019	100% CONSTRUCTION DOCUMENTS
0	AUG 23, 2019	CONSTRUCTION DOCUMENTS

PROJECT NUMBER

60601397

SHEET TITLE

ELECTRICAL PANEL SCHEDULES

SHEET NUMBER

E5-1-30

Printed on ___% Post-Consumer Recycled Content Paper
©2016 AECOM Corporation