HVAC GENERAL NOTES

NOTE #	DESCRIPTION
1.	VISIT THE SITE OF THE WORK TO GAIN AN ACCEPTABLE KNOWLEDGE OF CONDITIONS AFFECTING THE EXECUTION OF THE WORK. AFTER VISITING THE SITE, REQUEST SUCH INFORMATION AND/OR CLARIFICATIONS AS NECESSARY TO FULLY UNDERSTAND THE WORK REQUIRED AND TO PROPERLY ESTIMATE COSTS.
2.	REVIEW ALL DRAWINGS TO VERIFY EXTENT AND SCHEDULING OF ALL DEMOLITION ACTIVITIES PRIOR TO COMMENCING DEMOLITION WORK. FIELD VERIFY ALL SIZES AND LOCATIONS OF EXISTING DUCTWORK AND PIPING TO REMAIN. NOTIFY ARCHITECT/ENGINEER OF DEVIATIONS WHICH AFFECT RENOVATION WORK PRIOR TO PROCEEDING WITH THE WORK.
3.	ITEMS NOTED TO BE DEMOLISHED INCLUDES BUT IS NOT LIMITED TO ALL ASSOCIATED COMPONENTS, CONTROL WIRING, PIPING, DUCTWORK, ELECTRICAL CONNECTIONS, SUPPORTS, INSULATION, ETC. COORDINATE WITH OTHER TRADES AS REQUIRED.
4.	ALL WORK IS TO BE PHASED AS INDICATED ON THE ARCHITECTURAL DRAWINGS. COORDINATE PHASING OF ALL DEMOLITION, RENOVATION, AND NEW WORK WITH OTHER TRADES. CLOSELY COORDINATE PHASING OF WORK WITHIN CORRIDORS WITH THE OWNER. CORRIDORS CANNOT BE COMPLETELY CLOSED OFF TO PEDESTRIAN TRAFFIC. TO ACCOMMODATE PHASING, CORRIDOR ACCESS WORK MAY NEED TO BE PERFORMED DURING OFF PEAK PERIODS. PRIOR TO MOVING ON TO THE NEXT PHASE, ALL WORK IN PREVIOUSLY PHASED AREAS MUST BE COMPLETE AND OPERATIONAL.
5.	ENSURE THAT THE WORK WILL NOT INTERFERE OR INTERRUPT SERVICES TO AREAS OUTSIDE OF THE DESIGNATED CONTRACT AREAS. SCHEDULE ALL WORK AS TO CAUSE MINIMAL SERVICE INTERRUPTIONS FOR THE OWNER. UNAVOIDABLE INTERRUPTIONS ARE TO BE SCHEDULED WITH THE OWNER NO LESS THAN TWO WEEKS PRIOR TO THEIR EXPECTED COMMENCEMENT. WORK SHALL BE PERFORMED AT SUCH TIMES AS DIRECTED BY THE OWNER AND, IF POSSIBLE, ARE TO OCCUR DURING OFF PEAK PERIODS.
6.	THE CONTRACTOR IS TO VERIFY THE EXACT SERVICE OF ANY EXISTING PIPING OR DUCTWORK PRIOR TO INSTALLING ANY NEW CONNECTIONS. ANY DISCREPANCIES BETWEEN THE CONSTRUCTION DOCUMENTS OR THE DESIGN INTENT AND ACTUAL CONDITIONS ARE TO BE BROUGHT TO THE ATTENTION OF THE ENGINEER IMMEDIATELY, PRIOR TO FABRICATION OR INSTALLATION.
7.	CONTRACTOR SHALL REMOVE AND REPLACE EXISTING LAY-IN CEILING GRID AND TILES AS NECESSARY TO COMPLETE ABOVE CEILING WORK. RETURN CEILING TO ORIGINAL CONDITION FOLLOWING COMPLETION OF CONSTRUCTION.
8.	PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS AS INDICATED ON THE DRAWINGS AND SPECIFICATIONS. INCLUDE ALL NECESSARY AND APPLICABLE APPURTENANCES, WHETHER INDICATED OR NOT.
9.	ANY DEVIATIONS FROM THE BASIS OF DESIGN THAT REQUIRE ADDITIONAL PROVISIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
10.	COORDINATE THE EXACT REQUIREMENTS AND LOCATION OF WORK WITH THE WORK OF OTHER TRADES PRIOR TO FABRICATION AND INSTALLATION. PROVIDE ADDITIONAL OFFSETS AND SECTIONS IN DUCTWORK AND/OR PIPING REQUIRED TO MEET THE APPLICABLE JOB CONDITION REQUIREMENTS. VERIFY JOB SITE ELEVATIONS, DIMENSIONS, AND CONDITIONS, PRIOR TO FABRICATION OR INSTALLATION OF THE WORK. COORDINATE EXACT ROUTING OF DUCTWORK AND PIPING WITH OTHER TRADES SO THAT NO CONFLICTS OCCUR WITH DUCTWORK, PIPING, LIGHTS, STRUCTURE, ETC. PROVIDE ALL PERTINENT DATA CONCERNING THE LOCATION, DIMENSIONS, ETC., OF THE MECHANICAL EQUIPMENT THAT REQUIRES BASES, CURBS AND SUPPORTS TO THE APPROPRIATE TRADES.
11.	WHERE CEILINGS ARE INDICATED, ALL DUCTS AND PIPES SHALL BE RAN ABOVE CEILING. IN EXPOSED CONDITIONS, INSTALL DUCTWORK AND PIPING TIGHT TO THE BOTTOM OF STRUCTURE.
12.	WHERE CEILINGS ARE INDICATED, ALL DUCTS AND PIPES SHALL BE RAN ABOVE CEILING. IN EXPOSED CONDITIONS, INSTALL DUCTWORK AND PIPING TIGHT TO THE BOTTOM OF STRUCTURE.
13.	ALL ITEMS THAT REQUIRE MAINTENANCE OR ADJUSTMENT MUST BE INSTALLED IN ACCESSIBLE LOCATIONS. PROVIDE AN APPROPRIATELY SIZED ACCESS DOOR AS REQUIRED.
14.	ALL SEALS, BEARINGS, PACKINGS, AND ACCESSORIES FOR ALL EQUIPMENT AND PIPING SPECIALTIES SHALL BE SUITABLE FOR THE CONTINUOUS OPERATIONAL TEMPERATURES, PRESSURES AND CHARACTERISTICS, OF THE SYSTEM THEY SERVE.
15.	EACH TRADE SHALL PAY THE GENERAL CONTRACTOR TO PATCH FLOOR SLAB AND WALL PENETRATIONS TO MATCH EXISTING WHERE THEIR PIPING, DUCT OR EQUIPMENT IS BEING REMOVED OR INSTALLED.
16.	INSTALL ALL WORK TO COMPLY WITH ALL LAWS, REGULATIONS, CODES, AND STANDARDS (FEDERAL, STATE, AND LOCAL), AS ADOPTED BY THE AGENCIES HAVING JURISDICTION, INCLUDING REASONABLY ANTICIPATED REVISIONS BASED ON EMERGING TRENDS IN BUILDING REGULATIONS. WHERE ANY OF THESE DIFFER, THE MOST STRINGENT SHALL APPLY.
17.	CONTRACT DOCUMENTS FOR MECHANICAL WORK ARE SCHEMATIC IN NATURE AND ARE INTENDED TO CONVEY SCOPE AND GENERAL ARRANGEMENT ONLY.
18.	ALL ROOFING MODIFICATIONS SHALL BE DONE BY OWNER'S ROOFING VENDOR TO MAINTAIN ANY AND ALL WARRANTIES. COST TO BE INCLUDED IN THIS CONTRACT UNLESS SPECIFICALLY INCLUDED IN GENERAL TRADES CONTRACTOR'S SCOPE OF WORK.
19.	INSULATE DUCTWORK AND PIPING WHERE EXISTING INSULATION HAS BEEN DAMAGED AND/OR REMOVED IN THE PERFORMANCE OF WORK FOR THIS PROJECT.
20.	FOR RENOVATION WORK, IT IS PROHIBITED TO SUSPEND NEW WORK FROM THE EXISTING FLOOR SLAB OR ROOF DECK.
21.	PERFORM A COMPLETE AIR AND WATER SYSTEM FLOW BALANCE FOR ALL EQUIPMENT THAT IS SHOWN, SCHEDULED OR OTHERWISE IDENTIFIED, AT THE END OF CONSTRUCTION.
22.	INSTALL EQUIPMENT, MATERIALS, ETC. IN STRICT ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND DIRECTION. PROVIDE STRAIGHT INLET AND OUTLET DUCTS/PIPES BASED ON MANUFACTURER'S RECOMMENDATIONS. IF IN CONFLICT WITH THE DESIGN INDICATED HEREIN, ADVISE THE ENGINEERS PRIOR TO INSTALLATION FOR CLARIFICATION.
23.	COORDINATE THE EXACT LOCATIONS OF DIFFUSERS, GRILLES AND REGISTERS WITH ARCHITECTURAL REFLECTED CEILING PLANS, AREA SMOKE DETECTORS, SPRINKLERS, LIGHTS AND ELECTRICAL DEVICES. AIR DEVICES SHALL NOT BE WITHIN 3 FEET OF AN AREA SMOKE DETECTOR.
24.	UNLESS NOTED OTHERWISE, PROVIDE BRANCH DUCT TO DIFFUSERS SAME SIZE AS DIFFUSER NECK. FLEXIBLE DUCT CONNECTION TO THE DIFFUSER SHALL BE NO MORE THAN FIVE FEET IN LENGTH. ALL BRANCH DUCT TAKEOFFS TO AIR DEVICES SHALL HAVE A MANUAL BALANCING DAMPER INSTALLED IN AN ACCESSIBLE LOCATION.
25.	AIR DEVICES PROVIDED WITH INTEGRAL BALANCE DAMPERS DO NOT REQUIRE ADDITIONAL BALANCING DAMPER AT AIR DEVICE BRANCH TAKEOFF.
26.	PROVIDE ROOM TEMPERATURE THERMOSTATS FOR ALL EQUIPMENT THAT MAINTAINS SPACE TEMPERATURE. PREFERRED LOCATIONS ARE SHOWN ON THE PLANS. THERMOSTATS SHALL BE MOUNTED AT 48" ABOVE FINISHED FLOOR, UNLESS NOTED OTHERWISE. COORDINATE THE EXACT LOCATIONS OF THERMOSTATS WITH MARKERBOARDS, SWITCHES, AND ANY OTHER WALL MOUNTED FIXTURES PRIOR TO ROUGH IN.
27.	UNLESS NOTED OTHERWISE, MINIMUM PIPE SIZE SHALL BE 3/4 INCH AND MINIMUM FLOW SHALL BE 0.5 GPM.
28.	PROVIDE SHUT-OFF VALVES WITHIN ALL SUPPLY PIPING BRANCH TAKEOFFS FROM MAINS. PROVIDE A MANUAL BALANCE VALVE AND A SEPARATE SHUT-OFF VALVE WITHIN ALL RETURN PIPING BRANCH TAKE-OFFS FROM MAINS. LOCATE VALVES IN ACCESSIBLE LOCATIONS.
29.	INSTALL ALL PIPING IN LOCATIONS AND ELEVATIONS SUCH THAT COILS, TUBES, AND FILTERS CAN BE REMOVED AND REPLACED WITHOUT MAJOR PIPING REMOVAL. LOCATE VALVES IN APPROPRIATE PLACES TO ACCOMMODATE MAINTENANCE. FOR GRAVITY FLOW PIPING, ADEQUATE SLOPE SHALL BE PROVIDED.
30.	INSTALL TWO-WAY CONTROL VALVES ON ALL EQUIPMENT UNLESS NOTED OTHERWISE.
31.	AT TIME OF ROUGH INSTALLATION, DURING STORAGE ON THE CONSTRUCTION SITE, AND UNTIL FINAL STARTUP OF THE HEATING AND COOLING EQUIPMENT, ALL DUCT AND OTHER RELATED AIR DISTRIBUTION COMPONENT OPENINGS SHALL BE COVERED WITH TAPE, PLASTIC, SHEET METAL OR OTHER METHODS ACCEPTABLE FOR PROTECTION TO THE ENFORCING AGENCY TO REDUCE THE AMOUNT OF DUST OR DEBRIS WHICH MAY COLLECT IN THE SYSTEM(S).
32.	IN MECHANICALLY VENTILATED BUILDINGS, PROVIDE REGULARLY OCCUPIED AREAS OF THE BUILDING WITH AIR FILTRATION MEDIA FOR OUTSIDE AND RETURN AIR THAT PROVIDES AT LEAST A MINIMUM EFFICIENCY REPORTING VALUE (MERV) OF 8 PRIOR TO OCCUPANCY. FILTERS SHALL BE CHANGED PRIOR TO AIR BALANCE AND COMMISSIONING, AND AGAIN AT THE COMPLETION OF CONSTRUCTION JUST PRIOR TO OCCUPANCY OF THE BUILDING WITH FINAL FILTERS PER SPECIFICATIONS. MAINTENANCE RECOMMENDATIONS FOR FILTERS OF THE SAME VALUE SHALL BE INCLUDED IN THE OPERATION AND MAINTENANCE MANUAL.
33.	INSTALLATION OF HVAC, REFRIGERATION, AND FIRE SUPPRESSION EQUIPMENT SHALL NOT CONTAIN ANY CFCS OR HALONS.
34.	ALL SUPPORTS FOR EQUIPMENT, DUCTWORK AND PIPING SYSTEMS, DEVICES SHALL BE FROM THE BUILDING STRUCTURE. SUPPORT FROM STRUCTURAL BRIDGING IS UNACCEPTABLE.
35.	INSTALL NO PIPING, CONDUIT, DUCTWORK, ETC., IN A LOCATION OR IN A MANNER THAT WILL ALLOW FREEZING AND/OR THE COLLECTION OF CONDENSATION.
36.	CONTRACTOR IS RESPONSIBLE FOR DRAINING, FLUSHING, PURGING, AND FILLING ALL PIPING SYSTEMS AS REQUIRED. THESE SYSTEMS INCLUDE (BUT MAY NOT BE LIMITED TO): HEATING HOT WATER SYSTEMS, CHILLED WATER SYSTEMS, BUILDING STEAM SYSTEMS, ALL REQUIRED CHEMICAL TREATMENT SYSTEMS, CONDENSER WATER SYSTEMS (AND COOLING TOWER SUMPS), WATER-SOURCE HEAT PUMP LOOP SYSTEMS, GROUND-SOURCE HEAT PUMP LOOP SYSTEMS, AND MAKE-UP WATER CONNECTIONS.

MECHANICAL EQUIPMENT ABBREVIATIONS

ABBREVIATION	DESCRIPTION
ACC1	AIR COOLED CONDENSER
ACCU1	AIR COOLED CONDENSING UNIT
AFMS1	AIR FLOW MEASURING STATION
AHU1	AIR HANDLING UNIT
AS1	AIR SEPARATOR
B1	BOILER
BC1	BLOWER COIL
BDS1	BLOWDOWN SEPARATOR
BDT1	BLOWDOWN TANK
CAH1	COMBUSTION AIR HEATER
CAHU1	COMPUTER AIR HANDLING UNIT
CC1	COOLING COIL
CH1	CHILLER
CHP1	CHILLED WATER PUMP
CN1	CONDENSATE NEUTRALIZER
CP1	COOLING COIL CONDENSATE PUMP
CRAC1	COMPUTER ROOM AIR CONDITIONING UNIT
CRU1	STEAM CONDENSATE RETURN UNIT
CT1	COOLING TOWER
CTP1	STEAM CONDENSATE TRANSFER PUMP
CUH1	CABINET UNIT HEATER
CWP1	CONDENSER WATER PUMP
DA1	DEAERATOR
DAC1	AIR CURTAIN/DOOR HEATER
DH1	DEHUMIDIFIER (PLUG-IN)
DHU1	DEHUMIDIFICATION UNIT
E1	EXHAUST GRILLE
EBH1	ELECTRIC BASEBOARD HEATER
ECH1	ELECTRIC CABINET HEATER
EF1	EXHAUST FAN
EIH1	ELECTRIC INFRARED HEATER
ET1	EXPANSION TANK
EUH1	ELECTRIC UNIT HEATER
EUV1	ELECTRIC UNIT VENTILATOR
F1	FURNACE
FC1	FAN COIL
FT1	FIN TUBE RADIANT HEATER
GIH	GAS INFRARED HEATER
GUH1	GAS UNIT HEATER
GV1	GRAVITY VENTILATOR
H1	HUMIDIFIER
HC1	HEATING COIL
HP1	HEAT PUMP
HRC1	HEAT RECOVERY VENTILATOR
HWP1	HEATING HOT WATER PUMP
ERV1	ENERGY RECOVERY VENTILATOR
HX1	HEAT EXCHANGER
KH1	KITCHEN HOOD
L1	LOUVER
LH1	LAB HOOD
MAU1	MAKEUP AIR UNIT
PRV1	PRESSURE REDUCING VALVE
R1	RETURN GRILLE
RP1	RADIANT CEILING PANEL
RF1	RETURN FAN
RTU1	ROOFTOP UNIT
S1	SUPPLY DIFFUSER
SC1	STEAM COIL
SF1	SUPPLY FAN
SP1	STEAM POWERED PUMP
ST1	STORAGE TANK
SST1	STEAM SURGE TANK
TB1	TERMINAL BOX
UH1	UNIT HEATER
UV1	UNIT VENTILATOR
LP1	LOUVERED PENTHOUSE
SA1	SOUND ATTENUATOR
DOAS1	DEDICATED OUTDOOR AIR UNIT
CB1	CHILLED BEAM
VFD1	VARIABLE FREQUENCY DRIVE
FWP1	FEEDWATER PUMP
VP1	VACUUM PUMP
SG1	STEAM GENERATOR

MECHANICAL ABBREVIATIONS

ABBREVIATION	DESCRIPTION
(D)	EXISTING TO BE DEMOLISHED
(E)	EXISTING TO REMAIN
(F)	FUTURE
AFF	ABOVE FINISHED FLOOR
AMB	AMBIENT
APD	AIR PRESSURE DROP
BAS	BUILDING AUTOMATION SYSTEM
BFP	BACKFLOW PREVENTOR
BHP	BRAKE HORSEPOWER
BLDG	BUILDING
BOB	BOTTOM OF BEAM
BOD	BOTTOM OF DUCT
BOP	BOTTOM OF PIPE
BOS	BOTTOM OF STRUCTURE
BTUH	BRITISH TEHRMAL UNITS PER HOUR
CFM	CUBIC FEET PER MINUTE
CL	CENTER LINE
CO	CLEAN OUT
COMPR	COMPRESSOR
COP	COEFFICIENT OF PERFORMANCE
DB	DRY BULB
DIA	DIAMETER
DN	DOWN
EAT	ENTERING AIR TEMPERATURE
EER	ENERGY EFFICIENCY RATIO
EFF	EFFICIENCY
EG	ETHYLENE GLYCOL
ESP	EXTERNAL STATIC PRESSURE
EWT	ENTERING WATER TEMPERATURE
FLA	FULL LOAD AMPS
FPI	FINS PER INCH
FPM	FEET PER MINUTE
FPS	FEET PER SECOND
FT	FEET
GAL	GALLONS
GPM	GALLONS PER MINUTE
HD	HEAD
HP	HORSEPOWER
ID	INNER DIAMETER
IPLV	INTEGRATED PART LOAD VALUE
KW	KILOWATTS
LAT	LEAVING AIR TEMPERATURE
LWT	LEAVING WATER TEMPERATURE
MBH	THOUSAND BTUH
MCA	MAXIMUM CURRENT AMPACITY
MFR	MANUFACTURER
MOCP	MAXIMUM OVERCURRENT PROTECTION
N/A	NOT APPLICABLE
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
NOX	NITROUS OXIDE
NPLV	NON-STANDARD PART LOAD VALUE
NPSH	NET POSITIVE SUCTION HEAD
NTS	NOT TO SCALE
OD	OUTSIDE DIAMETER
PD	PRESSURE DROP
PG	PROPYLENE GLYCOL
PPM	PARTS PER MILLION
PRV	PRESSURE REDUCING VALVE
PPH	POUNDS PER HOUR
PSI	PUNDS PER SQUARE INCH
REFRIG	REFRIGERANT
RH	RELATIVE HUMIDITY
RPM	REVOLUTIONS PER MINUTE
SEER	SEASONAL ENERGY EFFICIENCY RATIO
SP	STATIC PRESSURE
TSP	TOTAL STATIC PRESSURE
TYP	TYPICAL
UNO	UNLESS NOTED OTHERWISE
VAV	VARIABLE AIR VOLUME
VFD	VARIABLE FREQUENCY DRIVE
VRF	VARIABLE REFRIGERANT FLOW
W	WATTS
WB	WET BULB
WG	WATER GAUGE
WPD	WATER PRESSURE DROP
CV	CONSTANT VOLUME

MECHANICAL SYMBOLS LIST

NOTE: NOT ALL SYMBOLS MAY BE USED.

SYMBOL	DESCRIPTION
	AIRFLOW ARROW
	FLOW ARROW
	CONNECT TO EXISTING
	END OF DEMOLITION
	PIPE CAPPED
	PIPE DROP
	PIPE RISE
	PIPE TEE DOWN
	PIPE REDUCER
	PIPE UNION
	PIPE GUIDES OR SLEEVES
	PIPE ANCHOR
	FLEXIBLE PIPE CONNECTION
	GENERAL SERVICE VALVE (SEE SPECIFICATIONS FOR VALVE TYPE PER APPLICATION)
	CHECK VALVE (ARROW INDICATES DIRECTION OF FLOW)
	MANUAL BALANCING VALVE
	AUTOMATIC BALANCING VALVE
	TWO-WAY CONTROL VALVE
	THREE-WAY CONTROL VALVE
PICBV	TWO-WAY PRESSURE INDEPENDENT CONTROL AND BALANCE VALVE
	PRESSURE REDUCING VALVE
	STEAM PRESSURE REGULATING VALVE
	RELIEF VALVE
	DRAIN VALVE WITH THREADED HOSE CONNECTION
	REDUCED PRESSURE BACKFLOW PREVENTER
	PRESSURE GAUGE WITH STOPCOCK
	STRAINER WITH BLOW DOWN VALVE
AV	AUTOMATIC AIR VENT
MAV	MANUAL AIR VENT
	TEMPERATURE/PRESSURE TEST PLUG (PETE'S PLUG)
	STEAM TRAP
CO CO	CLEAN OUT
	FLOW METER
	THERMOMETER
	PITCH DOWN IN DIRECTION OF ARROW
H	HUMIDISTAT WITH ADJUSTABLE CONTROL
T	THERMOSTAT WITH ADJUSTABLE CONTROL
H	HUMIDITY SENSOR
T	TEMPERATURE SENSOR
CO2	CARBON DIOXIDE SENSOR
CO	CARBON MONOXIDE SENSOR
NO2	NITROGEN DIOXIDE SENSOR
OS	OCCUPANCY SENSOR

MECHANICAL SYMBOLS LIST CONT.

NOTE: NOT ALL SYMBOLS MAY BE USED.

SYMBOL	DESCRIPTION
	SUPPLY DIFFUSER WITH FLEXIBLE DUCT TAG - NECK SIZE / AIRFLOW (CFM) — TAG EXAMPLE: S1-6a / 100
	SUPPLY DIFFUSER TAG - NECK SIZE / AIRFLOW (CFM) — TAG EXAMPLE: S1-6a / 100
	RETURN/EXHAUST GRILLE TAG - NECK SIZE / AIRFLOW (CFM) — TAG EXAMPLE: R1-22x10 / 500; E1-22x10 / 500
	SIDEWALL SUPPLY DIFFUSER TAG - NECK SIZE / AIRFLOW (CFM) — TAG EXAMPLE: S2-12x8 / 100
	SIDEWALL RETURN/EXHAUST GRILLE TAG - NECK SIZE / AIRFLOW (CFM) — TAG EXAMPLE: R2-12x8 / 100; E2-12x8 / 100
BDD OR BDD	DAMPERS/SENSOR BDD: BACKDRAFT DAMPER FSD: FIRE/SMOKE DAMPER FD: FIRE DAMPER FS: FLOW SENSOR MD: MOTORIZED DAMPER SD: SMOKE DETECTOR VD: VOLUME DAMPER
	SUPPLY AND OUTDOOR AIR RECTANGULAR DUCT ELBOW UP OVAL DUCT ELBOW UP ROUND DUCT ELBOW UP
	RETURN, RELIEF, AND EXHAUST AIR RECTANGULAR DUCT ELBOW UP OVAL DUCT ELBOW UP ROUND DUCT ELBOW UP
	SUPPLY AND OUTDOOR AIR RECTANGULAR DUCT ELBOW DOWN OVAL DUCT ELBOW DOWN ROUND DUCT ELBOW DOWN
	RETURN, RELIEF, AND EXHAUST AIR RECTANGULAR DUCT ELBOW DOWN OVAL DUCT ELBOW DOWN ROUND DUCT ELBOW DOWN
	NEW WORK DUCTWORK
	EXISTING DUCTWORK
	DEMOLITION DUCTWORK
	NEW WORK PIPING
	EXISTING PIPING
	DEMOLISHED PIPING
	NEW WORK MECHANICAL EQUIPMENT (WITH CLEARANCE SHOWN)
	EXISTING MECHANICAL EQUIPMENT
	DEMOLISHED MECHANICAL EQUIPMENT
	GENERIC FAN
	GENERIC PUMP
	ACCESS DOOR
	TERMINAL BOXES VAV TERMINAL BOX (WITH REHEAT) VAV TERMINAL BOX (NO REHEAT)
	TERMINAL BOX NOTES 1. IF MIN COOLING CFM IS NOT SHOWN ON PLANS, THEN MIN COOLING CFM IS EQUAL TO 30% OF MAX COOLING CFM. 2. HEATING CFM IS EQUAL TO MIN COOLING CFM.
	DUCTWORK PLANS TAG / MAX COOLING CFM / MIN COOLING CFM
	PIPING PLANS TAG / GPM
	TAG EXAMPLES: DUCTWORK PLANS: TB1 / 500/200; TB1 / 500 — PIPING PLANS: TB1 / 0.5

Building Inspection Division
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Date: 11/15/19
Permit Number: BLD19-06035

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHTIECTURE
LICENSE NO. AA260000687

ENGINEERING
CA LIC. NO. 8115

www.aecom.com

REGISTRATION

JOHN TYE RECTOR
LICENSE
No. 53292
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

JOHN T. RECTOR, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 53292
08/22/19

John T Rector — John T Rector 2019.08.22 15:28:17 -04'00'

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JOHN T. RECTOR, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 53292 ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
	AUG 23, 2019	CONSTRUCTION DOCUMENTS
	MAY 31, 2019	35% DESIGN COMPLETION

PROJECT NUMBER

60601397

SHEET TITLE

HVAC LEGEND & NOTES

SHEET NUMBER

M0-0-01

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

Printed on ___% Post-Consumer Recycled Content Paper
©2016 AECOM Corporation