M0-0-10-HVAC SCHEDULES
Project Management Initials:
Designer: Designer Checker: Checker Approved: Approver ARCH E1 30"x42"

Building Inspection Division
City of Lakeland
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Date: 11/15/19
Permit Number: BLD19-06035

AIR HANDLING UNIT SCHEDULE

TAG	BASIS OF DESIGN: MANUFACTURER	MODEL	NOM. TONS	AIRFLOWS (CFM): SUPPLY MAX	SUPPLY MIN	OUTSIDE AIR	CHILLED WATER COOLING COIL: CAPACITY (MBH): SENSIBLE	TOTAL	EAT (F): DB	WB	LAT (F): DB	WB	CHILLED WATER TEMP (F): EWT	LWT	FLOW (GPM)	WATER PRESSURE DROP (FT H2O)	FACE VELOCITY (FPM)	AIRSIDE PRESSURE DROP (IN WG)	FILTRATION: PRE-FILTER	FINAL FILTER	FINAL VELOCITY (FPM)	SUPPLY FAN: HP	BHP	FLA	ESP (IN WG)	ELECTRICAL DATA: VOLTS	HZ	PHASES	OPERATING WEIGHT (LBS)
AHU-1-8	KREUGER	KAH	33	16945	5875	1725	358.7	390.9	73.5	59.4	53.9	51.0	42	56	55.8	9.4	3.0	0.36	MERV-8	MERV-13	452	20	18.34	24	3.00	480	60	3	4406
AHU-1-9	KREUGER	KAH	33.5	18960	6810	1925	397.8	398.5	73.3	59.7	53.9	51.0	42	56	56.9	4.5	2.2	0.33	MERV-8	MERV-13	474	25	22.68	30.4	3.25	480	60	3	4795
AHU-1-10	KREUGER	KAH	29	15360	4695	1400	325.8	346.2	73.5	59.3	53.9	51.0	42	56	49.5	9.0	2.9	0.32	MERV-8	MERV-13	461	20	19.59	25	3.50	480	60	3	3734
AHU-1-11	KREUGER	KAH	33	16385	5650	1650	345.7	392.0	73.4	59.7	53.9	51.0	42	56	56.0	9.7	3.0	0.36	MERV-8	MERV-13	492	25	21.64	29.9	3.50	480	60	3	3947
AHU-2-7	KREUGER	KAH	35	17920	6120	1725	379.8	418.8	73.5	59.7	53.9	51.0	42	56	59.8	12.3	3.4	0.36	MERV-8	MERV-13	488	25	22.35	29.9	3.00	480	60	3	4078
AHU-2-8	KREUGER	KAH	37.5	18885	6555	1875	397.2	445.7	73.4	59.6	53.9	51.0	42	56	63.7	15.0	3.6	0.34	MERV-8	MERV-13	472	30	23.99	35.4	3.25	480	60	3	4418
AHU-2-9	KREUGER	KAH	37.5	19495	6165	1575	418.0	446.2	73.8	59.5	53.9	51.0	42	56	63.7	15.5	3.7	0.35	MERV-8	MERV-13	487	30	26.42	35.4	3.50	480	60	3	4457
AHU-2-10	KREUGER	KAH	33	16525	5910	1700	347.9	391.7	73.4	59.7	53.9	51.0	42	56	56.0	10.0	3.1	0.37	MERV-8	MERV-13	496	25	21.95	29.9	3.50	480	60	3	3947
AHU-3-7	KREUGER	KAH	38.5	17790	6095	1725	420.2	459.0	75.8	60.4	53.9	51.0	42	56	65.6	14.0	3.6	0.35	MERV-8	MERV-13	485	25	22.04	29.9	3.00	480	60	3	4079
AHU-3-8	KREUGER	KAH	38	18910	6485	1875	405.1	453.7	73.7	59.8	53.9	51.0	42	56	64.8	15.5	3.7	0.34	MERV-8	MERV-13	473	25	24.03	29.9	3.25	480	60	3	4381
AHU-3-9	KREUGER	KAH	37.5	19400	6100	1575	421.5	449.7	74.0	59.6	53.9	51.0	42	56	64.2	16.0	3.8	0.35	MERV-8	MERV-13	485	25	24.76	30.4	3.50	480	60	3	4823
AHU-3-10	KREUGER	KAH	36.5	16765	5810	1700	389.3	434.6	75.4	60.4	53.9	51.0	42	56	62.1	12.6	3.4	0.32	MERV-8	MERV-13	457	25	21.80	29.9	3.50	480	60	3	4067

NOTES:
1. ALL AIR HANDLING UNITS TO BE PROVIDED WITH INTEGRAL BASE RAILS.
2. PROVIDE FLEXIBLE CONNECTION AT INLET OF ALL UNITS. PROVIDE FLEXIBLE CONNECTION AT DISCHARGE OF ALL UNITS.

ENERGY RECOVERY VENTILATOR SCHEDULE

TAG	BASIS OF DESIGN: MANUFACTURER	MODEL	NOM. TONS	AIRFLOWS (CFM): SUPPLY MAX	SUPPLY MIN	EXHAUST MAX	EXHAUST MIN	ENERGY RECOVERY WHEEL: SUMMER EAT (F) DB	SUMMER EAT (F) WB	SUMMER LAT (F) DB	SUMMER LAT (F) WB	WINTER EAT (F) DB	WINTER LAT (F) DB	CHILLED WATER COOLING COIL: CAPACITY (MBH): SENSIBLE	TOTAL	EAT (F): DB	WB	LAT (F): DB	WB	CHILLED WATER TEMP (F): EWT	LWT	FLOW (GPM)	WATER PRESSURE DROP (FT H2O)	AIRSIDE PRESSURE DROP (IN WG)	FILTRATION: PRE-FILTER	FINAL FILTER	SUPPLY FAN: HP	BHP	ESP (IN WG)	EXHAUST FAN: HP	BHP	ESP (IN WG)	ELECTRICAL DATA: VOLTS	HZ	PHASES	OPERATING WEIGHT (LBS)
ERV-4	VALENT	VPRE	44	10850	7200	9000	7200	81.9	78.6	77.5	69.8	37.7	59.7	263.7	526.4	77.5	69.8	55.0	54.5	42	56	75.2	3.6	0.5	MERV-8	MERV-13	5	3.7	2.00	5	3.6	2.5	480	60	3	7707
ERV-5	VALENT	VPRE	39	9600	1000	8000	1000	81.9	78.6	79.0	71.8	37.7	52.0	233.3	465.7	79.0	71.8	55.0	54.5	42	56	66.5	4.2	0.4	MERV-8	MERV-13	5	3.1	2.00	3	1.85	2.5	480	60	3	7815

NOTES:
1. PROVIDE UNITS WITH PRE-FABRICATED CURB AND SPRING ISOLATORS. INSTALL PER MANUFACTURER RECCOMENDATIONS.
2. ERV'S SHALL BE EQUIPPED WITH VARIABLE FREQUENCY DRIVES FOR THE SUPPLY AND EXHAUST FANS.
3. PROVIDE STAINLESS STEEL SLOPED DRAIN PAN WITH SIDE DRAIN THROUGH FRAME.
4. SUPPLY AND RETURN ROOF OPENINGS SHALL BE COORDINATED WITH DRAWING PRIOR TO ORDERING TO VERIFY CONFIGURATION.
5. PROVIDE UNIT WITH SINGLE POINT POWER CONNECTION. IN ADDITION PROVIDE A SEPARATE 120V POWER CONNECTION.

COOLING TOWER SCHEDULE

MARK	MANUFACTURER	MODEL	NO. CELLS	CAPACITY (TONS)	AIR DATA: MAX SUPPLY CFM	AIR TEMP WB (°F)	FAN DATA: QTY	HP	WATER DATA: FLOW (GPM)	WATER TEMP (F): EWT	LWT	VOLT./PH.
CT-3	EVAPCO	USS 29-4J28		650	145300	79	1	40	1950	85	95	480/3

NOTES:
1. PROVIDE UNIT WITH VARIABLE FREQUENCY DRIVES.
2. TOWER MANUFACTURER SHALL GUARANTEE IN WRITING THAT TOWER WILL PERFORM AS SCHEDULED.

PUMP SCHEDULE

MARK	BASIS OF DESIGN: MANUFACTURER	MODEL	SERVICE TEMP (°F)	GPM	TDH FT. W.G.	NPSHR (FT.) MAX	MOTOR RPM	FULL FLOW EFFICIENCY	VFD	BHP	N.O.C. HP	H.P.	VOLTS	HERTZ	PHASES
CHWPP-3	ARMSTRONG	4300	42	825	45	-	1200	85		12	15		480	60	3
CHWSP-1	ARMSTRONG	4300	42	825	90	-	1200	80		24	30		480	60	3
CWP-3	ARMSTRONG	4300	85	1950	50	8	1200	80		32	40		480	60	3

NOTES:
1. PROVIDE PUMPS WITH MULTI-PURPOSE VALVES.
2. PROVIDE SUCTION GUIDES TO PRIMARY AND SECONDARY PUMPS.
3. PROVIDE INVERTER DUTY MOTORS FOR SECONDARY PUMPS.

WATER COOLED CENTRIFUGAL CHILLER SCHEDULE

MARK	BAISIS OF DESIGN: MANUFACTURER	MODEL	CAPACITY (TONS)	EFFICIENCY (KW/TON) 100%	NPLV	ELECTRICAL SERVICE (VOLT/PH)	REFRIGERANT	EVAPORATOR: GPM (OPR)	CHILLED WATER TEMP. - ENT/LVG (°F)	NO. OF PASSES	WPD (FT-W.G.) MAX.	FOUL FACTOR (SQ.FT. °F HR / BTU)	CONDENSER: GPM (OPR)	COND. WATER TEMP. - ENT/LVG (°F)	NO. OF PASSES	WPD (FT-W.G.) MAX.	FOUL FACTOR (SQ.FT. °F HR / BTU)
CH-3	YORK	YK CENTRIFUGAL	480	0.5864	0.3659	480/3	R-134A	825	56/42	3	19.6	0.0001	1032	85/95	3	19.6	0.00025

NOTES:
1. MOUNT CHILLER ON NEOPRENE PAD.
2. EQUIP CHILLER WITH VARIABLE FREQUENCY DRIVE.

FAN COIL UNIT SCHEDULE

TAG	BASIS OF DESIGN: MANUFACTURER	MODEL	AIRFLOWS (CFM): SUPPLY MAX	SUPPLY MIN	CHILLED WATER COOLING COIL: CAPACITY (MBH): SENSIBLE	TOTAL	EAT (F): DB	WB	LAT (F): DB	WB	CHILLED WATER TEMP (F): EWT	LWT	FLOW (GPM)	WATER PRESSURE DROP (FT H2O)	AIRSIDE PRESSURE DROP (IN WG)	SUPPLY FAN: HP	FLA	ESP (IN WG)	ELECTRICAL DATA: VOLTS	HZ	PHASES
FCU-1	PRICE	BCH	1000	600	14.7	18.0	80	67	55	54.5	45	55	3.58	1.07	0.4	1/2	1.1	0.4	460	60	3
FCU-2	PRICE	BCH	1400	900	26.2	35.0	80	67	55	54.5	45	55	6.94	3.40	0.4	1/2	1.1	0.4	460	60	3
FCU-3	PRICE	BCH	1000	600	14.7	18.0	80	67	55	54.5	45	55	3.58	1.07	0.4	1/2	1.1	0.4	460	60	3
FCU-4	PRICE	BCH	1400	900	26.2	35.0	80	67	55	54.5	45	55	6.94	3.40	0.4	1/2	1.1	0.4	460	60	3
FCU-5	PRICE	BCH	1000	600	14.7	18.0	80	67	55	54.5	45	55	3.58	1.07	0.4	1/2	1.1	0.4	460	60	3
FCU-6	PRICE	BCH	1400	900	26.2	35.0	80	67	55	54.5	45	55	6.94	3.40	0.4	1/2	1.1	0.4	460	60	3

NOTES:
1. FAN COILS SHALL BE FURNISHED WITH FACTORY CONTROLS
2. PROVIDE PLENUM AND FILTER.
3. PROVIDE EMERGENCY DRAIN PAN.

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHTIECTURE
LICENSE NO. AA260000687

ENGINEERING
CA LIC. NO. 8115

www.aecom.com

REGISTRATION

JOHN TYE RECTOR
LICENSE
No. 53292
STATE OF FLORIDA
PROFESSIONAL ENGINEER

JOHN T. RECTOR, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 53292
08/22/19

John T Rector
John T Rector
2019.08.22
15:28:57 -04'00'

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JOHN T. RECTOR, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 53292 ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
	AUG 23, 2019	CONSTRUCTION DOCUMENTS
	MAY 31, 2019	35% DESIGN COMPLETION

PROJECT NUMBER

60601397

SHEET TITLE

HVAC SCHEDULES

SHEET NUMBER

M0-0-10

Last Plotted: 8/22/2019 3:12:58 PM
Filename: BM-300100060139 P-Publix HQ\60601397_Publix HQ_MECH_R2019.rvt

Printed on ___% Post-Consumer Recycled Content Paper

©2016 AECOM Corporation