M0-0-20-HVAC SCHEDULES
Project Management Initials: Designer: Designer Checker: Checker Approved: Approver ARCH E1 30"x42"

VARIABLE AIR VOLUME UNI...

Mark	INLET SIZE	AIRFLOWS MAX CFM	AIRFLOWS MIN CFM
VAV 1-8-1	10	1125	210
VAV 1-8-2	8	625	125
VAV 1-8-3	4	200	45
VAV 1-8-4	6	600	65
VAV 1-8-5	4	375	45
VAV 1-8-6	4	375	45
VAV 1-8-7	4	90	45
VAV 1-8-8	4	270	45
VAV 1-8-9	4	180	45
VAV 1-8-10	4	270	45
VAV 1-8-11	4	375	45
VAV 1-8-12	8	750	125
VAV 1-8-13	4	115	45
VAV 1-8-14	4	145	45
VAV 1-8-15	4	115	45
VAV 1-8-16	4	145	45
VAV 1-8-17	6	500	65
VAV 1-8-18	4	115	45
VAV 1-8-19	4	50	45
VAV 1-8-20	4	120	45
VAV 1-8-21	4	300	45
VAV 1-8-22	4	265	45
VAV 1-9-1	4	340	45
VAV 1-9-2	4	80	45
VAV 1-9-3	4	220	45
VAV 1-9-4	4	150	45
VAV 1-9-5	4	215	45
VAV 1-9-6	4	215	45
VAV 1-9-7	4	225	45
VAV 1-9-8	4	150	45
VAV 1-9-9	4	150	45
VAV 1-9-10	4	120	45
VAV 1-9-11	4	260	45
VAV 1-9-12	4	120	45
VAV 1-9-13	4	50	45
VAV 1-9-14	4	120	45
VAV 1-9-15	4	120	45
VAV 1-9-16	4	50	45
VAV 1-9-17	4	120	45
VAV 1-9-18	8	840	125
VAV 1-9-19	8	840	125
VAV 1-9-20	8	840	125
VAV 1-9-21	6	420	65
VAV 1-9-22	4	50	45
VAV 1-9-23	4	50	45
VAV 1-9-24	4	50	45
VAV 1-9-25	4	120	45
VAV 1-9-26	6	420	65
VAV 1-9-27	4	120	45
VAV 1-9-28	4	55	45
VAV 1-9-29	4	120	45
VAV 1-9-30	8	840	125
VAV 1-9-31	4	120	45
VAV 1-9-32	4	55	45
VAV 1-9-33	4	120	45
VAV 1-10-1	8	900	125
VAV 1-10-2	4	120	45
VAV 1-10-3	4	55	45
VAV 1-10-4	4	120	45
VAV 1-10-6	4	100	45
VAV 1-10-7	4	120	45
VAV 1-10-8	4	120	45
VAV 1-10-9	4	160	45
VAV 1-10-10	8	900	125
VAV 1-10-11	4	120	45
VAV 1-10-12	4	55	45
VAV 1-10-13	4	120	45
VAV 1-10-14	8	900	125
VAV 1-10-15	8	565	125
VAV 1-10-16	8	600	125
VAV 1-10-17	10	1645	210
VAV 1-10-18	10	1190	210
VAV 1-10-19	4	350	45
VAV 1-11-1	6	495	65
VAV 1-11-2	6	495	65
VAV 1-11-3	8	990	125
VAV 1-11-4	4	120	45
VAV 1-11-5	4	120	45
VAV 1-11-6	4	120	45
VAV 1-11-7	4	200	45
VAV 1-11-8	8	990	125
VAV 1-11-9	4	120	45
VAV 1-11-10	4	55	45
VAV 1-11-11	4	55	45
VAV 1-11-12	4	55	45
VAV 1-11-13	4	290	45
VAV 1-11-14	4	290	45
VAV 1-11-15	4	260	45
VAV 1-11-16	4	80	45
VAV 1-11-17	4	55	45
VAV 1-11-18	4	55	45
VAV 1-11-19	4	55	45
VAV 1-11-20	4	120	45
VAV 1-11-21	8	990	125
VAV 1-11-22	4	200	45
VAV 1-11-23	6	495	65
VAV 1-11-24	8	990	125
VAV 2-7-1	8	840	125
VAV 2-7-2	4	120	45
VAV 2-7-3	4	55	45
VAV 2-7-4	4	120	45
VAV 2-7-5	6	420	65
VAV 2-7-6	8	560	125

VARIABLE AIR VOLUME UNI...

Mark	INLET SIZE	AIRFLOWS MAX CFM	AIRFLOWS MIN CFM
VAV 2-7-7	6	420	65
VAV 2-7-8	6	420	65
VAV 2-7-9	6	420	65
VAV 2-7-10	4	200	45
VAV 2-7-11	4	105	45
VAV 2-7-12	4	300	45
VAV 2-7-13	4	130	45
VAV 2-7-14	4	270	45
VAV 2-7-15	6	420	65
VAV 2-7-16	10	840	210
VAV 2-7-17	4	120	45
VAV 2-7-18	4	120	45
VAV 2-7-19	4	145	45
VAV 2-7-20	4	145	45
VAV 2-7-21	4	310	45
VAV 2-7-22	8	560	125
VAV 2-7-23	4	120	45
VAV 2-7-24	4	55	45
VAV 2-7-25	4	120	45
VAV 2-7-26	4	275	45
VAV 2-8-1	4	330	45
VAV 2-8-2	4	80	45
VAV 2-8-3	4	220	45
VAV 2-8-4	4	140	45
VAV 2-8-5	4	145	45
VAV 2-8-6	4	220	45
VAV 2-8-7	4	225	45
VAV 2-8-8	4	150	45
VAV 2-8-9	4	150	45
VAV 2-8-10	4	120	45
VAV 2-8-11	4	260	45
VAV 2-8-12	4	120	45
VAV 2-8-13	4	50	45
VAV 2-8-14	4	120	45
VAV 2-8-15	4	120	45
VAV 2-8-16	4	50	45
VAV 2-8-17	4	120	45
VAV 2-8-18	8	930	125
VAV 2-8-19	8	930	125
VAV 2-8-20	8	930	125
VAV 2-8-21	6	465	65
VAV 2-8-22	4	50	45
VAV 2-8-23	4	50	45
VAV 2-8-24	4	50	45
VAV 2-8-25	4	120	45
VAV 2-8-26	6	465	65
VAV 2-8-27	4	120	45
VAV 2-8-28	4	55	45
VAV 2-8-29	4	120	45
VAV 2-8-30	6	465	65
VAV 2-8-31	4	50	45
VAV 2-8-32	4	50	45
VAV 2-8-33	4	50	45
VAV 2-8-34	4	120	45
VAV 2-9-1	8	810	125
VAV 2-9-3	4	100	45
VAV 2-9-4	4	120	45
VAV 2-9-5	4	120	45
VAV 2-9-6	8	810	125
VAV 2-9-7	4	375	45
VAV 2-9-8	4	160	45
VAV 2-9-9	6	405	65
VAV 2-9-10	4	120	45
VAV 2-9-11	4	55	45
VAV 2-9-12	4	120	45
VAV 2-9-13	6	405	65
VAV 2-9-14	8	565	125
VAV 2-9-15	4	120	45
VAV 2-9-16	4	55	45
VAV 2-9-17	4	120	45
VAV 2-9-18	6	405	65
VAV 2-9-19	8	620	125
VAV 2-9-20	4	360	45
VAV 2-9-21	8	620	125
VAV 2-10-1	6	460	65
VAV 2-10-2	6	460	65
VAV 2-10-3	6	460	65
VAV 2-10-4	8	920	125
VAV 2-10-5	4	120	45
VAV 2-10-6	4	120	45
VAV 2-10-7	4	120	45
VAV 2-10-8	4	200	45
VAV 2-10-9	8	920	125
VAV 2-10-10	4	120	45
VAV 2-10-11	4	55	45
VAV 2-10-12	4	55	45
VAV 2-10-13	4	55	45
VAV 2-10-14	4	280	45
VAV 2-10-15	4	280	45
VAV 2-10-16	4	280	45
VAV 2-10-17	4	80	45
VAV 2-10-18	4	120	45
VAV 2-10-19	4	55	45
VAV 2-10-20	4	120	45
VAV 2-10-21	8	920	125
VAV 2-10-22	4	200	45
VAV 2-10-23	6	460	65
VAV 2-10-24	8	920	125
VAV 3-7-1	8	900	125
VAV 3-7-2	4	125	45
VAV 3-7-3	4	55	45
VAV 3-7-4	4	125	45
VAV 3-7-5	6	450	65

VARIABLE AIR VOLUME UNI...

Mark	INLET SIZE	AIRFLOWS MAX CFM	AIRFLOWS MIN CFM
VAV 3-7-6	8	600	125
VAV 3-7-7	6	450	65
VAV 3-7-8	6	450	65
VAV 3-7-9	6	450	65
VAV 3-7-10	4	200	45
VAV 3-7-11	4	105	45
VAV 3-7-12	4	310	45
VAV 3-7-13	4	130	45
VAV 3-7-14	4	290	45
VAV 3-7-15	6	450	65
VAV 3-7-16	6	450	65
VAV 3-7-17	6	450	65
VAV 3-7-18	4	125	45
VAV 3-7-19	4	140	45
VAV 3-7-20	4	125	45
VAV 3-7-21	4	140	45
VAV 3-7-22	4	300	45
VAV 3-7-23	6	450	65
VAV 3-7-24	4	125	45
VAV 3-7-25	4	50	45
VAV 3-7-26	4	125	45
VAV 3-7-27	4	265	45
VAV 3-8-1	4	350	45
VAV 3-8-2	4	85	45
VAV 3-8-3	4	230	45
VAV 3-8-4	4	155	45
VAV 3-8-5	4	160	45
VAV 3-8-6	4	230	45
VAV 3-8-7	4	240	45
VAV 3-8-8	4	155	45
VAV 3-8-9	4	155	45
VAV 3-8-10	4	120	45
VAV 3-8-11	4	260	45
VAV 3-8-12	4	125	45
VAV 3-8-13	4	50	45
VAV 3-8-14	4	125	45
VAV 3-8-15	4	125	45
VAV 3-8-16	4	50	45
VAV 3-8-17	4	125	45
VAV 3-8-18	8	990	125
VAV 3-8-19	8	990	125
VAV 3-8-20	8	990	125
VAV 3-8-21	6	495	65
VAV 3-8-22	4	50	45
VAV 3-8-23	4	50	45
VAV 3-8-24	4	50	45
VAV 3-8-25	4	125	45
VAV 3-8-26	6	495	65
VAV 3-8-27	4	125	45
VAV 3-8-28	4	55	45
VAV 3-8-29	4	125	45
VAV 3-8-30	6	495	65
VAV 3-8-31	4	50	45
VAV 3-8-32	4	50	45
VAV 3-8-33	4	50	45
VAV 3-8-34	4	125	45
VAV 3-9-1	8	870	125
VAV 3-9-3	4	110	45
VAV 3-9-4	4	125	45
VAV 3-9-5	4	125	45
VAV 3-9-6	8	870	125
VAV 3-9-7	6	435	65
VAV 3-9-8	4	165	45
VAV 3-9-9	6	435	65
VAV 3-9-10	4	125	45
VAV 3-9-11	4	55	45
VAV 3-9-12	4	125	45
VAV 3-9-13	6	435	65
VAV 3-9-14	8	565	125
VAV 3-9-15	4	125	45
VAV 3-9-16	4	55	45
VAV 3-9-17	4	125	45
VAV 3-9-18	6	435	65
VAV 3-9-19	8	580	125
VAV 3-9-20	4	360	45
VAV 3-9-21	8	580	125
VAV 3-10-1	6	495	65
VAV 3-10-2	6	495	65
VAV 3-10-3	6	495	65
VAV 3-10-4	8	990	125
VAV 3-10-5	4	125	45
VAV 3-10-6	4	125	45
VAV 3-10-7	4	125	45
VAV 3-10-8	4	200	45
VAV 3-10-9	8	990	45
VAV 3-10-10	4	125	45
VAV 3-10-11	4	55	45
VAV 3-10-12	4	125	45
VAV 3-10-13	4	290	45
VAV 3-10-14	4	290	45
VAV 3-10-15	4	290	45
VAV 3-10-16	4	120	45
VAV 3-10-17	4	125	45
VAV 3-10-18	4	55	45
VAV 3-10-19	4	125	45
VAV 3-10-20	8	990	125
VAV 3-10-21	4	200	45
VAV 3-10-22	6	495	65
VAV 3-10-23	8	990	125

1. EACH VAV SHALL BE CONTROLLED BY A WIRED THERMOSTAT. THERMOSTAT WIRE MUST BE INSTALLED WITH ENOUGH SLACK TO FACILITATE MOVING BETWEEN WALLS.

FAN POWERED UNIT SCHEDULE

Mark	INLET SIZE	COOLING AIRFLOWS MAX CFM	COOLING AIRFLOWS MIN CFM	FAN CFM	HEATING HEATING CAPACITY (KW)	HEATING FAN POWER (HP)	HEATING ELECTRICAL CHARACTERISTICS (V/PH/HZ)
FPU 1-8-1	14	3375	430	430	7.5	1/2	480/3/60
FPU 1-8-2	14	3355	430	430	7.5	1/2	480/3/60
FPU 1-8-3	14	2920	430	430	7.5	1/2	480/3/60
FPU 1-9-1	16	3760	575	575	10	3/4	480/3/60
FPU 1-9-2	14	3450	430	430	7.5	1/2	480/3/60
FPU 1-9-3	16	3985	575	575	10	3/4	480/3/60
FPU 1-10-1	12	2065	300	300	5	1/2	480/3/60
FPU 1-10-2	12	2235	300	300	5	1/2	480/3/60
FPU 1-10-3	12	2420	300	300	5	1/2	480/3/60
FPU 1-11-1	14	3345	430	430	7.5	1/2	480/3/60
FPU 1-11-2	16	5345	575	575	10	3/4	480/3/60
FPU 2-7-1	14	3635	430	430	7.5	1/2	480/3/60
FPU 2-7-2	14	3675	430	430	7.5	1/2	480/3/60
FPU 2-7-3	14	3000	430	430	7.5	1/2	480/3/60
FPU 2-8-1	16	3845	575	575	10	3/4	480/3/60
FPU 2-8-2	14	3400	430	430	7.5	1/2	480/3/60
FPU 2-8-3	16	4000	575	575	10	3/4	480/3/60
FPU 2-9-1	12	2065	300	300	5	1/2	480/3/60
FPU 2-9-2	14	2910	430	430	7.5	1/2	480/3/60
FPU 2-9-3	16	4410	575	575	10	3/4	480/3/60
FPU 2-9-4	14	3145	430	430	7.5	1/2	480/3/60
FPU 2-10-1	14	3440	430	430	7.5	1/2	480/3/60
FPU 2-10-2	16	5325	575	575	10	3/4	480/3/60
FPU 3-7-1	14	3425	430	430	7.5	1/2	480/3/60
FPU 3-7-2	14	3600	430	430	7.5	1/2	480/3/60
FPU 3-7-3	14	2930	430	430	7.5	1/2	480/3/60
FPU 3-8-1	14	3615	430	430	7.5	1/2	480/3/60
FPU 3-8-2	14	3330	430	430	7.5	1/2	480/3/60
FPU 3-8-3	16	3915	575	575	10	3/4	480/3/60
FPU 3-9-1	12	1940	300	300	5	1/2	480/3/60
FPU 3-9-2	14	2880	430	430	7.5	1/2	480/3/60
FPU 3-9-3	16	4315	575	575	10	3/4	480/3/60
FPU 3-9-4	14	3065	430	430	7.5	1/2	480/3/60
FPU 3-10-1	14	3240	430	430	7.5	1/2	480/3/60
FPU 3-10-2	16	5210	575	575	10	3/4	480/3/60

1. EACH FPU SHALL BE CONTROLLED BY A WIRED THERMOSTAT. THERMOSTAT WIRE MUST BE INSTALLED WITH ENOUGH SLACK TO FACILITATE MOVING BETWEEN WALLS.

ELECTRICAL DUCT HEATER SCHEDULE

MARK	LOCATION	AHU/FAN NO.	AIRFLOW MIN. CFM	COIL FACE MIN. VEL. (FPM)	HEATING CAP KW	NO. OF STEPS	VOLT./PH.	DUCT SIZE WIDTH (IN)	DUCT SIZE HEIGHT (IN)
EDH-1-7	MECH RM 1-134	AHU 1-8	1845		45		480/3/60		
EDH-1-8	MECH RM 1-134	AHU 1-9	2030		45		480/3/60		
EDH-1-9	MECH RM 1-165	AHU 1-10	1470		45		480/3/60		
EDH-1-10	MECH RM 1-165	AHU 1-11	1675		45		480/3/60		
EDH-2-7	MECH RM 2-134	AHU 2-7	1795		45		480/3/60		
EDH-2-8	MECH RM 2-134	AHU 2-8	1975		45		480/3/60		
EDH-2-9	MECH RM 2-165	AHU 2-9	1585		45		480/3/60		
EDH-2-10	MECH RM 2-165	AHU 2-10	1760		45		480/3/60		
EDH-3-7	MECH RM 3-134	AHU 3-7	1825		45		480/3/60		
EDH-3-8	MECH RM 3-134	AHU 3-8	1985		45		480/3/60		
EDH-3-9	MECH RM 3-165	AHU 3-9	1585		45		480/3/60		
EDH-3-10	MECH RM 3-165	AHU 3-10	1735		45				

EXHAUST FAN SCHEDULE

Mark	TYPE	DRIVE TYPE	CFM	E.S.P. (IN W.G.)	FAN RPM	FAN POWER (HP)	ELECTRICAL CHARACTERISTICS (V/PH/HZ)
EF-1	PROPELLER	DIRECT	2,000	0.375	1,688	0.3	208/1/60

Building Inspection Division
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Lakeland
Date: 11/15/19
Permit Number: BLD19-06035

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHTIECTURE
LICENSE NO. AA260000687

ENGINEERING
CA LIC. NO. 8115

www.aecom.com

REGISTRATION

JOHN TYE RECTOR LICENSE No. 53292 STATE OF FLORIDA PROFESSIONAL ENGINEER

JOHN T. RECTOR, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 53292
08/22/19

John T Rector
John T Rector
2019.08.22
15:29:34 -04'00'

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JOHN T. RECTOR, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 53292 ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
	AUG 23, 2019	CONSTRUCTION DOCUMENTS
	MAY 31, 2019	35% DESIGN COMPLETION

PROJECT NUMBER

60601397

SHEET TITLE

HVAC SCHEDULES

SHEET NUMBER

M0-0-20

©2016 AECOM Corporation

Last Plotted: 8/22/2019 3:13:09 PM
Filename: Bldl 360\60601397-Publix HQ\60601397_Publix HQ_MECH_R2019-v1

Printed on ___% Post-Consumer Recycled Content Paper