PLUMBING GENERAL NOTES

1. VISIT THE SITE OF THE WORK TO GAIN AN ACCEPTABLE KNOWLEDGE OF CONDITIONS AFFECTING THE EXECUTION OF THE WORK. AFTER VISITING THE SITE, REQUEST SUCH INFORMATION AND/OR CLARIFICATIONS AS NECESSARY TO FULLY UNDERSTAND THE WORK REQUIRED AND TO PROPERLY ESTIMATE COSTS.
2. REVIEW ALL DRAWINGS TO VERIFY EXTENT AND SCHEDULING OF ALL DEMOLITION ACTIVITIES PRIOR TO COMMENCING DEMOLITION WORK. FIELD VERIFY ALL SIZES AND LOCATIONS OF EXISTING DUCTWORK AND PIPING TO REMAIN. NOTIFY ARCHITECT/ENGINEER OF DEVIATIONS WHICH AFFECT RENOVATION WORK PRIOR TO PROCEEDING WITH THE WORK.
3. ITEMS NOTED TO BE DEMOLISHED INCLUDES BUT IS NOT LIMITED TO ALL ASSOCIATED COMPONENTS, CONTROL WIRING, PIPING, DUCTWORK, ELECTRICAL CONNECTIONS, SUPPORTS, INSULATION, ETC. COORDINATE WITH OTHER TRADES AS REQUIRED.
4. ALL WORK IS TO BE PHASED AS INDICATED ON THE ARCHITECTURAL DRAWINGS. COORDINATE PHASING OF ALL DEMOLITION, RENOVATION, AND NEW WORK WITH OTHER TRADES. CLOSELY COORDINATE PHASING OF WORK WITHIN CORRIDORS WITH THE OWNER. CORRIDORS CANNOT BE COMPLETELY CLOSED OFF TO PEDESTRIAN TRAFFIC. TO ACCOMMODATE PHASING, CORRIDOR ACCESS WORK MAY NEED TO BE PERFORMED DURING OFF PEAK PERIODS. PRIOR TO MOVING ON TO THE NEXT PHASE, ALL WORK IN PREVIOUSLY PHASED AREAS MUST BE COMPLETE AND OPERATIONAL.
5. ENSURE THAT THE WORK WILL NOT INTERFERE OR INTERRUPT SERVICES TO AREAS OUTSIDE OF THE DESIGNATED CONTRACT AREAS. SCHEDULE ALL WORK AS TO CAUSE MINIMAL SERVICE INTERRUPTIONS FOR THE OWNER. UNAVOIDABLE INTERRUPTIONS ARE TO BE SCHEDULED WITH THE OWNER NO LESS THAN TWO WEEKS PRIOR TO THEIR EXPECTED COMMENCEMENT. WORK SHALL BE PERFORMED AT SUCH TIMES AS DIRECTED BY THE OWNER AND, IF POSSIBLE, ARE TO OCCUR DURING OFF PEAK PERIODS.
6. THE CONTRACTOR IS TO VERIFY THE EXACT SERVICE OF ANY EXISTING PIPING OR DUCTWORK PRIOR TO INSTALLING ANY NEW CONNECTIONS. ANY DISCREPANCIES BETWEEN THE CONSTRUCTION DOCUMENTS OR THE DESIGN INTENT AND ACTUAL CONDITIONS ARE TO BE BROUGHT TO THE ATTENTION OF THE ENGINEER IMMEDIATELY, PRIOR TO FABRICATION OR INSTALLATION.
7. CONTRACTOR SHALL REMOVE AND REPLACE EXISTING LAY-IN CEILING GRID AND TILES AS NECESSARY TO COMPLETE ABOVE CEILING WORK. RETURN CEILING TO ORIGINAL CONDITION FOLLOWING COMPLETION OF CONSTRUCTION.
8. PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE SYSTEMS AS INDICATED ON THE DRAWINGS AND SPECIFICATIONS. INCLUDE ALL NECESSARY AND APPLICABLE APPURTENANCES, WHETHER INDICATED OR NOT.
9. ANY DEVIATIONS FROM THE BASIS OF DESIGN THAT REQUIRE ADDITIONAL PROVISIONS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
10. COORDINATE THE EXACT REQUIREMENTS AND LOCATION OF WORK WITH THE WORK OF OTHER TRADES PRIOR TO FABRICATION AND INSTALLATION. PROVIDE ADDITIONAL OFFSETS AND SECTIONS IN PIPING REQUIRED TO MEET THE APPLICABLE JOB CONDITION REQUIREMENTS. VERIFY JOB SITE ELEVATIONS, DIMENSIONS, AND CONDITIONS, PRIOR TO FABRICATION OR INSTALLATION OF THE WORK. COORDINATE EXACT ROUTING OF PIPING WITH OTHER TRADES SO THAT NO CONFLICTS OCCUR WITH DUCTWORK, PIPING, LIGHTS, STRUCTURE, ETC. PROVIDE ALL PERTINENT DATA CONCERNING THE LOCATION, DIMENSIONS, ETC., OF THE PLUMBING EQUIPMENT THAT REQUIRES BASES, CURBS AND SUPPORTS TO THE APPROPRIATE TRADES.
11. WHERE CEILINGS ARE INDICATED, ALL PIPES SHALL BE RAN ABOVE CEILING. IN EXPOSED CONDITIONS, INSTALL PIPING TIGHT TO THE BOTTOM OF STRUCTURE.
12. ALL HORIZONTAL DRAINAGE PIPING SHALL BE INSTALLED AT 1/8" PER FOOT SLOPE FOR PIPES 3" OR LARGER AND AT 1/4" PER FOOT FOR 2-1/2" AND SMALLER PIPES.
13. ALL ITEMS THAT REQUIRE MAINTENANCE OR ADJUSTMENT MUST BE INSTALLED IN ACCESSIBLE LOCATIONS. PROVIDE AN APPROPRIATELY SIZED ACCESS DOOR AS REQUIRED.
14. ALL SEALS, BEARINGS, PACKINGS, AND ACCESSORIES FOR ALL EQUIPMENT AND PIPING SPECIALTIES SHALL BE SUITABLE FOR THE CONTINUOUS OPERATIONAL TEMPERATURES, PRESSURES AND CHARACTERISTICS, OF THE SYSTEM THEY SERVE.
15. EACH TRADE SHALL PAY THE GENERAL CONTRACTOR TO PATCH FLOOR SLAB AND WALL PENETRATIONS TO MATCH EXISTING WHERE THEIR PIPING, DUCT OR EQUIPMENT IS BEING REMOVED OR INSTALLED.
16. INSTALL ALL WORK TO COMPLY WITH ALL LAWS, REGULATIONS, CODES, AND STANDARDS (FEDERAL, STATE, AND LOCAL), AS ADOPTED BY THE AGENCIES HAVING JURISDICTION, INCLUDING REASONABLY ANTICIPATED REVISIONS BASED ON EMERGING TRENDS IN BUILDING REGULATIONS. WHERE ANY OF THESE DIFFER, THE MOST STRINGENT SHALL APPLY.
17. CONTRACT DOCUMENTS FOR PLUMBING WORK ARE SCHEMATIC IN NATURE AND ARE INTENDED TO CONVEY SCOPE AND GENERAL ARRANGEMENT ONLY.
18. ALL ROOFING MODIFICATIONS SHALL BE DONE BY OWNER'S ROOFING VENDOR TO MAINTAIN ANY AND ALL WARRANTIES. COST TO BE INCLUDED IN THIS CONTRACT UNLESS SPECIFICALLY INCLUDED IN GENERAL TRADES CONTRACTOR'S SCOPE OF WORK.
19. INSULATE PIPING WHERE EXISTING INSULATION HAS BEEN DAMAGED AND/OR REMOVED IN THE PERFORMANCE OF WORK FOR THIS PROJECT.
20. FOR RENOVATION WORK, IT IS PROHIBITED TO SUSPEND NEW WORK FROM THE EXISTING FLOOR SLAB OR ROOF DECK.
21. ALL SANITARY AND DOMESTIC WATER SUPPLY PIPING SHALL BE TESTED FOR LEAKS BEFORE PIPING IS CONCEALED OR CONNECTED TO EQUIPMENT AND PLUMBING FIXTURES. ALL DOMESTIC WATER PIPING SHALL BE DISINFECTED BY INTRODUCING A SOLUTION OF CALCIUM HYPOCHLORITE OF 50 PPM OF CHLORIDE AND AS PER AWWA STANDARDS AND SHALL MEET THE REQUIREMENTS OF THE LOCAL JURISDICTION.
22. INSTALL EQUIPMENT, MATERIALS, ETC. IN STRICT ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND DIRECTION. PROVIDE STRAIGHT INLET AND OUTLET PIPES BASED ON MANUFACTURER'S RECOMMENDATIONS. IF IN CONFLICT WITH THE DESIGN INDICATED HEREIN, ADVISE THE ENGINEERS PRIOR TO INSTALLATION FOR CLARIFICATION.
23. CONTRACTOR SHALL FIRE PROTECT AND SEAL ALL OPENINGS AND PIPE PENETRATIONS THRU FIRE RATED WALLS AND CEILINGS. MATERIALS AND METHODS FOR FIRE RATING SHALL BE APPROVED BY THE LOCAL BUILDING CONTROL DIVISION.
24. PROVIDE AUTOMATIC TRAP PRIMER TO EVERY FLOOR DRAIN AND FLOOR SINK.
25. RESEALS SHALL BE FED BY A WATER CLOSET FLUSH VALVE TAIL PIECE OR SAFE WASTED FROM AN ELECTRIC WATER COOLER OR DRINKING FOUNTAIN. MECHANICAL AUTOMATIC RESEALERS SHALL BE USED WHERE NO SUITABLE WATER CLOSET, ELECTRIC WATER COOLER OR DRINKING FOUNTAIN IS WITHIN 30 FEET.
26. LAVATORY VALVES SHALL BE SLOW ACTING AND SELF CLOSING. SEE SPECIFIATIONS FOR COMPLETE INFORMATION.
27. CONTRACTOR SHALL VERIFY DEPTHS AND LOCATIONS OF CONNECTION POINTS WITH EXISTING PRESSURE LINES AND DRAINAGE LINES BEFORE STARTING WORK.
28. ALL EXPOSED TRIM SHALL BE CHROME PLATED FINISH FOR ALL WATER SUPPLY AND WASTE ASSEMBLIES.
29. FOR EXACT LOCATION OF ALL AREA DRAINS (AD-), ROOF DRAINS (RD-), AND EMERGENCY OVERFLOW DRAINS (OFD-) REFER TO THE ARCHITECTURAL DRAWINGS.
30. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING THE BACKFLOW PREVENTOR REQUIRED TO THE WATER SUPPLY LINE OF THE VENDING MACHINES, ICE MAKER, COFFEE MAKER OR ANY OTHER EQUIPMENT REQUIRING SPECIAL PROTECTION BY THE LOCAL AUTHORITIES.
31. INVERT ELEVATIONS SHOWN ON PLANS ARE FOR REFERENCE ONLY. THE CONTRACTOR MUST VERIFY AND COORDINATE ALL SANITARY AND STORM INVERT ELEVATIONS WITH THE SITE UTILITIES PLAN AND CIVIL ENGINEER.
32. PLUMBING FIXTURES SHALL BE AS SPECIFIED AND SHALL BE FURNISHED AND INSTALLED BY THIS CONTRACTOR. FIXTURES SHALL BE COMPLETE WITH DRAINS, TRAPS, SUPPLIES, AND ANY OTHER ACCESSORIES REQUIRED.
33. INSTALL NO PIPING, CONDUIT, DUCTWORK, ETC., IN A LOCATION OR IN A MANNER THAT WILL ALLOW FREEZING AND/OR THE COLLECTION OF CONDENSATION.
34. ALL SUPPORTS FOR EQUIPMENT AND PIPING SYSTEMS, DEVICES SHALL BE FROM THE BUILDING STRUCTURE. SUPPORT FROM STRUCTURAL BRIDGING IS UNACCEPTABLE.

PLUMBING ABBREVIATIONS

NOTE: NOT ALL ABBREVIATIONS MAY BE USED.

ABBREVIATION	DESCRIPTION
A/E	ARCHITECT / ENGINEER
AD	ACCESS DOOR
AFF	ABOVE FINSED FLOOR
AFG	ABOVE FINISHED GRADE
AMB	AMBIENT
APPROX	APPROXIMATE
ARCH	ARCHITECTURE
ASHRAE	AMERICAN SOCIETY OF HEATING, REFRIGERATION, AIR CONDITIONING ENGINEERS
ASME	AMERICAN SOCIETY OF MECHANICAL ENGINEERS
ASPE	AMERICAN SOCIETY OF PLUMBING ENGINEERS
BFP	BLACKFLOW PREVENTER
BHP	BRAKE HORSEPOWER
BLDG	BUILDING
BTUH	BRITISH THERMAL UNITS PER HOUR
CI	CAST IRON
CL	CENTERLINE
DN	DOWN
DSN	DOWN SPOUT NOZZLE
DWG	DRAWING
DWV	DRAIN WASTE VENT
EFF	EFFICIENCY
EL	ELEVATION
FFE	FINISHED FLOOR ELEVATION
FLA	FULL LOAD AMPS
FT	FEET
FU	FIXTURE UNIT
GAL	GALLON
GPD	GALLONS PER DAY
GPH	GALLONS PER HOUR
GPM	GALLONS PER MINUTE
HP	HORSEPOWER
INV EL	INVERT ELEVATION
KW	KILOWATT
LF	LINEAR FEET
MAV	MANUAL AIR VENT
MBH	THOUSAND BTUH
MCA	MINIMUM CIRCUIT AMPACITY
MCF	THOUSAND CUBIC FEET
MECH	MECHANICAL
MFR	MANUFACTURER
MH	MANHOLE
MOCP	MAXIMUM OVER CURRENT PROTECTION
MOU	MEMORANDUM OF UNDERSTANDING
N/A	NOT APPLICABLE
NC	NORMALLY CLOSED
NO	NORMALLY OPEN
NPSH	NET POSITIVE SUCTION HEAD
NTS	NOT TO SCALE
OD	OUTSIDE DIAMETER
PD	PRESSURE DROP
PDI	PLUMBING AND DRAINAGE INSTITUTE
PPM	PARTS PER MILLION
PRV	PRESSURE REGULATING VALVE
PSI	POUNDS PER SQUARE INCH
RPM	REVOLUTIONS PER MINUTE
SCFM	STANDARD CUBIC FEET PER MINUTE
SQ FT	SQUARE FEET
SS	STAINLESS STEEL
TEMP	TEMPERATURE
TYP	TYPICAL
UNO	UNLESS NOTED OTHERWISE
VTR	VENT THROUGH ROOF
W	WATTS
WG	WATER GAUGE
WM	WATER METER
WPD	WATER PRESSURE DROP
°C	DEGREES CENTIGRADE (CELCIUS)
°F	DEGREES FAHRENHEIT
Ø	DIAMETER

PLUMBING SYSTEM TYPES AND ABBREVIATIONS

NOTE: NOT ALL ABBREVIATIONS MAY BE USED.

ABBREVIATION	DESCRIPTION
CD	CONDENSATE DRAIN
D	DRAIN
DCW	DOMESTIC COLD WATER
DHW	DOMESTIC HOT WATER
DHWR	DOMESTIC HOT WATER RETURN
SAN	SANITARY SEWER
SST	SECONDARY STORM PIPING
V	VENT

PLUMBING SYMBOLS LIST

NOTE: NOT ALL SYMBOLS MAY BE USED.

SYMBOL	DESCRIPTION
—SAN—	SANITARY PIPING
—V—	VENT PIPING
—ST—	STORM PIPING
—SS—	SECONDARY STORM PIPING
— — —	DOMESTIC COLD WATER PIPING
— — —	DOMESTIC HOT WATER PIPING
— — — —	DOMESTIC HOT WATER RECIRCULATING PIPING
—G—	NATURAL GAS PIPING
	FLOW ARROW
	CONNECT TO EXISTING
	END OF DEMOLITION
	PIPE CAPPED
	PIPE UNION
	PIPE GUIDES OR SLEEVES
	PIPE ANCHOR
	FLEXIBLE PIPE CONNECTION
	GENERAL SERVICE VALVE (SEE SPECIFICATIONS FOR VALVE TYPE PER APPLICATION)
	CHECK VALVE (ARROW INDICATES DIRECTION OF FLOW)
	MANUAL BALANCING VALVE
	AUTOMATIC BALANCING VALVE
	TWO-WAY CONTROL VALVE
	THREE-WAY CONTROL VALVE
PICBV	TWO-WAY PRESSURE INDEPENDENT CONTROL AND BALANCE VALVE
	PRESSURE REDUCING VALVE
	STEAM PRESSURE REGULATING VALVE
	TEMPERATURE AND PRESSURE RELIEF VALVE
	DRAIN VALVE WITH THREADED HOSE CONNECTION
	REDUCED PRESSURE BACKFLOW PREVENTER
	PRESSURE GAUGE WITH STOPCOCK
	STRAINER WITH BLOW DOWN VALVE
AV	AUTOMATIC AIR VENT
MAV	MANUAL AIR VENT
	TEMPERATURE/PRESSURE TEST PLUG (PETE'S PLUG)
	STEAM TRAP
CO CO	CLEAN OUT
	FLOW METER
	THERMOMETER
	PITCH DOWN IN DIRECTION OF ARROW
H	HUMIDISTAT WITH ADJUSTABLE CONTROL
T	THERMOSTAT WITH ADJUSTABLE CONTROL
H	HUMIDITY SENSOR
T	TEMPERATURE SENSOR
CO2	CARBON DIOXIDE SENSOR
CO	CARBON MONOXIDE SENSOR
NO2	NITROGEN DIOXIDE SENSOR
OS	OCCUPANCY SENSOR

DOMESTIC WATER HEATER SCHEDULE

TAG	BASIS OF DESIGN		TANK VOLUME (GAL)	HEATING CAPACITY			ELECTRICAL	
	MANUFACTURER	MODEL		ELEC kW	GPH	TEMP RISE (F)	VOLT	PH
EWH-1	A. O. Smith	DRE-52A-6	50	30	54	64	480 V	3
EWH-2	A. O. Smith	DRE-52A-6	50	30	54	64	480 V	3
EWH-3	A. O. Smith	DRE-52A-6	50	30	54	64	480 V	3

PLUMBING FIXTURE SCHEDULE

MARK	FIXTURE TYPE	MOUNT	CONNECTIONS			COMPONENTS	BASIS OF DESIGN
			COLD WATER	HOT WATER	SANITARY		
EWC-1	BI-LEVEL ELECTRIC WATER COOLER & BOTTLE FILLER	WALL	1/2"	-	1-1/2"	STAINLESS STEEL VANDAL RESISTANT; FRONT PUSH BUTTON BUBBLER ACTIVATION; ELECTRONIC BOTTLE FILLER BUTTON; FILTERED 8 GPH CAPACITY; 120 VOLT; WALL HANGER BRACKET	ELKAY LVRCTL8WSK
FD-1	FLOOR DRAIN	FLOOR	1/2"	-	3"	CAST-IRON BODY; ROUND NICKLE BRONZE ADJUSTABLE STRAINER; TRAP AND TRAP PRIMER CONNECTION. OUTLET TO MATCH TYPE OF PIPING SYSTEM USED.	JAY R SMITH 2005 SERIES
FS-1	FLOOR SINK	FLOOR	1/2"	-	3"	PORCELAIN ENAMALED CAST-IRON BODY WITH 3/4" GRATE; 12" SQUARE BODY; DEEP WITH FLANGE; NO-HUB OUTLET AND TRAP.	JAY R SMITH 335-Y03
HB-1	HOSE BIBB	WALL	3/4"	-	-	FREEZLESS, ANTI-SIPHON; ALUMINUM HANDLE; ADJUSTABLE WALL FLANGE.	WOODFORD MODEL 19
HD-1	HUB DRAIN	FLOOR	-	-	3"	CAST-IRON BODY; HUB CONNECTION WITH AIR GAP; TRAP; TRAP PRIMER CONNECTION.	JAY R SMITH 2005; 2645-CAN
KS-1	BREAK ROOM KITCHEN SINK	COUNTERTOP	1/2"	1/2"	2"	SINGLE BOWL, 20 GAUGE STAINLESS STEEL, DROP-IN SINK WITH SOUND ABSORBING SYSTEM; 3-1/2" DRAIN OPENING; 2" TAIL PIECE WITH GRID BASKET STRAINER; 2" P-TRAP; SUPPLY STOPS; SINGLE LEVER/HOLE FAUCET; CHROME FINISH, MANUAL; ADA COMPLIANT.	SINK: MOEN GS201961BQ, FAUCET: MOEN 7423, P-TRAP: MCGUIRE 8904, SUPPLY: MCGUIRE LF175, DRAIN: SIGNATURE HARDWARE MODEL 902367
L-1 (LAV-1)	LAVATORY	WALL	1/2"	1/2"	1-1/4"	20" x 18" WHITE VITREOUS CHINA WALL HUNG LAVATORY WITH ADA COMPLIANT SINGLE LEVER 4" CENTERSET FAUCET; GRID STRAINER; 1.25" P-TRAP; SUPPLY STOPS AND WALL HANGER.	SINK; ZURN Z5340, FAUCET: ZURN Z7440-XL, P-TRAP: ZURN Z8700, SUPPLY: ZURN Z8800, STRAINER: ZURN Z8473-PC, PROTECTORS: ZURN Z8496-3-NT
L-2 (LAV-2)	LAVATORY	COUNTERTOP	1/2"	1/2"	1-1/4"	19" ROUND, WHITE VITREOUS CHINA, SELF RIMMING COUNTERTOP LAVATORY WITH ADA COMPLIANT SINGLE LEVER 4" CENTERSET FAUCET; GRID STRAINER; 1.25" P-TRAP AND SUPPLY STOPS.	FAUCET: ZURN Z7440-XL, P-TRAP: ZURN Z8700, SUPPLY: ZURN Z8800, STRAINER: ZURN Z8473-PC, PROTECTORS: ZURN Z8496-3-NT
RCP-1	RECIRCULATING PUMP	INLINE	-	1/2" (x2)	-	1.5 GPM HOT WATER INLINE RECIRCULATING PUMP. STAINLESS STEEL CASING AND FLANGES. 120 VOLT SINGLE PHASE POWER CONNECTION.	TACO 009-SF5
MSB-1	MOP SERVICE BASIN	FLOOR	1/2"	1/2"	3"	24" SQUARE BY 10" DEEP MOLDED HIGH DENSITY COMPOSITE MOP SERVICE BASIN WITH STAINLESS STEEL BUMPER GAURDS. PVC DRAIN BODY. STAINLESS STEEL STRAINER AND 3" OUTLET CONNECTION. WALL HUNG DUAL LEVER FAUCET WITH 6" SPOUT, 3/4" HOSE THREADED OUTLET, PAIL HOOK AND WALL BRACE; P-TRAP AND SUPPLY STOPS.	SINK: ZURN Z1996-24, FAUCET: ZURN Z843M1
TP-1	TRAP PRIMER VALVE	INLINE	1/2"	-	-	AUTOMATIC MECHANICAL TRAP PRIMER; 30-150 PSI OPERATING RATING; ACTIVATION; ACTIVATE WITH 10 PSI PRESSURE DROP.	SIOUX CHIEF 695 SERIES
U-1 (UR-1)	ADA URINAL	WALL	3/4"	-	2"	0.128 GPF, LOW CONSUMPTION, WHITE VITREOUS CHINA WALL HUNG URINAL. MANUAL FLUSH VALVE; WALL HANGER; COMPLY WITH ADA REGULATIONS; VANDAL-RESISTANT.	ZURN Z5758 SERIES WITH Z6003AV-ULF MANUAL FLUSH VALVE; WALL CARRIER BY ZURN. (UR-1 IN SPECIFICATIONS)
WC-1	WATER CLOSET	WALL	1"	-	3"	1.1 GPF, HIGH EFFICIENCY, WHITE VITREOUS CHINA, ELONGATED WALL HUNG WATER CLOSET; MANUAL FLUSH VALVE; CLOSET CARRIER; OPEN FRONT SEAT.	ZURN Z5615 SERIES WITH Z6000AV-ONE MANUAL FLUSH VALVE; CLOSET CARRIER BY ZURN.
WC-2	ADA WATER CLOSET	WALL	1"	-	3"	1.1 GPF, HIGH EFFICIENCY, WHITE VITREOUS CHINA, ELONGATED WALL HUNG WATER CLOSET; MANUAL FLUSH VALVE; CLOSET CARRIER; OPEN FRONT SEAT. COMPLY WITH ADA REGULATIONS	ZURN Z5615 SERIES WITH Z6000AV-ONE MANUAL FLUSH VALVE; CLOSET CARRIER BY ZURN.
WHA-1	WATER HAMMER ARRESTOR	INLINE	AS REQUIRED	-	-	PISTON TYPE WATER HAMMER ARRESTOR; TYPE L COPPER BODY; MAX WORKING PRESSURE 350 PSIG.	SOUX CHIEF 650 SERIES

Building Inspection Division
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Lakeland
Date: 11/15/19
Permit Number: BLD19-06035

AECOM
CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHTIECTURE
LICENSE NO. AA260000687

ENGINEERING
CA LIC. NO. 8115

www.aecom.com

REGISTRATION

JOHN TYE RECTOR
LICENSE
No. 53292
STATE OF
FLORIDA
PROFESSIONAL ENGINEER

JOHN T. RECTOR, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 53292
08/22/19

John T Rector
John T Rector 2019.08.22 15:49:26 -04'00'

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY JOHN T. RECTOR, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 53292 ON THE DATE ADJACENT TO THE SEAL. PRINTED COPIES OF THIS DOCUMENT MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
	AUG 23, 2019	CONSTRUCTION DOCUMENTS
	MAY 31, 2019	35% DESIGN COMPLETION

PROJECT NUMBER

60601397

SHEET TITLE

PLUMBING LEGEND & NOTES

SHEET NUMBER

P0-0-01

Printed on ___% Post-Consumer Recycled Content Paper
©2016 AECOM Corporation