Project Management Initials: Designer: Designer Checked: Checker Approved: Approver/RCH E1 30"x42"

Building Inspection Division
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Lakeland Date: 11/15/19
Permit Number: BLD19-06035

DESIGN CRITERIA

1.) ALL WORK SHALL CONFORM TO THE STANDARDS OF THE 2017 FLORIDA BUILDING CODE

2.) LIVE LOADS:

ROOFS
ROOF .....30 PSF

FLOOR LOADS
OFFICE SPACES .....65 PSF
CORRIDORS ABOVE 1ST FLOOR .....80 PSF
ASSEMBLY AREAS .....100 PSF
STAIRS .....100 PSF
MECHANICAL & ELECTRICAL ROOMS** .....150 PSF
ELEVATOR LOBBY .....100 PSF
RESTROOMS & TOILET ROOMS .....75 PSF

3.) WIND LOADS PER AMERICAN SOCIETY OF CIVIL ENGINEERS ASCE 7-10 "MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES."

4.) THE PROPOSED STRUCTURE IS LOCATED NOT WITHIN THE WIND-BORNE DEBRIS REGION.

5.) BASIC WIND SPEED, (3 SECOND GUST)
VULT = 138 MPH (ULTIMATE WIND SPEED)
Vasd = 107 MPH (EQUIVALENT NOMINAL WIND SPEED)

6.) WIND DIRECTIONALITY FACTOR (Kd) = 0.85

7.) BUILDING RISK CATEGORY = II

8.) WIND EXPOSURE CATEGORY = EXPOSURE C, WITH NO SIGNIFICANT ESCARPMENTS.

9.) BUILDING ENCLOSURE CLASSIFICATION = PARTIALLY ENCLOSED BUILDING

10.) INTERNAL PRESSURE COEFFICIENT (GCpi) = +/- 0.55

11.) ALL EXTERIOR COMPONENT AND CLADDING SHALL BE DESIGNED TO RESIST THE WIND PRESSURES INDICATED IN THE WALL AND ROOF "MINIMUM COMPONENT AND CLADDING ULTIMATE DESIGN WIND PRESSURES" TABLES ON THESE DRAWINGS. ROOF COMPONENTS SHALL ALSO COMPLY WITH THE APPROPRIATE FACTORY MUTUAL CLASSIFICATION CORRESPONDING WITH THESE PRESSURES.

FOUNDATION

1.) DESIGN SOIL BEARING PRESSURE = 3,000 PSF AT PERIMETER FOUNDATIONS, AND 4000 PSF FOR ALL INTERIOR FOUNDATIONS BASED UPON GEOTECHNICAL EXPLORATION REPORTS BY "ARDAMAN & ASSOCIATES, INC." (19-51-9050 DATED APRIL 9, 2019). THESE GEOTECHNICAL REPORTS SHALL BE INCORPORATED INTO THE SPECIFICATIONS AND AS SUCH BECOME PART OF THESE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL BECOME FAMILIAR WITH AND FOLLOW ALL OF THE RECOMMENDATIONS CONTAINED IN THESE GEOTECHNICAL INVESTIGATIONS INCLUDING, BUT NOT LIMITED TO GROUNDWATER CONTROL, SUBGRADE PREPARATION, AND FILL SUITABILITY.

2.) QUALITY ASSURANCE COMPACTION DENSITY UNDER FOOTINGS AND SLABS SHALL BE A MINIMUM OF "95%" OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D-1557 (MODIFIED PROCTOR) THROUGHOUT EACH 12-INCH LIFT, TO A DEPTH AS INDICATED IN THE GEOTECHNICAL REPORT. IN ADDITION TO THIS MINIMUM COMPACTION REQUIREMENT, THE BEARING SOILS MUST EXHIBIT STABILITY AND BE FREE OF "PUMPING" CONDITIONS.

3.) FOUNDATIONS SHALL NOT BE PLACED ABOVE SLOPES EXCEEDING ONE VERTICAL AND TWO HORIZONTAL AS MEASURED FROM THE CLOSEST EDGE OF ANY UNDISTURBED SOIL OR OTHER FOUNDATION STRUCTURE.

4.) ALL FOUNDATIONS SHALL BE CENTERED UNDER COLUMN OR WALL CENTERLINES UNLESS SHOWN OR NOTED OTHERWISE.

5.) REPORT ANY UNUSUAL BELOW GRADE CONDITIONS ENCOUNTERED TO THE STRUCTURAL ENGINEER.

GENERAL

1.) GENERAL NOTES AND TYPICAL DETAILS APPLY TO ALL STRUCTURAL FEATURES UNLESS OTHERWISE SHOWN OR NOTED. IF CERTAIN FEATURES ARE NOT FULLY SHOWN OR CALLED FOR ON THE DRAWINGS OR SPECIFICATIONS, THEIR CONSTRUCTION SHALL BE OF THE SAME CHARACTER AS FOR SIMILAR CONDITIONS.

2.) ANCHORS ARE TO BE INSTALLED WITHIN A TOLERANCE OF 1/4" OF SPECIFIED LOCATION.

3.) A SOIL OR WASTE PIPE OR A BUILDING DRAIN, ETC PASSING UNDER A FOOTING OR THROUGH A FOUNDATION WALL SHALL BE PROVIDED WITH A RELIEVING ARCH, OR THERE SHALL BE BUILT INTO THE WALL OR FOUNDATION AN IRON PIPE SLEEVE TWO PIPE SIZES GREATER THAN THE PIPE PASSING THROUGH FOR PIPES 6"ø AND LESS AND ONE PIPE SIZE GREATER THAN THE PIPE PASSING THROUGH FOR PIPES GREATER THAN 6"ø.

4.) THIS STRUCTURE IS DESIGNED TO BE SELF-SUPPORTING AND STABLE AFTER THE BUILDING IS FULLY COMPLETED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE ERECTION PROCEDURE AND SEQUENCE AND TO ENSURE THE SAFETY OF WORKERS, THE BUILDING AND ITS COMPONENT PARTS DURING ERECTION. THIS INCLUDES THE ADDITION OF WHATEVER SHORING, TEMPORARY BRACING, ETC. THAT MAY BE NECESSARY AS WELL AS FULL COMPLIANCE WITH ALL APPLICABLE OSHA REGULATIONS. OBSERVATION VISITS TO THE SITE SHALL NOT INCLUDE INSPECTION FOR THESE ITEMS.

5.) IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO ENSURE ALL WORK IS PERFORMED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

6.) REFER TO ARCHITECTURAL DRAWINGS FOR LOCATIONS AND HEIGHTS OF ALL MASONRY WALLS NOT SHOWN OR OTHERWISE NOTED ON THE STRUCTURAL DRAWINGS.

7.) REFER TO ARCHITECTURAL AND MECHANICAL DRAWINGS FOR SIZE AND LOCATION OF ALL FLOOR AND ROOF OPENINGS NOT SHOWN OR OTHERWISE NOTED ON THE STRUCTURAL DRAWINGS.

8.) DIMENSIONS SHALL NOT BE SCALED.

9.) COORDINATE BONDING OF FOUNDATION REBAR TO ELECTRICAL GROUND WITH ELECTRICAL CONTRACTOR.

10.) SPECIALTY ENGINEER REQUIREMENTS: THE FLORIDA BOARD OF PROFESSIONAL ENGINEERS IS ON RECORD STATING THE RESPONSIBILITIES OF PROFESSIONAL ENGINEERS, PURSUANT TO RULE 61G15-31. CERTAIN COMPONENTS OF THIS STRUCTURE REQUIRES THE WORK OF A SPECIALTY ENGINEER. ALL PROCEDURES STATED IN RULE 61G15-31 STATEMENT SHALL APPLY TO THIS PROJECT.

11.) SPECIFICATIONS, CODES, AND STANDARDS NOTED IN THESE CONTRACT DOCUMENTS SHALL BE OF THE LATEST EDITION APPROVED BY THE APPROPRIATE REGULATORY AGENCIES.

12.) SHOP DRAWINGS AND CALCULATIONS FOR ALL STOREFRONT SYSTEMS, CANOPIES, AND SPECIALTY ENGINEERED BUILDING ELEMENTS MUST BE SIGNED AND SEALED BY THE CURRENTLY LICENSED, FLORIDA SPECIALTY ENGINEER RESPONSIBLE FOR THE DESIGN AT TIME OF SUBMISSION.

13.) THE STRUCTURAL ENGINEER OF RECORD IS NOT RESPONSIBLE FOR THE DESIGN OF STEEL STAIRS, HANDRAILS, LADDERS, CURTAINWALL/WINDOW WALL SYSTEMS, ANY COLD-FORMED STEEL FRAMING, OR OTHER SYSTEMS NOT SHOWN IN THE STRUCTURAL DOCUMENTS. SUCH SYSTEMS SHALL BE DESIGNED, FURNISHED, AND INSTALLED AS REQUIRED BY OTHER PORTIONS OF THE CONTRACT DOCUMENTS.

14.) THE CONTRACT STRUCTURAL DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE, AND DO NOT INDICATE THE METHOD OR MEANS OF CONSTRUCTION. THE CONTRACTOR SHALL SUPERVISE AND DIRECT THE WORK AND SHALL BE SOLELY RESPONSIBLE FOR ALL CONSTRUCTION MEANS, METHODS, PROCEDURES, TECHNIQUES, SEQUENCES, OR PROCEDURES, FOR SAFETY PRECAUTIONS AND PROGRAMS IN CONNECTION WITH THE WORK, FOR THE ACTS OR OMISSION OF THE CONTRACTOR, SUBCONTRACTOR, OR ANY OTHER PERSONS PERFORMING ANY OF THE WORK, OR FOR THE FAILURE OF ANY OF THEM TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

15.) OPENINGS THROUGH FLOORS, ROOFS, WALLS FOR DUCTS, PIPING, AND/OR CONDUIT SHALL BE COORDINATED BY THE CONTRACTOR. THE CONTRACTOR SHALL VERIFY SIZES AND LOCATIONS OF HOLES AND OPENINGS WITH THE ARCHITECTURAL, MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION DRAWINGS AND THE RESPECTIVE SUBCONTRACTORS.

16.) WHERE CONFLICT EXISTS AMONG THE VARIOUS PARTS OF THE STRUCTURAL CONTRACT DOCUMENTS, STRUCTURAL DRAWINGS, GENERAL NOTES, AND SPECIFICATIONS, THE STRICTEST REQUIREMENTS, AS INDICATED BY THE ENGINEER, SHALL GOVERN.

17.) NO PROVISIONS HAVE BEEN MADE FOR VERTICAL OR HORIZONTAL EXPANSION.

18.) WHERE MEMBER LOCATIONS ARE NOT SPECIFICALLY DIMENSIONED, MEMBERS ARE EITHER LOCATED ON COLUMN LINES OR ARE EQUALLY SPACED BETWEEN LOCATED MEMBERS.

CONCRETE

1.) CONCRETE TO BE IN ACCORDANCE WITH ACI 318-14/318R-14 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE AND COMMENTARY".

2.) ALL REINFORCEMENT SHALL BE SECURELY HELD IN PLACE WITH STANDARD ACCESSORIES WHILE PLACING CONCRETE. IF REQUIRED, ADDITIONAL BARS OR STIRRUPS SHALL BE PROVIDED BY CONTRACTOR TO FURNISH SUPPORT FOR ALL BARS.

3.) CONCRETING SHOULD BE CARRIED ON AT SUCH A RATE THAT THE CONCRETE IS AT ALL TIMES PLASTIC.

4.) CONCRETE FOR FOOTINGS, FOUNDATION WALLS AND BUILDING FRAME MEMBERS SHALL BE NORMAL WEIGHT WITH A COMPRESSIVE STRENGTH AT 28 DAYS NO LESS THAN 4,000 PSI (UNO).

5.) PARTIALLY HARDENED CONCRETE, CONTAMINATED CONCRETE, RE-TEMPERED CONCRETE, AND CONCRETE THAT HAS BEEN RE-MIXED AFTER IT HAS TAKEN ITS INITIAL SET ARE NOT TO BE USED IN NEW CONCRETE PLACEMENT.

6.) ALL REINFORCING STEEL SHALL BE CLEAN AND FREE OF MUD, OIL, RUST, AND OTHER COATINGS THAT WOULD IMPAIR PROPER BOND TO CONCRETE. ALL REINFORCING STEEL SHALL HAVE A MINIMUM YIELD STRENGTH OF 60,000 PSI AND SHALL CONFORM TO ASTM A-615.

7.) MINIMUM COVER FOR REINFORCEMENT SHALL BE AS FOLLOWS:

CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH.....3"

CONCRETE EXPOSED TO EARTH OR WEATHER:
#5 BAR AND SMALLER.....1 1/2"
#6 BARS AND LARGER.....2"

CONCRETE NOT EXPOSED TO EARTH OR WEATHER:
SLABS, WALLS, AND JOISTS.....3/4"
BEAMS (TO STIRRUPS).....1 1/2"
COLUMNS AND PIERS (TO TIES).....1 1/2"

8.) ALL WELDED WIRE REINFORCING SHALL CONFORM TO ASTM A-1064, LAP SPLICE 6".

9.) DETAIL ALL REINFORCEMENT IN ACCORDANCE WITH ACI 315.

10.) SPLICES IN ALL REINFORCING SHALL BE CLASS B AS CALCULATED PER ACI 318 AND AS SHOWN ON THESE DWGS, WHICHEVER IS GREATER.

11.) REBAR SHALL BE CONTINUOUS AROUND ALL CORNERS AND INTERSECTIONS OF WALLS, BEAMS, AND FOOTINGS. PROVIDE CORNER BARS AS REQUIRED.

12.) CHAMFER 3/4" ALL EDGES OF EXPOSED CONCRETE , UON.

13.) TOP BARS ARE DEFINED AS HORIZONTAL BARS WITH MORE THAN 12 INCHES OF CONCRETE CAST BELOW THE BARS.

14.) USE TABLE #1 FOR A615 GRADE 60-UNCOATED REINFORCING WHEN CLEAR CONCRETE COVER IS NOT LESS THAN ONE (1) BAR DIAMETER (3/4" MINIMUM) AND CLEAR BAR SPACING IS NOT LESS THAN TWO (2) BAR DIAMETERS. IN ALL OTHER CASES, MULTIPLY THE TABLE VALUES BY 1.5 THE TABLE VALUES MAY BE REDUCED BY MULTIPLYING THE VALUES BY 1.5 AND THEN DIVIDING THE PRODUCTS BY RATIO OF ONE-HALF CENTER TO CENTER BAR SPACING TO BAR DIAMETER OR RATIO OF BAR CENTER TO SURFACE OF CONCRETE DISTANCE TO BAR DIAMATER, WHICHEVER GIVES SMALLER RATIO. THE RATIO SHALL NOT BE TAKEN LESS THAN 2.5. IN NO CASE LAP AND ANCHORAGE LENGTH SHALL BE LESS THAN 12".

15.) SLAB-ON-GRADE CONCRETE MIX DESIGN SHALL MEET REQUIREMENTS LISTED IN THE 2017 FLORIDA BUILDING CODE APPENDIX E SECTION E303.2.3.

NOTES FOR TABLE #1

16.) FOR BUNDLED BARS MULTIPLY THE TABLE VALUES BY: 1.2 (3 BAR BUNDLE), 1.33 (4 BAR BUNDLE)

17.) (MC) DENOTES MECHANICAL COUPLER DEVELOPING 125% OF THE BAR YIELD STRENGTH. NO OTHER SPLICE WILL BE ACCEPTED.

18.) WHEN LAPPING TWO DIFFERENT SIZE BARS, USE THE LAP DIMENSION OF THE SMALLER BAR OR THE ANCHORAGE DIMENSIONS OF THE LARGER BAR. USE WHICHEVER DIMENSION IS LARGER.

19.) MECHANICAL SPLICES MAY BE PROVIDED AS A CONTRACTOR OPTION; PROVIDED THE MECHANICAL COUPLERS ARE CAPABLE OF DEVLOPING 125% OF THE BAR YIELD STRENGTH.

TABLE #1
MINIMUM LAP SPLICE AND ANCHORAGE DIMENSION TABLE

4000 PSI CONCRETE				
BAR SIZE	TOP BARS		OTHER BARS	
	LAP	ANCH	LAP	ANCH
#3	24"	19"	19"	14"
#4	32"	25"	25"	19"
#5	40"	31"	31"	24"
#6	48"	37"	37"	29"
#7	71"	54"	54"	42"
#8	81"	62"	62"	48"
#9	91"	70"	70"	54"
#10	102"	79"	79"	61"
#11	(MC)	87"	(MC)	67"

STRUCTURAL STEEL

1.) STRUCTURAL STEEL SHALL BE IN ACCORDANCE WITH AISC "STEEL CONSTRUCTION MANUAL", ASD, 14TH EDITION, AND SHALL CONFORM TO THE FOLLOWING MINIMUM SPECIFICATIONS:

W-SHAPES.....ASTM A992 GRADE 50
HSS.....ASTM A500 GRADE B
PIPES.....ASTM A53 GRADE B
ANGLES, CHANNELS, PLATES & BARS.....ASTM A36
ANCHOR RODS.....ASTM F1554 GRADE 55 (UON)

2.) FRAMED BEAM CONNECTIONS SHALL DEVELOP ONE HALF OF THE ALLOWABLE UNIFORM LOAD FOR NON-COMPOSITE BEAMS AS SHOWN IN THE AISC TABLE OF ALLOWABLE UNIFORM LOAD CONSTANTS FOR THE SUBJECT MEMBER AND SPAN OR THE REACTION, IF SHOWN ON THE FRAMING PLANS.

3.) ALL WELDING SHALL BE PERFORMED BY WELDERS WITH CURRENT CERTIFICATES, VALID FOR AT LEAST THE PAST YEAR, SUBMITTED TO AECOM FOR VERIFICATION. ALL WELDING SHALL BE PERFORMED IN STRICT ACCORDANCE WITH AWS D1.1 "STRUCTURAL WELDING CODE - STEEL" (LATEST EDITION). MINIMUM SIZE OF ALL FILLET WELDS SHALL CONFORM TO AISC TABLE J2.4.

4.) STEEL TUBES SHALL HAVE 1/4" CLOSURE PLATES AT ALL EXPOSED ENDS.

5.) WELDING GALVANIZED STEEL: WELD GALVANIZED STEEL IN STRICT ACCORDANCE WITH AMERICAN WELDING SOCIETY'S (AWS) RECOMMENDATION WZC, WELDING ZINC COATED STEEL. WELDS OF GALVANIZED STEEL SHALL BE ON AREAS THAT ARE FREE OF ZINC. REMOVE ZINC COATING AT LEAST ONE TO FOUR INCHES FROM EITHER SIDE OF THE INTENDED WELD ZONE AND BOTH SIDES OF THE PIECE BY GRINDING BACK THE ZINC COATING OR BURNING THE ZINC AWAY. WELDING GALVANIZED STEEL SHALL BE DONE IN WELL-VENTILATED LOCATIONS TO MINIMIZE FUME INHALATION, IN STRICT ACCORDANCE WITH AWS/ANSI Z49:1; SAFETY AND CUTTING IN WELDING. WELDING SHALL BE GAS METAL ARC (GMAW), SHIELDED METAL ARC WELDING (SMAW), MANUAL METAL ARC, OXACETYLENE WELDING, FRICTION WELDING, OR RESISTANCE WELDING AS APPLICABLE. POINTED STUDS MUST BE USED WITH FRICTION WELDING STUDS TO GALVANIZED SURFACES IN ACCORDANCE WITH AWS D19.0. STUD SHALL HAVE A POINT WITH A 120° ANGLE.

6.) BOLTS IN MOMENT CONNECTIONS OR X-BRACED FRAMES SHALL BE INSTALLED WITH APPROVED DIRECT TENSION INDICATORS, OR BE APPROVED INDICATOR BOLTS. BOLTS IN ALL STRUCTURAL STEEL CONNECTIONS TO EMBED PLATES SHALL BE "FINGER TIGHT" WITH PEENED THREADS (U.N.O.). FIELD WELDING OF ANY BOLTED CONNECTION IS STRICTLY PROHIBITED WITHOUT PRIOR AUTHORIZATION IN WRITING BY AECOM.

7.) SHOP DRAWINGS FOR ALL STRUCTURAL STEEL SHALL BE SUBMITTED AND APPROVED PRIOR TO ANY FABRICATION AND ERECTION.

8.) CONNECTION DETAILS NOT COMPLETELY DETAILED ON THE DRAWINGS INCLUDING MATERIAL GRADE AND SIZES, WELD SIZES, AND NUMBER OF BOLTS SHALL BE DESIGNED BY THE CONTRACTOR PER THE SPECIFICATIONS. THE CONCEPTUAL DETAILS PROVIDED MAY NOT FULLY REPRESENT THE COMPLEXITY OF THE CONNECTION AS REQUIRED BY THE FINAL CONNECTION DESIGN FOR THE FORCES THEY MUST RESIST. ADDITIONAL CONNECTION ELEMENTS MAY NOT BE SPECIFICALLY SHOWN IN THE CONCEPTUAL DETAILS BUT MAY BE REQUIRED BY THE FINAL CONNECTION DESIGN, SUCH AS STIFFENER PLATES, DOUBLER PLATES, SUPPLEMENT/REINFORCING PLATES, OR OTHER CONNECTION MATERIAL. THE FABRICATOR IS RESPONSIBLE FOR ENGAGING THE SERVICES OF A CONNECTION SPECIALTY ENGINEER TO PREPARE ALL FINAL CONNECTION DESIGNS FOR SUBMISSION THAT MEETS THE REQUIREMENTS OF THE CONCEPTUAL CONNECTION DETAILS AND RESISTS THE REQUIRED DESIGN FORCES.

9.) STEEL SHOP DRAWINGS AND ASSOCIATED CONNECTION CALCULATIONS SHALL BE SIGNED AND SEALED BY A SPECIALTY STRUCTURAL ENGINEER WHO IS CURRENTLY LICENSED IN THE STATE OF FLORIDA. FABRICATION SHALL NOT COMMENCE UNTIL THE SHOP DRAWINGS HAVE BEEN STAMPED 'NO EXCEPTION TAKEN' OR 'MAKE CORRECTIONS NOTED BY AECOM.

10.) REACTIONS NOTED ON THE PLANS ARE BASED ON SERVICE LOADS AND ARE INTENDED FOR USE WITH THE ALLOWABLE SERVICE DESIGN METHOD.

11.) THE USE OF CUTTING TORCH IN THE FIELD WILL NOT BE PERMITTED.

12.) ALL WELDS SHALL BE WITH E70XX ELECTRODES IN ACCORDANCE WITH AWS STANDARDS.

STEEL JOISTS / JOIST GIRDERS:

1.) STEEL JOISTS SHALL CONFORM TO THE STEEL JOIST INSTITUE (SJI) "STANDARD SPECIFICATION FOR OPEN WEB STEEL-JOISTS, K-SERIES," AND STEEL JOIST GIDERS SHALL CONFORM TO SJI, "STANDARD SPECIFICATION FOR JOIST GIRDERS" AND AS OTHERWISE SPECIFIED.

2.) PROVIDE BRIDGING AND CAMBER FOR STEEL JOISTS / JOIST GIRDERS IN COMPLIANCE WITH MANUFACTURERS REQUIREMENTS AND THESE DRAWINGS.

3.) WELD FULL LENGTH OF ALL JOIST SEATS WHERE WELDS ARE INDICATED. INCREASE THICKNESS OF JOIST / JOIST GIRDER SEAT ANGLES AS REQ'D TO ACCOMODATE WELD SIZES INDICATED ON THESE DOCUMENTS.

4.) STEEL JOISTS / JOIST GIRDERS SHALL BE DESIGNED TO SUPPORT THE UNIFORM LOADS LISTED IN THE STEEL JOIST INSTITUTE (SJI) "STANDARD LOAD TABLES AND WEIGHT TABLES FOR STEEL JOISTS AND JOISTS GIRDERS." ANY ADDITIONAL UNIFORM OR CONCENTRATED COLLATERAL DEAD, LIVE, OR WIND LOADS SHOWN SHALL BE ADDED TO THESE UNIFORM LOADS.

5.) ROOF JOIST / JOIST GIRDER FABRICATION SHALL INCLUDE COORDINATION WITH MECHANICAL DRAWINGS TO ENSURE WEB SIZING ALLOWS DUCT WORK TO PASS THROUGH.

6.) UPLIFT FORCES TO STEEL JOISTS / JOIST GIRDERS SHALL BE DETERMINED ACCORDING TO THE "COMPONENT AND CLADDING ULTIMATE DESIGN WIND PRESSURES" SCHEDULE SHOWN ON THESE DRAWINGS.

7.) ALL JOISTS / JOIST GIRDERS SHALL BE DESIGNED TO RESIST A MINIMUM COLLATERAL LIVE ADD-LOAD OF 450 LBS AND A MINIMUM COLLATERAL LIVE BEND-CHECK LOAD OF 150 LBS LOCATED AT ANY POINT ALONG THE TOP OR BOTTOM CHORDS AS DEFINED IN THE SJI CODE OF STANDARD PRACTICE (COSP). ADD-LOADS SHALL BE IN ADDITION TO THE DEAD AND LIVE LOADS LISTED IN THE SJI LOAD TABLES FOR THE SUBJECT MEMBER AND SPAN, BUT BEND-CHECK LOADS NEED NOT BE CONCURRENT. ALL CONCENTRATED LOADS MUST BE CONCENTRICALLY LOADED TO JOIST CHORDS.

8.) ALL JOISTS SHALL BE DESIGNED TO LIMIT DIFFERENTIAL CAMBER BETWEEN ADJACENT JOISTS TO NO GREATER THAN 1-INCH.

9.) IF A STEEL BEAM SUPPORTS JOISTS ON ONLY ONE SIDE OR THE LENGTHS OF JOISTS ON ONE SIDE OF THE BEAM ARE 20% LONGER THAN THE JOISTS ON THE OPPOSING SIDE OF THE BEAM, THEN THE JOISTS SHALL BEAR ON THE FULL BEAM FLANGE OR 5 1/2", WHICHEVER IS MORE.

10.) JOIST / JOIST GIRDER SHOP DRAWINGS AND ASSOCIATED CALCULATIONS SHALL BE SIGNED AND SEALED BY A SPECIALTY STRUCTURAL ENGINEER WITH A MINIMUM OF 5 YEARS EXPERIENCE IN THE DESIGN OF STEEL JOISTS / JOIST GIRDERS AND IS CURRENTLY LICENSED IN THE STATE OF FLORIDA. FABRICATION SHALL NOT COMMENCE UNTIL THE SHOP DRAWINGS HAVE BEEN STAMPED "NO EXCEPTION TAKEN" OR "MAKE CORRECTIONS NOTED" BY AECOM.

11.) BOLT JOISTS/JOIST GIRDERS AS REQUIRED FOR COLUMN STABILITY IN STRICT ACCORDANCE WITH OSHA AND WHERE SHOWN IN PLAN.

METAL DECK

1.) METAL DECK TO COMPLY WITH "SDI SPECIFICATIONS AND COMMENTARY FOR STEEL ROOF DECK", SDI PUBLICATION NO. 29.

2.) GALVANIZE SHEET STEEL TO COMPLY W/ ASTM A653/A STRUCTURAL QUALITY(SQ) GRADE 33 OR HIGHER G90 (Z275)

3.) SIDE-LAP FASTENERS SHALL BE NO. 10 CORROSION-RESISTANT, HEXAGONAL WASHER HEAD, SELF-DRILLING, CARBON-STEEL SCREWS (UNO).

4.) WELDING SHALL BE FULL-FUSION WELDS MADE WITH AWS E60 ELECTRODES IN ACCORDANCE WITH AWS D1.1, "STRUCTURAL WELDING CODE -STEEL", AND AWS D1.3, "STRUCTURAL WELDING CODE -SHEET STEEL." METAL AROUND WELDS SHALL BE COMPLETELY INTACT AFTER WELDING.

5.) TOUCH UP ALL DECK WELDS AND DAMAGED GALVANIZED AREAS WITH GALVANIZING REPAIR PAINT PER ASTM A780 OR DOD-P-21035, WITH A DRY FILM CONTAINING A MINIMUM OF 94% ZINC BY WEIGHT.

6.) SCREWS MUST BE INSTALLED USING PROPERLY CALIBRATED TOOLS IN ORDER TO AVOID OVERDRIVING WHICH CAN STRIP THE THREADS AT SIDE LAPS OR SEVER THE SCREW WHEN IT IS PLACED INTO HEAVIER SUBSTRATA.

7.) UON, METAL DECK SHALL BE DETAILED, FABRCIATED, AND ERECTED SUCH THAT EACH SHEET IS SUPPORTED ON A MINIMUM OF 4 SUPPORTS (3 SPANS). DECK END LAPS MUST LAP A MINIMUM OF 4 INCHES.

8.) METAL DECK SHALL NOT BE USED TO SUPPORT PIPING, DUCTWORK, ROOF DRAINS, ETC. NO ITEMS SHALL BE HUNG DIRECTLY FROM THE ROOF DECK UNLESS INDICATED OTHERWISE IN THE DRAWINGS.

This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever to any party that modifies this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.

AECOM
BATSON-COOK CONSTRUCTION

PROJECT

PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT

Publix

3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

www.publix.com

CONSULTANT

AECOM

AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

http://www.aecom.com

REGISTRATION

LICENSE NO. 81224 STATE OF FLORIDA PROFESSIONAL ENGINEER

VINCENT RAJ VACCARELLO-WADEHRA, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 81224

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY VINCENT RAJ VACCARELLO-WADEHRA, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 81224 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Vincent R Vaccarello-Wadehra
Digitally signed by Vincent R Vaccarello-Wadehra
Date: 2019.08.22 17:56:38 -04'00'

NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.

ISSUE/REVISION

I/R	DATE	DESCRIPTION
0	AUGUST 23, 2019	CONSTRUCTION DOCUMENTS
	AUGUST 16, 2019	90% CONSTRUCTION DOCUMENTS
	JUNE 27, 2019	STEEL DESIGN PACKAGE
	JUNE 7, 2019	35% DESIGN COMPLETION

PROJECT NUMBER

60601397

SHEET TITLE

GENERAL NOTES (1 OF 2)

SHEET NUMBER

S0-1-01

Last Plotted: 8/22/2019 5:35:20 PM
Filename: BM-360-60601397-Publix HQ-S0601397_Publix HQ_STRUCT_R2019.rvt

Printed on ___% Post-Consumer Recycled Content Paper

©2016 AECOM Corporation