Building Inspection Division
THESE PLANS HAVE BEEN REVIEWED FOR COMPLIANCE WITH THE CURRENT EDITION OF THE FLORIDA BUILDING CODE
Lakeland
Date: 11/15/19
Permit Number: BLD19-06035

COLD-FORMED STEEL (CFS) FRAMING:

1.) ALL COLD-FORMED STEEL (CFS) FRAMING SHALL BE DESIGNED ANAT CONSTRUCTED IN ACCORDANCE WITH THE 2017 FLORIDA BUILDING CODE AND LATEST EDITIONS OF AISI S200-07 GENERAL (AMERICAN IRON AND STEEL NORTH AMERICAN STANDARD FOR COLD-FORMED STEEL FRAMING - GENERAL PROVISIONS). HEADERS PER AISI S212-07 HEADER; WALL STUDS PER AISI S211-07 WSD.

2.) ALL CFS MEMBERS SHALL HAVE A MINIMUM Fy = 33 KSI EXCEPT THAT ALL MEMBERS WITH THICKNESS EQUAL TO 0.0566" (16 GA) OR GREATER SHALL HAVE Fy = 50 KSI MINIMUM. ALL STEEL TO BE IN ACCORDANCE WITH ASTM A1003, GRADE C OR D FOR 16-GAUGE ELEMENTS AND HEAVIER.

3.) CFS COMPONENT PROPERTIES DATA SHALL BE AS INDICATED IN THE PRODUCT TECHNICAL INFORMATION PROVIDED BY THE STEEL STUD MANUFACTURERS ASSOCIATION (SSMA), LATEST EDITION UNLESS OTHERWISE NOTED.

4.) ALL SCREWS SHALL BE A MINIMUM #10 (UON). ALL SCREWS SHALL BE SELF TAPPING AND SHALL CONFORM TO SAE J78. A MINIMUM OF THREE EXPOSED THREADS SHALL EXTEND THROUGH THE STEEL. USE ONLY POLYMER FINISH OR STAINLESS STEEL UNITS.

5.) NO FLANGE OR WEB SHALL BE CUT, NOTCHED, REMOVED, OR OTHERWISE REDUCED IN STRENGTH. SPLICING SHALL NOT BE PERMITTED IN JOISTS OR WALL STUDS.

6.) ALL WELDS (E60XX ELECTRODES BY CERTIFIED WELDERS) TO GALVANIZED STEEL SHALL BE TOUCHED UP WITH A ZINC RICH PAINT, SUCH AS GALV-MATCH-PLUS BY NUWAVE SOLUTIONS (OR EQUAL).

7.) ALL INTERIOR & EXTERIOR CFS WALLS ARE VERTICALLY NON-LOADED AND SHALL HAVE SLIP CONNECTIONS (1/2" SPACE MIN) AT THE TOP TO ACCOUNT FOR STRUCTURAL FRAMING DEFLECTIONS.

8.) PROVIDE A MIN OF 10" FROM THE END OF ANY CFS MEMBER TO THE NEAR EDGE OF A WEB PUNCHOUT.

9.) VERTICAL WALL STUDS INTERRUPTED BY WALL OPENINGS SHALL BE DISTRIBUTED EQUALLY 1/2 TO EACH SIDE OF OPENING. WELD STUD FLANGES TOGETHER WITH FILLET WELDS @ 6" OC (OR EQUIVALENT FASTENER CONNECTION).

10.) MINIMUM ANCHORAGE OF DENSGLASS AND CEMENT BOARD EXTERIOR SHEATHING PANELS TO CFS FRAMING SHALL BE BUGLE HEAD FINE THREAD, RUST-RESISTANT, SHARP POINT DRYWALL SCREWS 1 1/4" LONG, SPACED @ 6" OC IN THE FIELD FOR ZONE (4), 4" OC IN THE FIELD FOR ZONE (5) AND 4" OC AROUND PERIMETER OF ALL PANELS. CONTRACTOR TO SUBMIT FOR REVIEW TO THE ENGINEER FASTENER ANCHORAGE TO FINAL APPROVED CFS FRAMING ALONG WITH SIGNED AND SEALED SPECIALTY ENGINEERED SUPPORTING CALCULATIONS FOR DESIGN GRAVITY AND WIND LOADS.

11.) INSTALL CONNECTORS IN STRICT ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS.

12.) NOTIFY ENGINEER OF RECORD IMMEDIATELY OF ANY CONFLICTS BETWEEN CONNECTORS INDICATED ON THESE DRAWINGS OR USE THE MORE STRINGENT CONNECTOR.

13.) OTHER MANUFACTURED CONNECTORS MAY BE SUBSTITUTED FOR THE CONNECTORS INDICATED IN THESE DRAWINGS PROVIDED THEY MEET OR EXCEED THE RATED CAPACITIES OF THE SPECIFIED CONNECTOR FOR GRAVITY, UPLIFT, AND LATERAL LOADS. NOTIFY THE ENGINEER OF RECORD AND OBTAIN WRITTEN APPROVAL FOR ALL PROPOSED ANCHOR, STRAPPING, OR MATERIAL SUBSTITUTIONS NOT OTHERWISE INDICATED ON THESE PLANS.

14.) ALL CFS FRAMING AND CONNECTIONS SHALL BE DESIGNED TO SAFELY RESIST ALL WIND, LIVE, DEAD, AND COLLATERAL LOADS SHOWN ON THESE CONTRACT DOCUMENTS AS WELL AS ALL APPLICABLE BUILDING CODE REQUIREMENT BY A SPECIALTY ENGINEER CURRENTLY LICENSED IN THE STATE OF FLORIDA.

EXTERIOR APERTURES INCLUDING, BUT NOT LIMITED TO CURTAINWALLS, STOREFRONTS, WINDOWS, DOORS, HOLLOW METAL FRAMES, ROOF HATCHES AND LOUVERS:

1.) EXTERIOR APERTURES INCLUDING, BUT NOT LIMITED TO CURTAINWALLS, STOREFRONTS, WINDOWS, DOORS, HOLLOW METAL FRAMES, ROOF HATCHES AND LOUVERS SHALL BE TESTED BY AN APPROVED INDEPENDENT TESTING LABORATORY, IN ACCORDANCE WITH ANSI/AAMA/NWWDA 101/IS2 STANDARD AND BEAR AN AAMA OR WDMA LABEL IDENTIFYING THE MANUFACTURER, PERFORMANCE CHARACTERISTICS AND APPROVED PRODUCT TESTING ENTITY.

2.) EXTERIOR APERTURES INCLUDING, BUT NOT LIMITED TO CURTAINWALLS, STOREFRONTS, WINDOWS, DOORS, HOLLOW METAL FRAMES, ROOF HATCHES AND LOUVERS SHALL BE ANCHORED PER PUBLISHED MANUFACTURER'S RECOMMENDATIONS IN ORDER TO SAFELY RESIST THE "MINIMUM COMPONENT AND CLADDING WIND PRESSURES" FOR THE ROOF AND WALL FIELD, CORNERS AND EDGES, AS APPLICABLE, INDICATED ON THESE DRAWINGS. ANCHORAGE SHALL BE SUBSTANTIATED BY SIGNED, SEALED (EMBOSSED), AND DATED CALCULATIONS PERFORMED BY A STRUCTURAL ENGINEER CURRENTLY REGISTERED IN THE STATE OF FLORIDA. CALCULATIONS SHALL BE SUBMITTED TO THE A/E FOR REVIEW PRIOR TO FABRICATION OR ERECTION.

3.) ALL WINDOW BUCKS SHALL EXTEND BEYOND THE INTERIOR LIP OF THE WINDOW. PROVIDE A MINIMUM GAP OF 1/16" AT ALL BUCKSTRIP JOINTS. FILLER PIECES OF BUCKSTRIP MUST BE AT LEAST 24" OR LONGER. CAULK ALL BUCKSTRIP JOINTS.

4.) ALL MULLIONS AND ADJACENT DOOR ASSEMBLIES SHALL BE TESTED OR ENGINEERED TO TRANSFER 1.5 TIMES THE COMPONENT DESIGN WIND LOADS TO THE ROUGH OPENING SUBSTRATE, WITH TESTING RESULTS PROVIDED TO THE A/E FOR REVIEW AND VERIFICATION.

5.) EXTERIOR APERTURES INCLUDING, BUT NOT LIMITED TO WINDOWS, DOORS, HOLLOW METAL FRAMES, ROOF TOP EQUIPMENT, ROOF HATCHES AND LOUVERS SHALL BE SUCCESSFULLY TESTED TO PROVIDE RESISTANCE TO PENETRATION BY FLYING MISSILES PER SSTD 12, ASTM E1886 AND ASTM E 1996 OR MIAMI DADE COUNTY PROTOCOLS PA-201, PA-202, AND PA-203 AS APPLICABLE.

MECHANICAL SYSTEMS SUPPORT:

1.) ALL MECHANICAL EQUIPMENT, APPLIANCES, AND SUPPORTS, INCLUDING, BUT NOT LIMITED TO ROOF CURBS FOR ROOFTOP UNITS, ISOLATION SPRINGS, AS WELL EXHAUST FANS THAT ARE EXPOSED TO WIND SHALL BE DESIGNED BY A CURRENTLY LICENSED SPECIALTY ENGINEER IN THE STATE OF FLORIDA AND INSTALLED TO RESIST THE WIND LOADS ON THE EQUIPMENT AND SUPPORTS AS SHOWN ON SHEET S0.03 AND THE FLORIDA BUILDING CODE.

2.) ALL ROOF TOP EQUIPMENT CURBS, ROOF TOP MECHANICAL EQUIPMENT, EQUIPMENT TIE DOWNS, AND CONNECTIONS OF ALL EQUIPMENT TO BUILDING STRUCTURE FOR WIND LOADING ARE TO BE DESIGNED AND ENGINEERED BY A REGISTERED SPECIALTY ENGINEER RETAINED BY THE MECHANICAL EQUIPMENT SUPPLIER. SIGNED AND SEALED DRAWINGS AND CALCULATIONS ARE TO BE SUBMITTED TO THE ENGINEER OF RECORD FOR REVIEW AND APPROVAL. THE EQUIPMENT MANUFACTURER SHALL PROVIDE THE ATTACHMENT OF THE UNIT TO THE STRUCTURE AND SUBMIT TO THE ENGINEER LOADS, LOCATIONS, AND METHOD OF ATTACHEMENT. THE STRUCTURAL ENGINEER WILL MAKE PROVISIONS IN THE DESIGN OF THE PRIMARY STRUCTURAL FRAME TO ACCOMODATE THE LOADS AND ATTACHEMENTS SUBMITTED BY THE MANUFACTURER.

DEWATERING:

1.) EXPECT TO PERFORM DEWATERING FOR FOUNDATIONS. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PREVENT THE FLOTATION OF STRUCTURES UNTIL ALL BACKFILL IS PROPERLY COMPACTED IN PLACE AND CONSTRUCTION IS COMPLETE.

SUBMITTALS:

1.) SHOP DRAWINGS AND CALCULATIONS FOR ALL STOREFRONT SYSTEMS, CANOPIES, AND SPECIALTY ENGINEERED BUILDING ELEMENTS MUST BE SIGNED AND SEALED BY THE CURRENTLY REGISTERED, FLORIDA SPECIALTY ENGINEER RESPONSIBLE FOR THE DESIGN AT TIME OF SUBMISSION.

2.) ALL SHOP DRAWINGS MUST BE REVIEWED AND STAMPED BY THE GENERAL CONTRACTOR PRIOR TO SUBMITTAL.

3.) THE GENERAL CONTRACTOR SHALL SUBMIT FOR ENGINEER REVIEW SHOP DRAWINGS FOR, BUT NOT LIMITED TO (SEE PROJECT SPECIFICATIONS), THE FOLLOWING ITEMS:

- CONCRETE MIX DESIGNS
- REINFORCING STEEL
- STRUCTURAL STEEL SHOP DRAWINGS AND CONNECTION CALCULATIONS (*)
- COLD FORM STEEL SHOP DRAWINGS AND CALCULATIONS (*)
- JOIST SHOP DRAWINGS AND CALCULATIONS (*)
- ANCHOR BOLT PLAN
- METAL DECK
- EXPANSION & EPOXY ANCHORS
- GUARDRAILS, HANDRAILS, AND POSTS (*)
- EXTERIOR CURTAIN WALLS (FRAMING, GLASS, GLAZING, AND CONNECTIONS) (*)
- LADDERS (*)
- MECHANICAL SUPPORTS AND TIE DOWNS. INCLUDING BUT NOT LIMITED TO CURBS & ISOLATION SPRINGS (*)
- , MASONRY WALL REINFORCING

ITEMS MARKED (*) SHALL HAVE SHOP DRAWINGS SIGNED AND SEALED BY A LICENSED PROFESSIONAL ENGINEER REGISTERED IN THE STATE OF FLORIDA.

DESIGN CALCULATIONS: THE GENERAL CONTRACTOR SHALL SUBMIT TO THE EOR FOR REVIEW TWO SETS OF DESIGN CALCULATIONS SIGNED AND SEALED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF FLORIDA, FOR THE FOLLOWING ITEMS:

- STRUCTURAL STEEL FRAMING CONNECTIONS
- COLD FORM STEEL FRAMING AND CONNECTIONS
- STEEL JOIST FRAMING
- LADDERS AND CONNECTIONS TO STRUCTURE
- GUARDRAILS, HANDRAILS, AND POSTS
- EXTERIOR WINDOW/CURTAIN WALL SYSTEMS
- MECHANICAL SUPPORTS AND TIE DOWNS

FLORIDA PRODUCT APPROVAL:

1.) IN ACCORDANCE WITH THE FLORIDA PRODUCT APPROVAL SYSTEM, MANUFACTURERS OF CURTAINWALLS, STOREFRONTS, WINDOWS, SKYLIGHTS, ROOF HATCHES, EXTERIOR DOORS, SHUTTERS, ROOFING PANELS, AND ALL STRUCTURAL COMPONENTS THAT AFFECT THE STRUCTURAL INTEGRITY OF BUILDINGS DURING HURRICANES MUST SUBMIT THE FOLLOWING DOCUMENTATIONS TO THE EOR FOR REVIEW AND APPROVAL:

A. EVIDENCE THAT THE PRODUCT HAS BEEN EVALUATED FOR COMPLIANCE WITH STANDARDS ESTABLISHED BY THE FLORIDA BUILDING CODE BY A FLORIDA BUILDING COMMISSION APPROVED ENTITY OR FLORIDA LICENSED P.E.

B. EVIDENCE THAT THE MANUFACTURER HAS CONTRACTED WITH A FLORIDA BUILDING COMMISSION APPROVED QUALITY ASSURANCE ENTITY TO MONITOR MANUFACTURING PRODUCTION AND HAS ACTIVELY COMPLIED OR HAVE THE PRODUCT LISTED AND LABELED BY A COMMISSION APPROVED CERTIFICATION PROGRAM.

C. INSTALLATION INSTRUCTIONS CONSISTENT WITH THE EVALUATION OF COMPLIANCE.

POST-INSTALLED ANCHORS FOR CONCRETE AND MASONRY

1.) POST INSTALLED ANCHORS SHALL ONLY BE USED WHERE SPECIFIED ON THE CONSTRUCTION DOCUMENTS.

2.) THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE ENGINEER OF RECORD PRIOR TO INSTALLING POST-INSTALLED ANCHORS IN PLACE OF MISSING OR MISPLACED CAST-IN-PLACE ANCHORS.

3.) CARE SHALL BE TAKEN IN PLACING POST-INSTALLED ANCHORS TO AVOID CONFLICTS WITH EXISTING REBAR.

4.) HOLES SHALL BE DRILLED AND CLEANED IN STRICT ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.

5.) CONTACT MANUFACTURER'S REPRESENTATIVE FOR THE INITIAL TRAINING AND INSTALLATION OF ANCHORS AND FOR PRODUCT RELATED QUESTIONS AND AVAILABILITY. (NOTE: ACI 318-14 WILL REQUIRE SPECIAL CERTIFICATION OF INSTALLERS FOR ADHESIVE ANCHOR APPLICATIONS FOR CERTAIN ADHESIVE ANCHOR APPLICATIONS. PER SECTION 17.8.2.2, INSTALLATION OF ADHESIVE ANCHORS HORIZONTALLY OR UPWARD INCLINED TO SUPPORT SUSTAINED TENSION LOADS SHALL BE PERFORMED BY PERSONNEL CERTIFIED BY AN APPLICABLE CERTIFICATION PROGRAM. CERTIFICATION SHALL INCLUDE WRITTEN AND PERFORMANCE TESTS IN ACCORDANCE WITH THE ACI/CRSI ADHESIVE ANCHOR INSTALLER CERTIFICATION PROGRAM, OR EQUIVALENT. THIS IS NOT SIMPLY A MANUFACTURER'S TRAINING. SOME ENGINEERS ARE REQUIRING THIS CERTIFICATION FOR ALL ADHESIVE ANCHOR INSTALLATION; NOT JUST HORIZONTAL AND OVERHEAD.) PROOF OF CURRENT CERTIFICATION SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO COMMENCEMENT OF INSTALLATION.

6.) PROVIDE SPECIAL INSPECTION FOR ALL MECHANICAL AND ADHESIVE ANCHORS PER THE APPLICABLE BUILDING CODE AND PER THE CURRENT EVALUATION REPORT FOR THE ANCHOR.

8.) CONCRETE ANCHORS:

MECHANICAL ANCHORS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ACI 355.2 AND ICC-ES AC193 FOR CRACKED AND UNCRACKED CONCRETE RECOGNITION.
PRE-APPROVED MECHANICAL ANCHORS INCLUDE:
HILTI FASTENERS:
KWIK HUS EZ ..... (ICC-ES ESR-3027)
ADHESIVE ANCHORS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ACI 355.4 AND ICC-ES AC308 FOR CRACKED AND UNCRACKED CONCRETE RECOGNITION.
PRE-APPROVED ADHESIVE ANCHORS INCLUDE:
HILTI FASTENERS:
HILTI HIT-HY 200 ..... (ISS-ES ESR-3187)

POWER-ACTUATED FASTENERS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ICC-ES AC70. PRE-APPROVED POWDER ACTUATED FASTENERS INCLUDE:
SIMPSON STRONG-TIE FASTENERS:
POWDER-ACTUATED FASTENERS ..... (ICC-ES ESR-2811)
GAS-ACTUATED FASTENERS ..... (ICC-ES ESR-2138)
POWERS FASTENERS:
TRAK-IT C5 FASTENERS ..... (ICC-ES ESR-3275)

(NOTE: GAS-ACTUATED FASTENERS ARE AN ALTERNATIVE TO POWDER-ACTUATED FASTENERS AND ARE COMMONLY USED ON JOB SITES. THERE IS NO OSHA TRAINING REQUIRED TO INSTALL GAS-ACTUATED FASTENERS AND HENCE THEY ARE CONSIDERED A SAFE INSTALLATION METHOD. GAS-ACTUATED FASTENERS ARE TESTED TO THE SAME STANDARDS AS POWDER-ACTUATED FASTENERS.)

9.) MASONRY ANCHORS (SOLID GROUTED CONCRETE MASONRY)
MECHANICAL ANCHORS SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ICC-ES AC01 OR AC106. PRE-APPROVED MECHANICAL ANCHORS INCLUDE:
SIMPSON STRONG-TIE STRONG-BOLT 2 ..... (IAPMO-UES-ER-240)
SIMPSON STRONG-TIE TITEN HD ..... (ICC-ES ESR-1056)
POWERS "POWER-STUD+ SD1" ..... (ICC-ES ESR-2966)
HILTI KWIK BOLT 3 ..... (ICC-ES ESR-2302)

DRAWING INTERPRETATION:

1.) PARTIAL PLANS, ELEVATIONS, SECTIONS, DETAILS, OR SCHEDULES LABELED WITH "TYPICAL" AT THE BEGINNING OF THEIR TITLE SHALL APPLY TO ALL SITUATIONS OCCURING ON THE PROJECT THAT ARE THE SAME OR SIMILIAR TO THOSE SPECIFICALLY SHOWN. THE APPLICABLITY OF THE CONTENT OF THESE VIEWS TO LOCATIONS ON THE PLAN CAN BE DETERMINED FROM THE TITLE OF THEIR VIEWS. SUCH VIEWS SHALL APPLY WHETHER OR NOT THEY ARE KEYED IN AT EACH LOCATION. DECISIONS REGARDING APPLICABILITY OF THESE "TYPICAL" VIEWS SHALL BE DETERMINED BY THE STRUCTURAL ENGINEER.

EXISTING CONDITIONS:

1.) CONTRACTOR SHALL VERIFY ALL FIELD CONDITIONS AND DIMENSIONS RELATIVE TO SAME. WHERE THERE ARE CONFLICTS BETWEEN ACTUAL FIELD CONDITIONS AND/OR DATA PRESENTED ON THESE DRAWINGS, SUCH CONDITIONS SHALL BE CALLED TO THE ATTENTION OF THE ARCHITECT & ENGINEER IMMEDIATELY, AND NECESSARY ADJUSTMENTS MADE PER THEIR INSTRUCTIONS.

2.) EXISTING CONSTRUCTION SHOWN ON THE DRAWINGS WAS OBTAINED FROM EXISTING CONSTRUCTION DOCUMENTS AND LIMITED SITE OBSERVATION. THE CONTRACTOR SHALL FIELD VERIFY ALL PERTINENT INFORMATION.

3.) DEMOLITION, CUTTING, DRILLING, ETC. OF EXISTING WORK SHALL BE PERFORMED WITH GREAT CARE SO AS NOT TO JEPARDIZE THE STRUCTURAL INTEGRITY OF THE EXISTING BUILDING. IF ANY ARCHITECTURAL, STRUCTURAL, OR MEP MEMBERS NOT DESIGNATED FOR REMOVAL INTERFERE WITH THE NEW WORK, NOTIFY AECOM IMMEDIATELY AND APPROVAL OBTAINED PRIOR TO REMOVAL OF THOSE MEMBERS.

4.) THE CONTRACTOR SHALL REPAIR ALL DAMAGE CAUSED DURING CONSTRUCTION WITH SIMILAR MATERIALS AND WORKMANSHIP TO RESTORE CONDITIONS TO LEVELS ACCEPTABLE TO THE ARCHITECT.

ABBREVIATIONS

@	AT	DIA	DIAMETER	HORIZ	HORIZONTAL	PJF	PRE-MOULDED JOINT FILLER
ACI	AMERICAN CONCRETE INSTITUTE	DWG	DRAWING	H.S., HSA	HEADED STUDS	PL	PLATE
ADA	AMERICANS WITH DISABILITIES ACT	E.F.	EACH FACE	L	ANGLE	PSF	POUNDS PER SQUARE FOOT
AESS	ARCHITECTURAL EXPOSED STRUCTURAL STEEL	EL.	ELEVATION	LLH	LONG LEG HORIZONTAL	PSI	POUNDS PER SQUARE INCH
A.F.F.	ABOVE FINISHED FLOOR	EOS	EDGE OF SLAB	LLV	LONG LEG VERTICAL	REINF	REINFORCING
ARCH / ARCH'L	ARCHITECTURAL	EQ	EQUAL	LT	LEFT	SECT	SECTION
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIAL	E.W.	EACH WAY	MFR	MANUFACTURER	SIM	SIMILAR
ANCH	ANCHORAGE	EXIST.	EXISTING	MAX.	MAXIMUM	SL	SLOPE
BOTT.	BOTTOM	FDN	FOUNDATION	MIN.	MINIMUM	SLV	SHORT LEG VERTICAL
BM	BEAM	FIN.	FINISHED	NO.	NUMBER	SPEC	SPECIFICATION
C L	CENTER LINE	F.S.	FAR SIDE	N.S.	NEAR SIDE	STD.	STANDARD
CLR	CLEAR	FT	FOOT	NTS	NOT TO SCALE	T&B	TOP AND BOTTOM
COL	COLUMN	FTG	FOOTING	O.H.	OVERHANG	TOC	TOP OF CONCRETE
CONC.	CONCRETE	F.V.	FIELD VERIFY	O.C.	ON CENTER	TOS	TOP OF STEEL
CONT.	CONTINUOUS	GALV	GALVANIZED	OPP	OPPOSITE	TYP	TYPICAL
				OPNG	OPENING	U.N.O. / UON / UNO	UNLESS OTHERWISE NOTED
						V.B.	VAPOR BARRIER
						VERT	VERTICAL
						V.I.F.	VERIFY IN FIELD
						W	WIDE FLANGE
						W.P.	WORK POINT

MATERIAL INDICATION


EARTH


GROUT OR SAND


C.I.P. CONCRETE


MASONRY

GRAPHIC SYMBOLS



FRAMING LEGEND



Building Inspection Division

AECOM
BATSON-COOK CONSTRUCTION

PROJECT
PUBLIX HEADQUARTERS BUILDING ADDITION AND PARKING LOT EXPANSION
3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811

CLIENT
Publix
3300 PUBLIX CORPORATE PARKWAY
LAKELAND, FL 33811
www.publix.com

CONSULTANT
AECOM
AECOM TECHNICAL SERVICES, INC.
800 Douglas Entrance
North Tower, 2nd Floor
Coral Gables, FL 33134
305.444.4691 tel 305.447.3580 fax
www.aecom.com

ARCHITECTURE
LICENSE NO. AA26000687

ENGINEERING
CA LIC. NO. 8115

http://www.aecom.com

REGISTRATION
VINCENT RAJ VACCARELLO-WADEHRA, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 81224

THIS ITEM HAS BEEN DIGITALLY SIGNED AND SEALED BY VINCENT RAJ VACCARELLO-WADEHRA, PROFESSIONAL ENGINEER, STATE OF FLORIDA, LICENSE NO. 81224 ON THE DATE INDICATED HERE. PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.

Vincent R Vaccarello -Wadehra
Digitally signed by Vincent R Vaccarello-Wadehra
Date: 2019.08.22 17:57:07 -04'00'

ISSUE/REVISION

I/R	DATE	DESCRIPTION
0	AUGUST 23, 2019	CONSTRUCTION DOUMENTS
	AUGUST 16, 2019	90% CONSTRUCTION DOCUMENTS
	JUNE 27, 2019	STEEL DESIGN PACKAGE
	JUNE 7, 2019	35% DESIGN COMPLETION

PROJECT NUMBER
60601397

SHEET TITLE
GENERAL NOTES (2 OF 2), ANNOTATIONS, AND ABBREVIATIONS

SHEET NUMBER
S0-1-02

This drawing has been prepared for the use of AECOM's client and may not be used, reproduced or relied upon by third parties, except as agreed by AECOM and its client, as required by law or for use by governmental reviewing agencies. AECOM accepts no responsibility, and denies any liability whatsoever to any party that modifies this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.
NOTICE: THE OFFICIAL RECORD OF THIS SHEET IS THE ELECTRONIC FILE SIGNED AND SEALED UNDER RULE 61G15-23.004, F.A.C.
©2016 AECOM Corporation

Project Management Initials: Designer: Designer Checker: Checker Approved: Approver/ARCH E1 30"x42"
Last Plotted: 8/22/2019 5:35:39 PM
Filename: BIM 360://60601397-Publix HQ/60601397_Publix HQ_STRUCT_R2019.rvt
Printed on ___% Post-Consumer Recycled Content Paper